

**2025 Biennial Groundwater
Monitoring Report - Erb Street Well Field
(W6B, W6C, W7, W8)**

The Region of Waterloo



BURNSIDE

2025 Biennial Groundwater Monitoring Report - Erb Street Well Field (W6B, W6C, W7, W8)

The Region of Waterloo

**R.J. Burnside & Associates Limited
292 Speedvale Avenue West Unit 20
Guelph ON N1H 1C4 CANADA**

**June 2026
HA0464020.2024**

Distribution List

No. of Hard Copies	PDF	Email	Organization Name
0	0	-	The Ministry of Environment, Conservation and Parks (MECP)
0	Yes	Yes	The Region of Waterloo

Record of Revisions

Revision	Date	Description
0	April 2026	Submission to the Region of Waterloo
1	June 2026	Submission to MECP

R.J. Burnside & Associates Limited

Report Prepared By:

Stephanie Charity, P.Geo.
Hydrogeologist
SC:js



Report Reviewed By:

Dave Hopkins, P.Geo.
Senior Hydrogeologist
DH:js



Table of Contents

1.0	Introduction	1
1.1	Scope of Work	1
2.0	Site Setting	2
2.1	Well Field Description	2
2.1.1	Pumping Wells	2
2.1.2	Monitoring Wells.....	3
2.2	Regional Geology and Hydrostratigraphy	4
2.2.1	Surficial Geology and Conceptual Hydrostratigraphy	5
2.2.2	Bedrock Geology.....	7
2.3	Local Geology.....	7
3.0	2024 / 2025 Results	7
3.1	Precipitation.....	8
3.2	Monitoring Results	9
4.0	Impact Assessment	11
4.1	Well Interference	11
4.2	Aquifer Response to Pumping and Precipitation	13
5.0	Conclusions	14
6.0	References	15

Tables

Table 1: Production Well Construction Details	2
Table 2: Water Takings 2024 / 2025	3
Table 3: Monitoring Well Construction Details	4
Table 4: Summary of Precipitation Data	8
Table 5: PTTWs in Vicinity of Erb Street Well Field (W6B, W6C, W7, W8)	12

Figures

Figure 1: Well Field Location Map
Figure 2: Wilmot Well Fields and Monitoring Network
Figure 3: Well Location Map
Figure 4: Surficial Geology
Figure 5: Location of Waterloo Moraine
Figure 6: Erb Street Well Field Cross Section A – A'
Figure 7: Erb Street Well Field Cross Section B – B'
Figure 8: Erb Street Well Field Cross Section C – C'

Appendices

Appendix A Permit To Take Water
Appendix B Well Records
Appendix C Monitoring Data (Pumped Volumes and Hydrographs)

2025 Biennial Groundwater Monitoring Report - Erb Street Well Field (W6B, W6C, W7, W8)
June 2026

Appendix D Precipitation Data

Appendix E Monitoring Program Overview

1.0 Introduction

The Regional Municipality of Waterloo (the Region) is unique in Ontario in that it is the largest urban municipality to rely almost exclusively on groundwater supplies for its drinking-water (Region of Waterloo, 2015). Figure 1 shows the location of municipal well fields within the Region.

The Permit to Take Water (PTTW 1541-AWGPZR) for the Erb Street Well Field (W6B, W6C, W7, W8), requires submission of a well field specific biennial report to the Ministry of Environment, Conservation and Parks (MECP) which documents production well pumping volumes and water levels in specific monitoring wells during 2024 and 2025. This report has been prepared to meet the reporting condition (4.3) of the PTTW for 2024 and 2025. A copy of the PTTW is included in Appendix A.

The location of the Erb Street Well Field is shown on Figure 1 and the production wells in Wilmot are shown in Figure 2 with the monitoring network for W6B, W6C, W7 and W8 shown in Figure 3. Well records for the production and monitoring wells are found in Appendix B.

1.1 Scope of Work

The Region records water levels on a regular basis within a network of monitoring wells to satisfy the requirements of their PTTW and to confirm that water taking is sustainable in the long term. The monitoring wells are concentrated near the production wells and in known aquifer recharge areas. The data from these wells and regular measurements of pumping volume obtained from the production wells are used to evaluate the impact of Region pumping on aquifers and potential impacts to private wells, other water takers and the natural environment.

The Region has developed a monitoring program for Erb Street Well Field in accordance with PTTW 1541-AWGPZR which consists of the following activities:

- Measuring the daily volume pumped from production wells W6B, W6C, W7 and W8 (Condition 4.1 of the PTTW);
- Measuring the water levels in monitoring wells WT-EB-OW322-02-AB, WT-EB-OW332-02-A, WT-EB-OW1-08-AB, WT-EB-OW2-08-AB, WT-EB-OW3-08-AB, WT-EB-OW6-09-AB, and WT-EB-OW1-15-AB (Condition 4.2 of the PTTW);
- Review of precipitation data from the nearest GRCA / Environment Canada weather station; and
- Completion of a biennial report (every 2 years) that presents data in compliance with condition 4.3 of the PTTW.

The Monitoring data (pumped volumes and hydrographs) are found in Appendix C with precipitation data in Appendix D. The monitoring program procedures and methodology are included in Appendix E.

2.0 Site Setting

2.1 Well Field Description

The Erb Street Well Field is located to the west of Waterloo, on the eastern boundary of the Township of Wilmot (Figure 2). Wells W6B and W6C are located north of Erb's Road between Wilmot Line and Notre Dame Drive. Wells W7 and W8 are located about 900 m south of Erb's Road (Figure 3). The closest active municipal well field is Strange Street, located about 4 km to the east (Figure 2). The Waterloo Waste Management Site is about 1.2 km east of the W7 and W8 wells. The closest surface water feature to the W6B, W6C, W7 and W8 site is the Knarr-Hoerle Drain located just north of Wells W7 and W8 (Figure 3).

2.1.1 Pumping Wells

The Erb Street Well Field consists of Wells W6B, W6C, W7 and W8. W6C was commissioned in November 2023. It was drilled adjacent to W6A / W6B in 2016 as a replacement for W6A, which was taken out of service in October 2012 and is no longer on the PTTW.

A summary of the production well construction details is provided in Table 1 below. Well records for the production wells are found in Appendix B.

Table 1: Production Well Construction Details

Well Name	Year Built	Casing / Screen Diameter (mm)	Screened Interval (mbgs)	Aquifer
W6B	1985	300	48.2 – 54.6	AFB2
W6C	2016	254	48.8 – 53.7	AFB2
W7	1966	400	32.9 – 42.1	AFB2
W8	1969	400	32.9 – 36.6	AFB2

The water taking volumes for the Erb Street Well Field is regulated by Condition 3.2 of the PTTW and are summarized in Table 2 below.

Table 2: Water Takings 2024 / 2025

Well	PTTW	2024			2025		
	Permitted Max. Daily Water Taking (m ³)	Avg. Daily Water Taking (m ³)	Max Taken per Day (m ³)	Total Volume Pumped (m ³)	Avg. Daily Water Taking (m ³)	Max Taken per Day (m ³)	Total Volume Pumped (m ³)
W6B	4,582	1,605	1,771	585,874	1,394	1,530	508,799
W6C	5,561	2,552	2,657	931,606	1,702	2,593	621,262
W7	9,166	6,660	7,629	2,409,089	6,853	7,778	2,501,309
W8	10,475	1,350	2,271	492,894	1,371	1,629	500,312
Total	29,788	12,108	13,275	4,419,463	11,320	12,298	4,131,682

Condition 3.3 of the PTTW specifies that the combined daily water taking from W6C, W6B, W7 and W8 must not exceed an annual daily average of 17,272.800 m³/day. As shown in Table 2, this requirement was met in both 2024 and 2025.

The Region of Waterloo's SCADA system records total daily water taking volumes including the dates and times of water takings, the rates of pumping, and calculations of the total amounts of water pumped per day for each supply well, which complies with condition 4.1 of the PTTW.

The pumping volumes are based on the total daily volumes as recorded by the Region's SCADA system and are presented in Appendix C as total monthly volumes. Pumping volumes from the well field ranged from 324,668 m³/month to 394,441 m³/month in 2024, and from 297,321 m³/month to 378,069 m³/month in 2025. In total, 4,419,463 m³ was produced at this well field in 2024 and 4,131,682 m³ was produced in 2025. These volumes are higher than volumes for the previous five years, and below the permitted volume of 6,304,572 m³ per year (Table C-1). The increase in pumping recorded in 2024 and 2025 is the result of increased pumping of W6B and W6C.

2.1.2 Monitoring Wells

Water level monitoring is completed at observation wells WT-EB-OW322-02-AB, WT-EB-OW332-02-A, WT-EB-OW1-08-AB, WT-EB-OW2-08-AB, WT-EB-OW3-08-AB, WT-EB-OW6-09-AB, and WT-EB-OW1-15-AB (Figure 3).

Construction and monitoring well location details for the observation wells are described in Table 3 below. Well records for the monitoring wells are provided in Appendix B.

Table 3: Monitoring Well Construction Details

Monitoring Well ID	Year Built	Screened Depth (mbgs)	Screened Formation	Distance to W6B/W6C (m)	Distance to W7/W8 (m)
WT-EB-OW322-02-A	2002	65.2 – 68.3	AFB2	1,000	700
WT-EB-OW322-02-B	2002	53.0 - 56.0	AFB2	1,000	700
WT-EB-OW332-02-A	2002	49.1 – 52.1	AFB2	700	800
WT-EB-OW1-08-A	2008	56.1 – 59.1	AFB2	700	400
WT-EB-OW1-08-B	2008	44.2 – 47.3	AFB2	700	400
WT-EB-OW2-08-A	2008	58.8 – 61.9	AFB2	1,100	240
WT-EB-OW2-08-B	2008	44.8 – 47.9	AFB2	1,100	240
WT-EB-OW3-08-A	2008	53.7 – 56.7	AFB2	130	700
WT-EB-OW3-08-B	2008	43.3 – 46.3	AFB2	130	700
WT-EB-OW6-09-A	2009	46.6 – 49.7	AFB2	720	500
WT-EB-OW6-09-B,	2009	35.1 – 41.2	AFB2	720	500
WT-EB-OW1-15-A	2015	35.1 – 42.2	AFB2	900	near
WT-EB-OW1-15-B	2015	24.4 – 25.9	AFB2	900	near

2.2 Regional Geology and Hydrostratigraphy

The following sections provide a brief overview of the regional geology and hydrogeology of the Erb Street Well Field. The surficial geology based on regional OGS mapping is provided in Figure 4. The Erb Street Well Field is located in the core of the Waterloo Moraine (Figure 5). Representative cross-sections showing the stratigraphy in the vicinity of the Erb Street Well Field (W6B, W6C, W7, W8) are included as Figures 6, 7 and 8. The cross-section locations are provided on Figure 3.

The cross-sections are provided as a visual aid and do not necessarily contain all wells in the monitoring program for the Erb Street Well Field. The recently completed Tier Three Assessment Update Project (Aqua Insight et al, 2023) has revised the previous (Matrix 2015) stratigraphic interpretation of the lithology around the Erb Street Well Field. The lithological layers were updated in accordance with documentation provided in the Numerical Model Surface Transfer memorandum (Aqua Insight Inc, 2026).

Refinements (Aqua Insight et al, 2023) along the cross-sections (Figures 6, 7 & 8) include the following:

- ATA1 is shown at surface overlying ATB1 resulting in a thinner ATB1, and
- ATB2 is thicker and AFB2 is thinner in the area of the production wells

2.2.1 Surficial Geology and Conceptual Hydrostratigraphy

The surficial geology of the Study Area has been mapped and described by the Ontario Geological Survey (2003) and updated in Bajc and Shirota (2007). The surficial geology of the Erb Street Well Field is characterized by silty to clayey till sediments (Figure 4). Fine textured glaciolacustrine sediments are mapped near W7 and W8 however were not encountered in the well records. The deposition of the Waterloo Moraine in this area resulted in fine to coarse-grained sand and gravel deposits at surface south and west of the well field. The thickness of the overburden deposits generally ranges from 80 to 100 m in this area.

The Quaternary units typically present beneath the Waterloo Moraine are briefly described below, in order from youngest to oldest.

Aquitard ATA1 – Whittlesey Clay

This silt and clay unit is present at surface across the section and corresponds to glaciolacustrine Whittlesey clay (Bajc and Shirota, 2007). This unit forms a laterally extensive, low-permeability aquitard that restricts infiltration and provides partial confinement to the underlying aquifer.

Aquitard ATB1 – Tavistock Till

The Tavistock Till is a dark brown clayey silty till that is predominantly found along the western flanks of the Waterloo Moraine. In other parts of the Region, Bajc and Shirota (2007) have also used unit ATB1 to represent Port Stanley, Mornington and Upper Maryhill Tills. ATB1 ranges from 13 m to 20 m thick in the area of Erb Street Well Field. This unit is considered an aquitard and, where present, acts to restrict recharge to the lower aquifers.

Aquifer AFB1 / AFB2 – Upper Waterloo Moraine Stratified Sediments and Equivalent

Aquifer AFB1 / AFB2 represents the main water supply aquifer in the core areas of the Waterloo Moraine, including the Erb Street Well Field production wells. These units are generally comprised of layered silt and fine sand to coarse sand and gravel. Throughout the core areas of the Moraine (Figure 5), the unit typically exceeds 45 m in thickness. In some areas, the Upper Waterloo Moraine is interpreted to be bisected by the middle Maryhill Till (ATB2), effectively separating the aquifer into two units, AFB1 and AFB2.

This aquifer is the most prolific aquifer in the Waterloo Region due to its high hydraulic conductivity and transmissivity, lateral extent, and high recharge rate. This unit is approximately 15 m to 30 m thick in the Erb Street Well Field area.

Aquitard ATB3 – Lower Maryhill Till

The Lower Maryhill Till is described as a clayey silt to silty clay till. This unit represents one of the primary regional aquitards due to its strong influence on the groundwater flow system within the Waterloo Moraine. This unit is extensive within the core area of the Waterloo Moraine, and along the eastern flank tends to be thin, discontinuous, or re-worked and re-deposited as glaciofluvial sediments. This unit is approximately 20 m thick in the Erb Street Well Field area.

Aquifer AFB3 – Lower Waterloo Moraine Stratified Sediments

The Lower Waterloo Moraine Stratified Sediments is present below the Lower Maryhill Till, mainly along the eastern flank of the Moraine. This unit consists of stratified gravels, sands, or silts and is of very limited extent. AFB3 is not present in the Erb Street Well Field Area.

Aquitard ATC1 / ATC2 – Catfish Creek Till

The Catfish Creek Till was deposited by a major glacial advance from the north to northeast that covered all of southern Ontario. It is a dense, stony, sandy silt to silty sand till with little clay content. The hydrogeologic properties of the Catfish Creek Till are variable, ranging from a good aquitard to a poor aquifer, depending on local lithology, degree of compaction, and the presence of overlying aquitard units. The Catfish Creek Till is typically thickest in the core area of the Waterloo Moraine, and thin or absent along the eastern flank. It is approximately 20 m thick in the Erb Street Well Field area.

Aquifer AFD1 – Pre-Catfish Creek Sand and Gravel

Pre-Catfish Creek Till aquifer corresponds to sands and gravel re-worked from Catfish Creek and Pre-Catfish Creek Till and represents the main supply aquifer in several production wells in the Cities of Kitchener and Waterloo. This unit is spatially discontinuous throughout much of the core areas of the Waterloo Moraine and pinches out near the Erb Street Well Field.

Aquitard ATE1 – Canning Drift

The Canning Drift is comprised of till and associated fine-textured lake deposits. It is typically found at depths of greater than 70 metres below ground surface (mbgs) in the Waterloo Moraine area and is identified to be discontinuous and limited in lateral extent

and thickness. Where it is absent, a hydraulic connection is present between the deep overburden aquifers and the underlying bedrock.

Aquifer AFF1 – Pre-Canning Till

The Pre-Canning aquifer is characterized by coarse-grained sand and gravel sediments and is typically found within bedrock depressions. This unit is discontinuous throughout the Region, and where present is hydraulically connected with the upper weathered portion of the bedrock aquifer.

2.2.2 Bedrock Geology

The underlying bedrock at the Erb Street Well Field consists of the Salina, Guelph and Amabel Formation (OGS, 1991). The Salina Formation consists of interbedded grey and brown dolostone, green to red shale units, and gypsum. Groundwater extracted from this unit tends to be of poor quality due to high concentrations of calcium and sulphates. In the Erb Street Well Field area, bedrock is found at depths of approximately 80 mbgs.

2.3 Local Geology

The following description of local geology is based on sediments reported in the production well logs and monitoring well logs in the area of the Erb Street Well Field. Borehole logs of the Erb Street Well Field are included in Appendix B.

Tavistock Till (ATB1) – This unit is encountered at surface in the area of the Erb Street Well Field and is described in well logs as clay and clay and gravel. ATB1 is logged as extending to 13 m at W8 and 14.9 m at W7. At W6C silty clay and clayey silt extends to 32 m.

Upper Waterloo Moraine (AFB1 / AFB2) – This unit was identified in all of the Erb Street production wells. The unit was encountered at depths of between 32.9 mbgs (W7) and 48.5 mbgs (W6B). It was generally described as sand and gravel in the driller's logs and ranged in thickness from 10 m to 30 m. The Erb Street Well Field Production wells are all completed in this aquifer.

Lower Maryhill Till (ATB3) – This unit described as clay with trace sand was identified at W6C at a depth of 59 mbgs and in the log for WT-EBS-OW2-08-A at a depth of 63 m.

3.0 2024 / 2025 Results

The following sections summarize groundwater levels at monitoring wells in relation to precipitation and water taking from the aquifer (in accordance with condition 4.3 of the PTTW).

3.1 Precipitation

Longer term precipitation trends can have an impact on water levels in the supply aquifer. To assess the potential influence, monthly precipitation is plotted for comparison to water levels and pumping and presented in Appendix C.

Since variations in precipitation totals can occur throughout the Region due to localized events, monthly precipitation data from the GRCA, University of Waterloo (U of W) or Environment Canada station located closest to the production wells are used. The closest GRCA weather station relative to the Erb Street well field is Laurel Creek station located 4.3 km from the well field. The closest Environment Canada station is the Roseville station (13 km southeast of the well field). The locations of the meteorological stations are shown on Figure 1. Annual precipitation data from the past 10 years for all stations are compared with long term averages in Table D.1, Appendix D. Monthly precipitation data for the past 10 years at the Laurel Dam station are shown on Figure D.1, Appendix D. At the Laurel Dam station, the long-term average was calculated from when measurements started until the end of 2025. The Roseville station has “Climate Normals” calculated by Environment Canada for 1981 to 2010.

Annual 2024 / 2025 precipitation data for the closest weather station and closest Environment Canada meteorological station to the Erb Street Well field are presented in Table 4 below. In 2024 Roseville was missing 5 days of data and 20 days in 2025. As a result, the precipitation totals may be under reported at this location.

Table 4: Summary of Precipitation Data

Station	2024 Precipitation (mm)	2024 Deviation (mm)	Long- Term Average (mm)	2025 Precipitation (mm)	2025 Deviation (mm)
Laurel Dam ^(C)	907	-31	938 ^A	894	-44
Roseville Station ^(A)	856	-63	919 ^B	786	-133
Sources: Environment Canada (1), GRCA (3), ^A 1991 to 2020 Normal ^C Average annual precipitation since monitoring began to the end of 2025					

Water levels typically follow a seasonal trend with highest levels occurring in the spring following the snowmelt and lowest levels occurring in July / August. Widespread synoptic rainfall events can also result in Region wide water level responses. Summer thunderstorms tend to be short lived and occur over a smaller area resulting in short term, localized water level rises.

The 2024 total precipitation at the Laurel Dam station was 907 mm, which is 31 mm below the long-term average, indicating 2024 was a drier-than-average year at

the well field. A similar below long-term average trend is noted at the Roseville station. The March 1 GRCA snow survey indicated a snowpack across the Region that was low compared to normal.

In 2025, the total precipitation at the Laurel Dam station was 894 mm, which is 44 mm below the long-term average. The total precipitation at the Roseville station was 133 mm below the long-term average, indicating 2025 was a drier-than-average year. However, Roseville was missing 25 days of data in 2024 / 2025 and as a result, precipitation totals may be under reported. The snow survey conducted by the GRCA on March 15, 2025, showed that the stations in the Region had a high to very high measured snow water equivalent.

3.2 Monitoring Results

Hydrographs showing the results of water level monitoring at each monitoring well over the past 10 years are provided in Appendix C. The method used to collect the water levels (manual or electronic) is indicated on the graphs in Appendix C.

WT-EB-OW1-08-AB

WT-EB-OW1-08-AB is located about 400 m west of W7 / W8. Both screens are installed in the AFB2 aquifer unit. Water levels have been measured manually on a monthly basis since September 2010. A datalogger was installed in OW1-08-A in 2017.

Water levels in the A and B screens are generally similar and have ranged between 349.2 and 351.4 masl during the past 10 years. Historically, short term water level rises (November 2019, December 2020 and August 2024) can be observed in response to reduced pumping of W7. In December 2023, a decreasing water level trend is observed, coinciding with pumping of W6B and W6C and increased overall water taking at the Erb Street Well Field. Water levels decline from 350.3 masl in December 2023 to 349.2 masl in December 2025.

WT-EB-OW322-02-AB

WT-EB-OW322-02-AB is located about 700 m northeast of W7 / W8. Both screens are installed in the AFB2 aquifer unit. Water level data is collected using an electronic data logger at the A screen, and monthly manual measurements at the B screen.

Water level trends are similar in each screen. Daily fluctuations in the A screen of about 0.4 m suggest impacts from the pumping cycles of production wells. In both screens, water levels showed an increasing trend from 2008 to 2019 due to reduced pumping at W8 during which time the levels increased by approximately 2 m. A decreasing trend in water levels is apparent from January 2021 until January 2023 after which water levels

were stable. In 2024 / 2025 water levels decline 1.1 m in response to increased pumping at W6B and W6C.

WT-EB-OW332-02-A

WT-EB-OW332-02-A is located about 700 m east of W6B / W6C and is screened in the production aquifer (AFB2). Manual water level monitoring at this location began in October 2004 and an automatic water level meter was installed in July 2017.

Daily water level fluctuations of about 0.4 m are due to pumping cycles of production wells. Over the past ten years, water levels have ranged from 348.7 masl in 2025 to 350.7 masl in 2020. In 2024 / 2025 water levels decline 1.1m in response to increased pumping at W6B and W6C.

WT-EB-OW2-08-AB

WT-EB-OW2-08-AB is located about 240 m south of W7 / W8. Both screens are installed in the AFB2 aquifer unit. Manual water level monitoring at this location began in July 2010, and dataloggers were installed in October 2014. The datalogger in the B screen was removed in May 2017 and water levels are now measured manually.

Water levels in the A and B screens show a similar pattern with variations corresponding to changes in pumping at W7 and W8. An increasing trend from 2012 to 2019 is a result of decreased pumping at W8. Water levels decline from 349.9 masl in January 2020 to 347.6 masl in December 2025. In 2024 / 2025 water levels are about 1.2 m below historical water levels.

WT-EB-OW3-08-AB

WT-EB-OW3-08 is located about 130 m southeast of W6B/W6C. Both screens are installed in the AFB2 aquifer unit. Manual monitoring at this location began in May 2010 with dataloggers installed in each well in October 2014.

Water levels in both screens display similar trends, with the levels in the B screen consistently about 2.5 m higher than levels in the A screen. Both wells show a response to changes in pumping rates at W6B and W6C due to being screened in the production well aquifer and close proximity to the pumping wells. Water levels in 2024 / 2025 are about 3 m lower than historical levels due to increased pumping at W6B and W6C.

WT-EB-OW6-09-AB

WT-EB-OW6-09 is located about 720 m east of W6B / W6C. Both screens are installed in the AFB2 aquifer unit. The collection of monthly manual water levels began at this location in September 2010 and dataloggers were installed in October 2014. The

datalogger in the B screen was removed in June 2017 with manual water levels now collected monthly.

Water levels in the A and B screens are almost identical and between 2016 and 2025 varied between 349.1 masl and 351.5 masl with 0.2 m daily fluctuations in response to pumping of W6B. Water levels indicate seasonal fluctuations with levels generally highest in the spring and a decrease through the remainder of the year. The 2024 / 2025 water levels show a decreasing trend in response to increased pumping at W6B and W6, decreasing about 1 m from December 2023 to December 2025. Water levels in 2024 / 2025 are about 1.5 m lower than historical levels due to increased pumping at W6B and W6C.

WT-EB-OW1-15-AB

WT-EB-OW1-15-AB is located on the W7/W8 production well site and 900 m from W6B / W6C. It was constructed in July 2015 as a replacement for ET-EBS-OW7-57-B, which was decommissioned in October 2016.

The water level data from both the A screen (AFB2) and the B screen (AFB2) show responses to pumping of W7 / W8. Fluctuations of up to 1 m occur in response to periods of reduced pumping, though the response in the B screen is more subdued. The largest water level rises in response to decreased pumping are seen in November 2019, December 2020, August 2021 and August 2024. Smaller scale responses to reduced pumping are seen throughout 2024 / 2025. In 2024 / 2025 water levels are about 1.2 m below historical water levels.

4.0 Impact Assessment

4.1 Well Interference

PTTW Condition 5.1 states, "The Permit Holder shall immediately notify the local District Office of any complaint arising from the taking of water authorized under this Permit and shall report any action which has been taken or is proposed with regard to such complaint. The Permit Holder shall immediately notify the local District Office if the taking of water is observed to have any significant impact on the surrounding waters. After hours, calls shall be directed to the Ministry's Spills Action Centre at 1-800-268-6060."

PTTW Condition 5.2 states: "For Groundwater Takings - If the taking of water is observed to cause any negative impact to other water supplies obtained from any adequate sources that were in use prior to initial issuance of a Permit for this water taking, the Permit Holder shall take such action necessary to make available to those affected, a supply of water equivalent in quantity and quality to their normal takings, or shall compensate such persons for their reasonable costs of so doing, or shall reduce

the rate and amount of taking to prevent or alleviate the observed negative impact. Pending permanent restoration of the affected supplies, the Permit Holder shall provide to those affected temporary water supplies adequate to meet their normal requirements or shall compensate such persons for their reasonable costs of doing so. If permanent interference is caused by the water taking, the Permit Holder shall restore the water supplies of those permanently affected."

There were no well interference complaints related to pumping of W6B, W6C, W7 and W8 received in 2024 and 2025, therefore both conditions 5.1 and 5.2 have been met.

There are properties that are not municipally serviced for water supply within 500 m of the Erb Street Well Field. When a well interference complaint is received, the Region has a Well Interference Policy in place. A copy of the policy is presented in Appendix F of the 2019 Biennial Groundwater Monitoring Report – Multiple Well Fields (Burnside, 2020).

Other groundwater takings registered in the MECP PTTW database within 2 km of the wellfield are mapped on Figure 3 and summarized below in Table 5.

Table 5: PTTWs in Vicinity of Erb Street Well Field (W6B, W6C, W7, W8)

Permit Number	Permit Holder	Purpose	Source, Max Liters per Day	Distance from W6B, W6C and W7, W8 Supply Wells	Expiry Date
0540-CCQK8U	Miller Paving Limited	Aggregate Washing	Source Pond 1 – 9,720,000	1,700 m (W7, W8)	2/28/2027
1113-9RHQAE	Herrle-Braun	Agricultural	Dugout Pond 1,400,000	45 m (W6B,W6C) 300 m (W7,W8)	1/31/2025
8320-A4MMFP	Paul Mauthe	Agricultural	Dugout Pond 1,717,000	60 m (W6B,W6C) 300 m (W7,W8)	11/30/2025
7814-AW9KZ4	Herrle Farms Ltd.	Agricultural	Well 1, 696,600 Herrle Pond, 816,600	150 m (W6B,W6C) 750 m (W7,W8)	03/31/2028
6348-CHTK9H	Region of Waterloo	Remediation	EW433-21 1,296,000	1.4 km (W7,W8)	3/31/2032

Permit Number	Permit Holder	Purpose	Source, Max Liters per Day	Distance from W6B, W6C and W7, W8 Supply Wells	Expiry Date
			EW379-13, 1,008,000		
			EW77R-16, 534,240		
			EW362-09, 845,280		
			EW376-13, 263,021		
			EW377-13, 236,021		
			EW378-13, 773,281		

4.2 Aquifer Response to Pumping and Precipitation

PTTW Condition 4.3 states: "The Permit Holder shall prepare and submit an electronic copy of a report every two years by June 30 commencing June 30, 2020, that presents the results of the well field water level monitoring for the two preceding calendar years, assesses changes in water levels in the supply aquifer(s) in relation to precipitation and water taking from the aquifer(s)".

All the Erb Street production wells and monitoring wells are located in the same sand aquifer (AFB2) and show daily water level fluctuations in response to pumping at the production wells. Water levels reported in 2024 and 2025 have declined in all wells in response to increased pumping at W6B and W6C. Water levels in all wells at the end of 2025 are the lowest seen in the last 10 years of monitoring. Aquifer levels are continuing to decline at the end of 2025 in all wells except WT-EB-OW1-15-AB and WT-EB-OW3-08-AB where levels have stabilized.

Most of the monitoring wells for the Erb Street Well Field do not show seasonal trends with aquifer levels being mostly impacted by the pumping rather than precipitation trends. Seasonal fluctuations are observed at WT-EB-OW6-09-AB when pumping rates are generally stable, with the highest and lowest levels observed in the spring and late summer / fall, respectively. Correlation of individual precipitation events with

groundwater levels is difficult due to several reasons including but not limited to hydraulic conductivity, well depth, precipitation intensity, ground cover conditions and the time between water level measurements (monthly).

5.0 Conclusions

Impacts from pumping the municipal wells at the Erb Street Well Field (W6B, W6C, W7, W8) were evaluated through implementation of the Groundwater Monitoring Program. Based on the information contained in the report, Burnside offers the following conclusions:

- The information presented in this report satisfies condition 4.3 of PTTW 1541-AWGPZR;
- There were no reported well interference complaints arising from water taking at the Erb Street well field;
- All monitoring wells show some response to pumping at the Erb Street production wells; and
- Increased pumping of W6B and W6C has resulted in declining water levels in 2024 and 2025.

6.0 References

Aqua Insight Inc., 2026. Technical Memorandum Numerical Model Surface Transfer, March 2026.

Aqua Insight Inc., et al. 2023. Hydrogeological Characterization and Conceptual Model Update Report, Region of Waterloo Tier Three Assessment Update Project, June 2023.

Aqua Insight Inc. 2023. Moraine Model Update and Recalibration Report. Region of Waterloo Tier Three Update Project. Final Report, June 2023.

Bajc, A.F. and Shirota J., 2007. Three-dimensional mapping of surficial deposits in the Regional Municipality of Waterloo, southwestern Ontario; report in Ontario Geological Survey, Groundwater Resources Study 3, p. 42.

Golder Associates, 2017. 2015 Municipal Well Construction and Testing-Erb Street Well Field W6 Site, January 2017.

Karrow, P.F., 1993. Quaternary Geology of the Stratford-Conestogo Area, Southern Ontario. Ontario Geologic Survey Report 283.

Matrix Solutions Inc., 2015. Technical Memorandum: Numerical Model Surfaces Data Transfer, Region of Waterloo, June 5, 2015.

R.J. Burnside & Associates Limited, 2020. Region of Waterloo 2018/2019 Biennial Groundwater Monitoring Report.

R.J. Burnside & Associates Limited, 2024. 2023 Biennial Groundwater Monitoring Report – Erb Street Well Field, Region of Waterloo.

Stantec Consulting Ltd., 2009. Revised January 2012. Tier 3 Water Budget and Local Area Risk Assessment. Erb Street Well Field Characterization Study.

Stantec Consulting Ltd., 2016. 2015 Monitoring Well Replacement Program, Regional Municipality of Waterloo, December 20, 2016.





BURNSIDE


[THE DIFFERENCE IS OUR PEOPLE]



Figures



Data Source:
Region of Waterloo; Includes material © 2012 of the Queen's
Printer for Ontario. All rights reserved.



- | | |
|-------------------------------|-------------------------------------|
| Well Field Location | Township of North Dumfries |
| Well Fields | Township of Wellesley |
| Regional Municipal Boundaries | Township of Wilmot |
| City of Cambridge | Township of Woolwich |
| City of Kitchener | Meteorological Monitoring Locations |
| City of Waterloo | |



Map Title

2025 GROUNDWATER MONITORING REPORT - ERB STREET WELL FIELD

WELL FIELD LOCATION MAP

Client

REGION OF WATERLOO

Drawn

HN

Scale

1:300,000

Checked

SQ

Date


February 2026

Project No.

HA0464020

Figure No.

1





LEGEND

- Production Well Location
- Monitoring Well Location
- Wilmot Municipal Boundary
- Well Fields
- Meteorological Monitoring Locations

Sources:

1. Ministry of Natural Resources, © Queen's Printer for Ontario
2. Natural Resources Canada © Her Majesty the Queen in Right of Canada.
3. Region of Waterloo

Datum: North American 1983 CSRS
Coord. System: NAD 1983 CSRS UTM Zone 17N



Client

REGION OF WATERLOO

Figure Title


**2025 GROUNDWATER MONITORING
REPORT - ERB STREET WELL FIELD**
**WILMOT WELL FIELDS AND
MONITORING NETWORK**

Drawn	Checked	Date	Figure No. 2
HN	SQ	February 2026	
Scale		Project No. HA0464020	



- Legend**
- Production Well Location
 - Nearby Monitoring Well Location
 - Abandoned Well Location
- Additional MECP PTTW Locations**
- Groundwater
 - Cross Section Orientation
 - Intermittent Creek
 - Creek
 - Ponds
 - Provincially Significant Wetland (MNR)
- Roads (Regional) Labels**
- Regional Road
 - Local Road
 - Private / Other Road

Sources:
Region of Waterloo GIS Data; Background 2020 Air Photo: ArcGIS Image Service Region of Waterloo; Ministry of Natural Resources, © Queen's Printer for Ontario, Natural Resources Canada © Her Majesty the Queen in Right of Canada.



Client			
REGION OF WATERLOO			
Figure Title			
2025 GROUNDWATER MONITORING REPORT - ERB STREET WELL FIELD			
WELL LOCATION MAP			
Drawn	Checked	Date	Figure No.
HN	SQ	February 2026	
Scale		Project No.	
1:15,000		HA0464020	3



Data Source:
 1. Ontario Geological Survey 2003. Surficial Geology of Southern Ontario; Ontario Geological Survey, Miscellaneous Release--Data 128.
 2. Region of Waterloo GIS

- | | |
|---|---|
| RMOV Supply Well
Watercourse
Waterbody
Surficial Geology
5d: Glaciolacustrine-derived silty to clayey till (ATB1 - Aquitard)
6: Ice-contact stratified deposits (AFB1 - Aquifer)
7a: Glaciofluvial deposits: Sandy deposits (AFA2 - Aquifer)
8a: Fine-textured glaciolacustrine deposits: Massive-well laminated (ATA1)
19: Modern alluvial deposits
20: Organic deposits | Sand and Gravel Pit
Sample Location
Hummocky Topography
Unit Contact
Boundary |
|---|---|



Map Title
**2025 GROUNDWATER MONITORING
 REPORT - ERB STREET WELL FIELD**

SURFICIAL GEOLOGY

Client

REGION OF WATERLOO

Drawn

HN

Scale

1:30,000

Checked

SQ

Date



February 2026

Project No.

HA0464020

Figure No.

4



Data Source:
 1. Andy F. Bajc, Hazen A.J. Russell and David R. Sharpe (2014) A three-dimensional hydrostratigraphic model of the Waterloo Moraine area, Southern Ontario, Canada, Canadian Water Resources Journal / Revue canadienne des ressources hydriques, 39:2, 95-119
 2. Region of Waterloo; Includes material © 2019 of the Queen's Printer for Ontario. All rights reserved.



- Production Well Location
- Waterloo Moraine (2014)
- Erb Street Well Field
- Waterbody
- Regional Municipal Boundaries



Map Title

2025 GROUNDWATER MONITORING REPORT - ERB STREET WELL FIELD

LOCATION OF THE WATERLOO MORaine

Client

REGION OF WATERLOO

Drawn

HN

Scale

1:300,000

Checked

SQ

Date

February 2026

Project No.


HA0464020

Figure No.

5

A

A'



Wells


- Production Well (Active)
- Production Well (Inactive)
- Monitoring Well

Moraine Model 2026

Surficial Geology, Whittlesey Clay (ATA1) Whittlesey Sand (AFA1) Upper Maryhill, Port Stanley, Tavistock, Mornington, & Stratford Tills (ATB1)	Upper Waterloo Moraine Stratified Sediments & Equivalents (AFB1) Middle Maryhill Till & Equivalents (ATB2) Middle Waterloo Moraine Stratified Sediments & Equivalents (AFB2)	Lower Maryhill Till & Stratified Equivalents (ATB3) Lower Waterloo Moraine Stratified Sediments or Catfish Creek Till Outwash (AFB3) Upper/Main Catfish Creek Till (ATC1), Middle Catfish Creek Stratified Deposits (AFC1), Lower Catfish Creek Till (ATC2)	Pre-Catfish Creek Coarse-Grained Glaciofluvial/Lacustrine Deposits (AFD1) Canning Drift, Till & Fine Textured Glaciolacustrine Deposits (ATE1) Pre-Canning Coarse Textured Glaciofluvial / Glaciolacustrine Deposits (AFF1), Pre-Canning Coarse Textured Till (ATG1)	Weathered Bedrock	Wellhead Well Screen or Open Hole	BURNSIDE Client REGION OF WATERLOO	Figure Title GEOLOGIC CROSS SECTION REGION OF WATERLOO Erb Street Cross Section A - A'	<table><tr><td>Drawn</td><td>Checked</td><td>Date</td><td rowspan="3">Figure No.</td></tr><tr><td>PS</td><td>DH</td><td>2026/06/01</td></tr><tr><td colspan="2">Horizontal Scale 1:10,000</td><td>Project No.</td></tr><tr><td colspan="2">Vertical Ex.:10x</td><td>HA046402</td><td></td></tr></table>	Drawn	Checked	Date	Figure No.	PS	DH	2026/06/01	Horizontal Scale 1:10,000		Project No.	Vertical Ex.:10x		HA046402	
Drawn	Checked	Date	Figure No.																			
PS	DH	2026/06/01																				
Horizontal Scale 1:10,000		Project No.																				
Vertical Ex.:10x		HA046402																				

C

C'




Wells

- Production Well (Active) ● Monitoring Well

Moraine Model 2026

 Surficial Geology, Whittlesey Clay (ATA1)	 Upper Waterloo Moraine Stratified Sediments & Equivalents (AFB1)	 Lower Maryhill Till & Stratified Equivalents (ATB3)	 Pre-Catfish Creek Coarse-Grained Glaciofluvial/Lacustrine Deposits (AFD1)	 Weathered Bedrock
 Whittlesey Sand (AFA1)	 Middle Maryhill Till & Equivalents (ATB2)	 Lower Waterloo Moraine Stratified Sediments or Catfish Creek Till Outwash (AFB3)	 Canning Drift, Till & Fine Textured Glaciolacustrine Deposits (ATE1)	
 Upper Maryhill, Port Stanley, Tavistock, Mornington, & Stratford Tills (ATB1)	 Middle Waterloo Moraine Stratified Sediments & Equivalents (AFB2)	 Upper/Main Catfish Creek Till (ATC1), Middle Catfish Creek Stratified Deposits (AFC1), Lower Catfish Creek Till (ATC2)	 Pre-Canning Coarse Textured Glaciofluvial / Glaciolacustrine Deposits (AFF1), Pre-Canning Coarse Textured Till (ATG1)	



Client
REGION OF WATERLOO

Figure Title
**GEOLOGIC CROSS SECTION
REGION OF WATERLOO**
Erb Street
Cross Section C - C'

Drawn PS	Checked DH	Date 2026/06/01	Figure No. 8
Horizontal Scale 1:10,000		Project No. HA046402	
Vertical Ex.:10x			



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix A

Permit To Take Water

AMENDED PERMIT TO TAKE WATERGround Water
NUMBER 1541-AWGP

Pursuant to Section 34.1 of the Ontario Water Resources Act, R.S.O. 1990 this Permit To Take Water is hereby issued to:

The Regional Municipality of Waterloo
Floor 7 - 150 Frederick St
Kitchener, Ontario, N2G 4J3
Canada

For the water taking from: W6C, W6B, W7 and W8

Located at: Lot 2, Concession GERMAN BLOCK SOUTH OF ERBS ROAD, Geographic
Township of Wilmot
Wilmot, Regional Municipality of Waterloo

Lot 2, Concession GERMAN BLOCK NORTH OF ERBS ROAD, Geographic
Township of Wilmot
Wilmot, Regional Municipality of Waterloo

For the purposes of this Permit, and the terms and conditions specified below, the following definitions apply:

DEFINITIONS

- (a) "Director" means any person appointed in writing as a Director pursuant to section 5 of the OWRA for the purposes of section 34.1, OWRA.
- (b) "Provincial Officer" means any person designated in writing by the Minister as a Provincial Officer pursuant to section 5 of the OWRA.
- (c) "Ministry" means Ontario Ministry of the Environment and Climate Change.

- (d) "District Office" means the Guelph District Office.
- (e) "Permit" means this Permit to Take Water No. 1541-AWGPZR including its Schedules, if any issued in accordance with Section 34.1 of the OWRA.
- (f) "Permit Holder" means The Regional Municipality of Waterloo.
- (g) "OWRA " means the *Ontario Water Resources Act*, R.S.O. 1990, c. O. 40, as amended.

You are hereby notified that this Permit is issued subject to the terms and conditions outlined below :

TERMS AND CONDITIONS

1. Compliance with Permit

- 1.1 Except where modified by this Permit, the water taking shall be in accordance with the application for this Permit To Take Water, dated November 29, 2017 and signed by Richard Wootton, and all Schedules included in this Permit.
- 1.2 The Permit Holder shall ensure that any person authorized by the Permit Holder to take water under this Permit is provided with a copy of this Permit and shall take all reasonable measures to ensure that any such person complies with the conditions of this Permit.
- 1.3 Any person authorized by the Permit Holder to take water under this Permit shall comply with the conditions of this Permit.
- 1.4 This Permit is not transferable to another person.
- 1.5 This Permit provides the Permit Holder with permission to take water in accordance with the conditions of this Permit, up to the date of the expiry of this Permit. This Permit does not constitute a legal right, vested or otherwise, to a water allocation, and the issuance of this Permit does not guarantee that, upon its expiry, it will be renewed.
- 1.6 The Permit Holder shall keep this Permit available at all times at or near the site of the taking, and shall produce this Permit immediately for inspection by a Provincial Officer upon his or her request.
- 1.7 The Permit Holder shall report any changes of address to the Director within thirty days of any

such change. The Permit Holder shall report any change of ownership of the property for which this Permit is issued within thirty days of any such change. A change in ownership in the property shall cause this Permit to be cancelled.

2. General Conditions and Interpretation

2.1 Inspections

The Permit Holder must forthwith, upon presentation of credentials, permit a Provincial Officer to carry out any and all inspections authorized by the OWRA, the *Environmental Protection Act*, R.S.O. 1990, the *Pesticides Act*, R.S.O. 1990, or the *Safe Drinking Water Act*, S.O. 2002.

2.2 Other Approvals

The issuance of, and compliance with this Permit, does not:

(a) relieve the Permit Holder or any other person from any obligation to comply with any other applicable legal requirements, including the provisions of the *Ontario Water Resources Act*, the *Environmental Protection Act*, and any regulations made thereunder; or

(b) limit in any way any authority of the Ministry, a Director, or a Provincial Officer, including the authority to require certain steps be taken or to require the Permit Holder to furnish any further information related to this Permit.

2.3 Information

The receipt of any information by the Ministry, the failure of the Ministry to take any action or require any person to take any action in relation to the information, or the failure of a Provincial Officer to prosecute any person in relation to the information, shall not be construed as:

(a) an approval, waiver or justification by the Ministry of any act or omission of any person that contravenes this Permit or other legal requirement; or

(b) acceptance by the Ministry of the information's completeness or accuracy.

2.4 Rights of Action

The issuance of, and compliance with this Permit shall not be construed as precluding or limiting any legal claims or rights of action that any person, including the Crown in right of Ontario or any agency thereof, has or may have against the Permit Holder, its officers, employees, agents, and contractors.

2.5 Severability

The requirements of this Permit are severable. If any requirements of this Permit, or the application of any requirements of this Permit to any circumstance, is held invalid or

unenforceable, the application of such requirements to other circumstances and the remainder this Permit shall not be affected thereby.

2.6 Conflicts

Where there is a conflict between a provision of any submitted document referred to in this Permit, including its Schedules, and the conditions of this Permit, the conditions in this Permit shall take precedence.

3. Water Takings Authorized by This Permit

3.1 Expiry

This Permit expires on **January 31, 2028**. No water shall be taken under authority of this Permit after the expiry date.

3.2 Amounts of Taking Permitted

The Permit Holder shall only take water from the source, during the periods and at the rates and amounts of taking specified in Table A. Water takings are authorized only for the purposes specified in Table A.

Table A

	Source Name / Description:	Source: Type:	Taking Specific Purpose:	Taking Major Category:	Max. Taken per Minute (litres):	Max. Num. of Hrs Taken per Day:	Max. Taken per Day (litres):	Max. Num. of Days Taken per Year:	Zone/ Easting/ Northing:
1	W6C	Well Drilled	Municipal	Water Supply	3,865	24	5,565,600	365	17 532487 4809801
2	W6B	Well Drilled	Municipal	Water Supply	3,182	24	4,582,080	365	17 532492 4809796
3	W7	Well Drilled	Municipal	Water Supply	6,365	24	9,165,600	365	17 533135 4809136
4	W8	Well Drilled	Municipal	Water Supply	7,274	24	10,474,560	365	17 533130 4809153
						Total Taking:	29,787,840		

3.3 Notwithstanding the maximum total taking per day specified in Table A of Condition 3.2, the combined taking from wells W6C, W6B, W7 and W8 shall not exceed an annual daily average of 17,272,800 L/day.

4. Monitoring

- 4.1 Under section 9 of O. Reg. 387/04, and as authorized by subsection 34(6) of the *Ontario Water Resources Act*, the Permit Holder shall, on each day water is taken under the authorization of this Permit, record the date, the volume of water taken on that date and the rate at which it was taken. The daily volume of water taken shall be measured by a flow meter or calculated in accordance with the method described in the application for this Permit, or as otherwise accepted by the Director. A separate record shall be maintained for each source. The Permit Holder shall keep all records required by this condition current and available at or near the site of the taking and shall produce the records for inspection by a Provincial Officer upon his or her request. The Permit Holder, unless otherwise required by the Director, shall submit, on or before March 31st in every year, the records required by this condition to the ministry's Water Taking Reporting System.

- 4.2 The Permit Holder shall measure and record water levels once a month in the following monitoring wells:

WT-EB-OW322-02-A
WT-EB-OW322-02-B
WT-EB-OW332-02-A
WT-EB-OW1-08-A
WT-EB-OW1-08-B
WT-EB-OW2-08-A
WT-EB-OW2-08-B
WT-EB-OW3-08-A
WT-EB-OW3-08-B
WT-EB-OW6-09-A
WT-EB-OW6-09-B
WT-EB-OW1-15-A
WT-EB-OW1-15-B

- 4.3 The Permit Holder shall prepare and submit a report every two years by June 30 commencing June 30, 2018, that presents the results of the well field water level monitoring for the two preceding calendar years, assesses changes in water levels in the supply aquifer(s) in relation to precipitation and water taking from the aquifer(s), and provides a summary for all interference complaints received by the Permit Holder related to this permit and reported in the District Office in accordance with Condition 5.1 and the manner in which the Permit Holder has dealt with the complaint.
- 4.4 Any application for renewal of this Permit shall be accompanied by an assessment of capture zones induced by the water taking under this Permit, relative to the Waterloo Landfill and related contamination in the municipal aquifer. Monthly water level monitoring data gathered both for this Permit and the following monitoring wells associated with the Waterloo Landfill shall be considered in that assessment:

OW358A-08
OW359A-08
OW338A-05
OW337A-05
OW6-57
OW336-05
OW345A-06
OW333-04

TW30-86

5. Impacts of the Water Taking

5.1 Notification

The Permit Holder shall immediately notify the local District Office of any complaint arising from the taking of water authorized under this Permit and shall report any action which has been taken or is proposed with regard to such complaint. The Permit Holder shall immediately notify the local District Office if the taking of water is observed to have any significant impact on the surrounding waters. After hours, calls shall be directed to the Ministry's Spills Action Centre at 1-800-268-6060.

5.2 For Groundwater Takings

If the taking of water is observed to cause any negative impact to other water supplies obtained from any adequate sources that were in use prior to initial issuance of a Permit for this water taking, the Permit Holder shall take such action necessary to make available to those affected, supply of water equivalent in quantity and quality to their normal takings, or shall compensate such persons for their reasonable costs of so doing, or shall reduce the rate and amount of taking to prevent or alleviate the observed negative impact. Pending permanent restoration of the affected supplies, the Permit Holder shall provide, to those affected, temporary water supplies adequate to meet their normal requirements, or shall compensate such persons for their reasonable costs of doing so.

If permanent interference is caused by the water taking, the Permit Holder shall restore the water supplies of those permanently affected.

6. Director May Amend Permit

The Director may amend this Permit by letter requiring the Permit Holder to suspend or reduce the taking to an amount or threshold specified by the Director in the letter. The suspension or reduction in taking shall be effective immediately and may be revoked at any time upon notification by the Director. This condition does not affect your right to appeal the suspension or reduction in taking to the Environmental Review Tribunal under the *Ontario Water Resources Act*, Section 100 (4).

The reasons for the imposition of these terms and conditions are as follows:

1. Condition 1 is included to ensure that the conditions in this Permit are complied with and can enforced.
2. Condition 2 is included to clarify the legal interpretation of aspects of this Permit.
3. Conditions 3 through 6 are included to protect the quality of the natural environment so as to safeguard the ecosystem and human health and foster efficient use and conservation of waters. These conditions allow for the beneficial use of waters while ensuring the fair sharing, conservation and sustainable use of the waters of Ontario. The conditions also specify the wa takings that are authorized by this Permit and the scope of this Permit.

In accordance with Section 100 of the Ontario Water Resources Act, R.S.O. 1990, you may by written Notice served upon me and the Environmental Review Tribunal within 15 days after receipt of this Notice, require a hearing by the Tribunal. Section 101 of the Ontario Water Resources Act, R.S.O. 1990, as amended, provides that the Notice requiring the hearing shall state:

1. The portions of the Permit or each term or condition in the Permit in respect of which the hearing required, and;
2. The grounds on which you intend to rely at the hearing in relation to each portion appealed.

In addition to these legal requirements, the Notice should also include:

- a. The name of the appellant;
- b. The address of the appellant;
- c. The Permit to Take Water number;
- d. The date of the Permit to Take Water;
- e. The name of the Director;
- f. The municipality within which the works are located;

This notice must be served upon:

*The Secretary
Environmental Review Tribunal
655 Bay Street, 15th Floor
Toronto ON
M5G 1E5
Fax: (416) 326-5370
Email: ERTTribunalsecretary@ontario.ca*

AND

*The Director, Section 34.1, Ministry of the
Environment and Climate Change
12th Floor
119 King St W
Hamilton ON L8P 4Y7
Fax: (905) 521-7820*

Further information on the Environmental Review Tribunal's requirements for an appeal can be obtained directly from the Tribunal:


by Telephone at
(416) 212-6349
Toll Free 1(866) 448-2248

by Fax at
(416) 326-5370
Toll Free 1(844) 213-3474

by e-mail at
www.ert.gov.on.ca

This Permit cancels and replaces Permit Number 0718-AV4S6J, issued on 2018/01/26.

Dated at Hamilton this 2nd day of March, 2018.



Belinda Koblik

Director, Section 34.1
Ontario Water Resources Act , R.S.O. 1990

Schedule A

This Schedule “A” forms part of Permit To Take Water 1541-AWGPZR, dated March 2, 2018.



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]


Appendix B

Well Records

WELL DIAGRAM

Depth
Ft. LOG

0—
— Brown Clay
—
18—
— Grey Clay
—
40—
—
50—
— Grey Clay
— Gravel
—
—
—
—
—
90—
— Sandy Clay
100— Gravel
103—
— Sandy Clay
— Boulders
115—
— Silty Grey Clay
125—
—
— Clay, Sandy
— Gravelly Boulders
150—
—
159—
— Fine Gravel
— & Sand
177 Fine/Coarse Gravel Sand
79 Fine Sandy Clay
82—
—
—



△ - Bentonite Pellet Seal

WELL MATERIAL

W6B

Outer Casing: 24" dia., 0.375" Wall Thk. Matl.: STL
Cemented from 0' - " to 28' - "
Inner Casing: 12" dia., 0.33" Wall Thk. Matl.: STL
Screen: Make John 12" dia., Opening & Matl.: #30 SS
Plug: Type Plate, Matl. SS, Other:
Gravel: Type, Size, Quantity

WELL TEST DATA

Preliminary Test Date: OCT 31/85 by R. Stroh
Static Level: 114.31' " below M.P. (+75'-0")
Pumping Rate IGM: STEP TEST 104/396/593
Pumping Duration: 6 hrs. min.
Pumping Level at Test End: 131.69' "
Performance Plots: dd-t Dwg.
dd-r Dwg.
Step Test B-85441

Final Test: Date by
Rated Well Capacity IGM
Pumping Rate IGM Static level
Pumping level at hrs. min.
Pump pressure: psi Main pressure psi
Shut off: AGH psi W.L.
Clear Well Depth from B.P. Air Line

PUMP & MOTOR DATA

Pump Make LAYNE Rating 700 IGM @ 260' TH
Head: Type 8" FAE 1WS GLB S.N.
Column: X 6" X " Shaft Mtl.
Bowl: BTH Stage 3 Curve: 36-069
Suction: " dia. " Long
Special: Zinc Sleeves Taped Oil Line
Other
Motor Make: Peugeot Frame: VN8-87 SN:
75 HP, 3 ph, 60 hz, 3500 rpm, 575 Volts
Bearing No. Upper
Lower

Special Equipment

CABLE: 2/3 J w/ No 6 Ground
Air Line Length: 145.0 ft.

WELL REVISIONS AND REHABILITATION

DATE	WORK DONE	BY

International Water Supply Limited

SASKATOON - BARRIE - MONTREAL

CLIENT: REGION of WATERLOO

WELL NO: W6B

DRILLED BY: Kyle


DATE: 1985

DRAWN: B

INSTALLED BY:

DATE:

DATE: Nov 19/85



CLIENT

Regional Municipality of Waterloo

TITLE

Well W6B
Pump Installation Drawing

PROJECT No. 006-205

G:\Lotowater Projects\006 Region of Waterloo\205 W6B Testing\Submersible Pump Installation.dwg

DESIGN		
DRAWN	EH	2011/04/25
CHECKED		


REVISION No. 2011-04-25

SCALE N.T.S.

FIGURE

4

W6B

Depth
in metres

CLIENT

Regional Municipality of Waterloo

TITLE

Well W6B
Pump Installation Drawing

PROJECT No.006-394

G:\Lotowater Projects\006 Region of Waterloo\394 W6B\Submersible Pump Installation.dwg

DESIGN

DRAWN

CHECKED

EH

2012/12/05

REVISION No. 2017/05/04

SCALE N.T.S.

FIGURE

1

PROJECT: 1520338

RECORD OF BOREHOLE: W6C Pilot Hole

SHEET 1 OF 6

LOCATION: N 4809801.00; E 532486.70

BORING DATE: December 2, 2015

DATUM: UTM NAD 83

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m				HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	SHEAR STRENGTH Cu, kPa		nat V. + Q - rem V. U -		WATER CONTENT PERCENT			
								20	40	60	80	10 ⁻⁶	10 ⁻⁵		
0		GROUND SURFACE		385.06											
		TOPSOIL		0.00											
1															
2		(CL) SILTY CLAY, trace fine to medium sand, light brown, cohesive, W>PL, soft to very soft		383.54 1.52											
3															
4															
5	Air Rotary														
6															
7															
8															
9															
10															
		CONTINUED NEXT PAGE													

DEPTH SCALE

1 : 50



LOGGED: HJ

CHECKED:

PROJECT: 1520338
LOCATION: N 4809801.00; E 532486.70

RECORD OF BOREHOLE: W6C Pilot Hole

BORING DATE: December 2, 2015

SHEET 2 OF 6
DATUM: UTM NAD 83

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m				HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	SHEAR STRENGTH Cu, kPa		nat V. + Q - ● rem V. ⊕ U - ○		WATER CONTENT PERCENT Wp — W — Wi				
								20	40	60	80	10 ⁻⁶	10 ⁻⁵			10 ⁻⁴
10	Air Rotary	--- CONTINUED FROM PREVIOUS PAGE --- (CL) SILTY CLAY, trace fine to medium sand, light brown, cohesive, W>PL, soft to very soft														
11																
12																
13																
14																
15																
16																
17																
18																
19																
20																
		CONTINUED NEXT PAGE														

DEPTH SCALE
1 : 50



LOGGED: HJ
CHECKED:

PROJECT: 1520338
LOCATION: N 4809801.00; E 532486.70

RECORD OF BOREHOLE: W6C Pilot Hole

BORING DATE: December 2, 2015

SHEET 3 OF 6
DATUM: UTM NAD 83

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m				HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	SHEAR STRENGTH Cu, kPa		nat V. + Q - rem V. ⊕ U - ○		WATER CONTENT PERCENT Wp — W — Wi			
								20	40	60	80	10 ⁻⁶	10 ⁻⁵		
20	Air Rotary	--- CONTINUED FROM PREVIOUS PAGE --- (CL) SILTY CLAY, trace fine to medium sand, light brown, cohesive, W>PL, soft to very soft		362.20 22.86											
21															
22															
23															
24															
25															
26															
27															
28															
29															
30															
CONTINUED NEXT PAGE															

DEPTH SCALE
1 : 50



LOGGED: HJ
CHECKED:

PROJECT: 1520338
LOCATION: N 4809801.00; E 532486.70

RECORD OF BOREHOLE: W6C Pilot Hole

BORING DATE: December 2, 2015

SHEET 4 OF 6
DATUM: UTM NAD 83

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m				HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	SHEAR STRENGTH Cu, kPa		nat V. + Q - rem V. U -		WATER CONTENT PERCENT Wp — W — Wi			
								20	40	60	80	10 ⁻⁶	10 ⁻⁵		
30	Air Rotary	--- CONTINUED FROM PREVIOUS PAGE --- (ML) CLAYEY SILT, trace to some sand to fine gravel, light brown, cohesive, W>PL, soft to very soft													
31															
32		(GM) SILTY GRAVEL, fine to coarse, some fine to coarse sand, non-cohesive		353.06 32.00											
33															
34															
35		(ML) GRAVELLY CLAYEY SILT, fine gravel, some medium to coarse sand, grey to brown, cohesive, soft		350.01 35.05											
36															
37		(CL) SILTY CLAY, trace to some sand, grey to brown, cohesive, soft to firm		348.48 36.58											
38															
39															
40															
		CONTINUED NEXT PAGE													

DEPTH SCALE
1 : 50



LOGGED: HJ
CHECKED:

PROJECT: 1520338
LOCATION: N 4809801.00; E 532486.70

RECORD OF BOREHOLE: W6C Pilot Hole

BORING DATE: December 2, 2015

SHEET 5 OF 6
DATUM: UTM NAD 83

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m				HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION								
		DESCRIPTION	STRATA PLOT ELEV. DEPTH (m)	NUMBER	TYPE	20		40		60		80				10 ⁻⁶		10 ⁻⁵		10 ⁻⁴		10 ⁻³	
						SHEAR STRENGTH Cu, kPa		nat V. + rem V. ⊕		Q - U -		● ○				WATER CONTENT PERCENT Wp — W — Wi							
40	Air Rotary	--- CONTINUED FROM PREVIOUS PAGE --- (CL) SILTY CLAY, trace to some sand, grey to brown, cohesive, soft to firm																					
41																							
42																							
43																							
44																							
45		(SM) GRAVELLY SILTY SAND, fine to coarse, fine to coarse gravel, some clay pockets, non-cohesive	340.86 44.20																				
46		(SP) SAND and GRAVEL, some silt and clay, fine to coarse sand, fine gravel, trace clay pockets	339.34 45.72																				
47		(SW) SAND, fine to medium, trace clay pockets	338.58 46.48																				
48		(SM) GRAVELLY SILTY SAND, fine to coarse, fine to coarse gravel, trace to some clay pockets to 49.5	337.05 48.01																				
49																							
50																							
		CONTINUED NEXT PAGE																					

DEPTH SCALE
1 : 50



LOGGED: HJ
CHECKED:

PROJECT: 1520338
LOCATION: N 4809801.00; E 532486.70

RECORD OF BOREHOLE: W6C Pilot Hole

BORING DATE: December 2, 2015

SHEET 6 OF 6
DATUM: UTM NAD 83

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m				HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	SHEAR STRENGTH Cu, kPa		nat V. + Q - rem V. U -		WATER CONTENT PERCENT				
								20	40	60	80	10 ⁻⁶	10 ⁻⁵	10 ⁻⁴		
50	Air Rotary	--- CONTINUED FROM PREVIOUS PAGE ---														
		(SM) GRAVELLY SILTY SAND, fine to coarse, fine to coarse gravel, trace to some clay pockets to 49.5														
51		(SP) GRAVELLY SAND, fine to coarse, trace to some silt		334.01 51.05												
52																
53																
54		(SM) SILTY SAND, fine to medium, trace gravel		330.96 54.10												
55																
56																
57																
58																
59		(CH) CLAY, trace medium to coarse sand, cohesive, soft		326.39 58.67												
60		END OF BOREHOLE		325.32 59.74												

DEPTH SCALE
1 : 50



LOGGED: HJ
CHECKED:

Driller Log

Pilot Hole W6C (Summary)
Refer to Appended Log for full Details

Top of Casing (Stick-up)
0.60 magl


As-Built

W6C

Protective Cap

Grade Elevation 385.06 masl

Depth
mbgl



*Note:

All depths are metres below ground level unless otherwise stated.
Depths from metres to feet nominal 1 foot intervals

Well Constructed March 1 - 9, 2016 by Gerrits Drilling

CLIENT
REGION OF WATERLOO

PROJECT
ERB STREET WELL FIELD
2015 CONSTRUCTION AND TESTING AT SITE W6

CONSULTANT



YYYY-MM-DD 2016-07-18

PREPARED JPR

DESIGN JAE

REVIEW

APPROVED GWS

TITLE

TEST PRODUCTION WELL W6C
CONSTRUCTION AS-BUILT

PROJECT No.
1520338

Phase

Rev.


Figure

9

Motor
 Manufacturer: U.S. Motors
 Power: 150hp / 575v / 3ph
 Serial #: U1120131392-0001 R 00 01

W7

Depth
 in metres




CLIENT

Regional Municipality of Waterloo


TITLE

Well W7
 Pump Installation Drawing

PROJECT No.006—360			G:\Lotowater Projects\006 Regional of Waterloo\360 Well W7\Pump Install.dwg		FIGURE 1
DESIGN			REVISION No. 2016—02—22	SCALE N.T.S.	
DRAWN	EH	2016—02—18			
CHECKED					



			CLIENT REGIONAL MUNICIPALITY OF WATERLOO		
			TITLE W8 Pump Installation Drawing		
PROJECT No. 006-232			G:\Lotowater Projects\006 Region of Waterloo\232 W8 Repair\7. Technical\Pump Install.dwg		FIGURE 1
DESIGN			REVISION No. 2012/08/02	SCALE N.T.S.	
DRAWN	EH	2012/08/02			
CHECKED					



CLIENT

Regional Municipality of Waterloo

TITLE

**Well W8
Pump Installation Drawing**PROJECT No. **006-320**

G:\Lotowater Projects\006 Region of Waterloo\320 W8 Emergency\Pump Install.dwg

DESIGN

DRAWN

EH**2014/10/21**


REVISION No. 2014-10-28

SCALE **N.T.S.**

FIGURE

1

CHECKED



Lotowater
TECHNICAL SERVICES INC.

CLIENT

Regional Municipality of Waterloo

TITLE

Well W8
Pump Installation Drawing

PROJECT No. 006-379

G:\Lotowater Projects\006 Region of Waterloo\379 W8 Emergency\Pump Install.dwg

DESIGN

DRAWN

CHECKED

EH

2016/09/27

REVISION No.

2016-09-27

SCALE N.T.S.

FIGURE

1




STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 4

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW345A-06
DATE COMPLETED: August 11, 2006
DRILLING METHOD: 6 1/4" ID HSA/PQ CORING
FIELD PERSONNEL: B. IOTZOV

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (m)	'N' VALUE
	TOPSOIL	0.15		01	X	0.46	15
1	ML-SILT, trace sand, trace clay, trace gravel, firm, low plasticity, massive, brown, dry			02	X	0.20	13
	- light brown to tan, trace silt at 1.52m BGS			03	X	0.20	19
2				04	X	0.51	44
3	SP-SAND, compact, fine to medium grained sand, moderately to poorly graded, dry to moist, brown	2.59		05	X	0.05	29
	ML-SILT, with sand, trace clay, trace gravel, firm, low plasticity, fine sand, massive, tan-brown, moist	3.20		06	X	0.55	21
4	SP-SAND, compact, fine to medium grained sand, moderately poorly graded, moist, brown	3.96		07	X	0.52	20
5	- stratified at 5.03m BGS			08	X	0.55	31
6	- massive at 5.79m BGS			09	X	0.30	65
	- stratified at 6.40m BGS			10		0.30	-
7				11		0.30	-
8				12		0.00	-
9	- moist at 9.14m BGS			13		1.52	-
10				14		0.15	-
11	SM-SAND, with silt, fine grained, moist, light grey-brown, stratified	11.06		15		1.37	-
12	SP-SAND, loose, coarse grained sand, poorly graded, dry to moist, light brown	11.89		16		0.30	-
13	SM-SAND, with silt, fine and medium grained sand, well graded, light brown, dry to moist	12.19					
14							
15							
16							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 2 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW345A-06

PROJECT NUMBER: 823-02

DATE COMPLETED: August 11, 2006

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: 6 1/4" ID HSA/PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. IOTZOV

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (m)	'N' VALUE
18		18.29		17		0.61	-
	SP-SAND, loose, coarse grained sand, poorly graded, dry to moist, light brown	18.90		18		0.91	-
19	SM/SP-SAND, with silt, fine to medium sand, stratified, light brown, dry to moist			19		0.00	-
20				20		1.22	-
21	SW/GW-SAND AND GRAVEL, dense, medium and coarse sand, fine to coarse gravel, possibly stratified, light brown - light grey, well graded, moist	21.34		21		0.00	-
22	- trace clay in sand lense from 22.13 to 22.19m BGS	22.10		22		0.91	-
23	SM-SAND, with silt, fine to medium sand, moderately to poorly graded, stratified, brown-tan, moist	22.40		23		0.91	-
24	- trace clay in sand lense from 22.37 to 22.40m BGS			24		0.30	-
25	SP-SAND, compact, medium to coarse sand, poorly graded, stratified, moist			25		1.22	-
26				26		0.00	-
27	SW/GW-SAND AND GRAVEL, dense, medium and coarse sand, fine to coarse gravel, possibly stratified, tan-brown, well graded, moist	25.91		27		0.00	-
28							
29	CL-SITY CLAY, stiff, medium to high plasticity, massive, reddish brown, moist	28.04					
30	SM/ML-SAND AND SILT, compact, fine sand, stratified, brown-tan, moist	28.13					
31	ML-SILT (WATERLAIN), with clay to clayey, trace fine sand, low plasticity, grey-brown, stratified, moist	28.96					
32	- no sample recovery, losing large volume of drilling fluid from 30.48 to 33.53m BGS						
33							
	SM-SAND (WATERLAIN), with silt, fine to medium	33.53					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2006).GPJ CRA CORP.GDT 10/16/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 4

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW345A-06
DATE COMPLETED: August 11, 2006
DRILLING METHOD: 6 1/4" ID HSA/ PQ CORING
FIELD PERSONNEL: B. IOTZOV

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (m)	'N' VALUE
35	sand, moderately to poorly graded, stratified, moist, light grey-brown			28		1.22	-
36				29		0.00	-
37	SW-SAND, loose to compact, fine to coarse grained, well graded, light grey to light brown, moist to wet	36.58		30		1.22	-
38	SM-SAND (WATERLAIN), with silt, fine to medium sand, moderately to poorly graded, stratified, moist, light grey-brown	37.95		31		0.91	-
39				32		0.00	-
40	ML-SILT (WATERLAIN), with clay, trace fine sand, low plasticity, stratified, light grey-brown, moist	39.62		33		1.52	-
41	SM/SP-SAND, with silt, medium grained sand, trace fine sand, stratified, occasional silt lense (1cm thick), light brown, wet	40.54		34		0.00	-
42	- medium to coarse grained sand at 41.15m BGS - medium grained, becoming grey at 41.45m BGS			35		0.00	-
43	- no sample recovery from 42.67 to 45.72m BGS			36		0.91	-
44				37		0.76	-
45				38		0.91	-
46	SM-SAND, with silt, fine to medium grained sand, brown, wet	45.72					
47							
48							
49	SP-SAND, trace silt, medium grained, poorly graded, brown, wet	48.77					
50							
	ML/SM-SILT AND SAND, stiff, very fine sand, stratified, dilatant, grey, wet, occasional clayey	50.29					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2006) GPJ CRA CORP GDT 10/16/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 4 of 4

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW345A-06
DATE COMPLETED: August 11, 2006
DRILLING METHOD: 6 1/4" ID HSA/PQ CORING
FIELD PERSONNEL: B. IOTZOV

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (m)	'N' VALUE
	seams			39		0.61	-
52	- slightly coarser with depth at 51.82m BGS			40		0.61	-
53	- medium grained sand from 53.34 to 53.64m BGS	53.64	#1 SILICA SAND	41		0.91	-
54	SP/SM-SAND, with silt, fine to medium grained, some stratification, grey, wet		2" Ø STAINLESS STEEL SCREEN	42		1.22	-
55	ML/SM-SILT AND SAND, stiff, very fine sand, grey, wet, occasional stratification	54.86		43		1.22	-
56				44		0.91	-
57				45		0.61	-
58		58.52		46		0.76	-
59	SM/SW-SAND, with silt, fine to coarse sand, well graded, grey, wet		BENTONITE CHIPS				
60							
61	CL/ML-CLAY AND SILT (MARYHILL TILL), stiff, medium plasticity, wet, grey	60.96					
62							
63	END OF BOREHOLE @ 62.48m BGS	62.48					
64	Lost large volume of drilling fluid between 27 and 33 metres below ground surface						
65							
66							
67							

WELL DETAILS
Screened interval:
52.12 to 55.17m BGS
Length: 3.05m
Diameter: 51mm
Slot Size: 10
Material: STAINLESS STEEL
Seal:
0.91 to 50.60m BGS
Material: BENTONITE GROUT
Sand Pack:
50.60 to 62.48m BGS
Material: #1 SILICA SAND

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2003).GPJ CRA_CORP.GDT 10/16/06

9203593

Monitoring Well: WT-EBS-OW6A-09

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R. Dong
Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
Date started/completed: Jan-2-2009 / Jan-3-2009
Ground surface elevation: 378.21 m AMSL
Top of casing elevation: 378.96 m AMSL
Easting: 533190.802
Northing: 4809730.08

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth (ft) (m)	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
0	0	Ground Surface	378.21						Stick up=0.75 m Blue steel protective casing
		TOPSOIL fine sand and silt, brown, rootlets, moist	0.00	1	SS	2-2-2-2 (4)	3" 13%		Concrete
				2	SS	1-2-2-2 (4)	16" 67%		
5		CLAYEY SILT trace very fine sand, brown with trace black, soft	376.68 1.52	3	SS	1-3-3-3 (6)	18" 75%		
		SAND fine grained, little coarse sand, little clay and silt, brown, firm, moist	376.08 2.13	4	SS	1-2-3-3 (5)	16" 67%		
		no clay and silt, trace coarse sand at 2.59 m BGS		5	SS	n/a	36" 95%		
10				6	SS	n/a	45" 75%		PVC Sch80 50 mm diameter
		seam of very fine sand, 0.13 m thick, at 4.67 m BGS increasing in moisture at 4.88 m BGS		7	CC	n/a	37" 61%		Bentonite Grout
		seam of very fine sand 0.18 m thick at 5.72 m BGS		8	CC	n/a	42" 71%		
		wet at 6.63 m BGS		9	CC	n/a	40" 67%		
		homogeneous, no trace at 8.13 m BGS		10	CC	n/a	53" 88%		
		seam of very fine and medium fine sand, mottled 0.13 m thick at 9.02 m BGS		11	CC	n/a	57" 95%		
		seam of silty clay and very fine sand 0.03 m thick at 10.13 m BGS							
		seam of layered silty clay 0.03 m thick at 10.69 m BGS seam of layered silty clay 0.03 m thick at 10.90 m BGS seam of very fine sand 0.03 m thick at 11.13 m BGS decrease in moisture content at 11.17 m BGS							
		seam of medium sand 0.64 m thick at 11.81 m BGS seam of very fine sand 0.03 m thick at 11.91 m BGS							
		wet at 12.70 m BGS	376.08						

Screen Interval: 46.63 - 49.68 m BGS
 Sand Pack Interval: 45.36 - 50.22 m BGS
 Well Seal Interval: 0.91 - 45.36 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOT - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 1 of 4

Monitoring Well: WT-EBS-OW6A-09

WT-EB-OW6-09-A

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field Investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Jan-2-2009 / Jan-3-2009
 Ground surface elevation: 378.21 m AMSL
 Top of casing elevation: 378.96 m AMSL
 Easting: 533190.802
 Northing: 4809730.08

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
45	14	SAND fine grained, little coarse sand, little clay and silt, brown, firm, moist seam of very fine sand 0.10 m thick at 13.41 m BGS seam of very fine sand 0.03 m thick at 13.51 m BGS seam of layered silty clay 0.03 m thick at 13.84 m BGS seam of very fine sand 0.13 m thick at 14.43 m BGS seam of very fine sand 0.08 m thick at 14.76 m BGS seam of very fine sand 0.25 m thick at 14.91 m BGS	2.13	12	CC	n/a	42" 70%		Bentonite Grout
50	15	4 seams of soft brown clayey silt 3 mm thick between 16.05 to 16.10 m BGS		13	CC	n/a	60" 100%		
55	16	becoming coarser fine sand at 17.65 m BGS becoming wet at 17.65 m BGS		14	CC	n/a	61" 100%		
60	17			15	CC	n/a	45" 76%		
65	18		359.90	16	CC	n/a	53" 88%		
70	19	SILTY CLAY AND CLAYEY SILT AND VERY FINE SAND brown, red, brown and black layers, very stiff, moist mottled structure beginning at 18.68 m BGS increasing very fine sand content from 18.80 to 19.40 m BGS	18.31	17	CC	n/a	57" 95%		
75	20	SAND fine grained, brown, moist very fine sand 0.20 m thick at 20.12 m BGS seam of stiff, brown, silty clay 2 mm thick at 20.14 m BGS seam of stiff, brown silty clay 1 mm thick at 20.15 m BGS sulfurous odour beginning at 20.32 m BGS seam of very fine sand 0.08 m thick at 20.75 m BGS seam of very fine sand 0.08 m thick at 20.98 m BGS seam of silty clay 3 mm thick at 21.06 m BGS seam of very fine sand 0.05 m thick at 21.62 m BGS	358.80	18	CC	n/a	53" 88%		
80	21	seam of silty clay 4 mm thick at 23.14 m BGS odour becoming less strong at 23.37 m BGS very wet from 23.14 to 23.37 m BGS	19.41	19	CC	n/a	49" 82%		
85	22	seam of very fine sand and silt 0.10 m thick at 23.93 m BGS seam of very fine sand and silt 0.03 m thick at 24.05 m BGS seam of very fine sand 0.18 m thick at 24.08 m BGS medium sand beginning at 24.38 m BGS		20	CC	n/a	57" 95%		
	26		358.80						

Screen Interval: 46.63 - 49.68 m BGS
 Sand Pack Interval: 45.36 - 50.22 m BGS
 Well Seal Interval: 0.91 - 45.36 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTCC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 2 of 4

Monitoring Well: WT-EBS-OW6A-09

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
Date started/completed: Jan-2-2009 / Jan-3-2009
Ground surface elevation: 378.21 m AMSL
Top of casing elevation: 378.96 m AMSL
Easting: 533190.802
Northing: 4809730.08

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
27		SAND fine grained, brown, moist seam of soft clayey silt 4 mm thick at 26.67 m BGS seam of very fine sand 0.15 m thick at 26.82 m BGS	19.41	21	CC	n/a	57" 95%		
28		black banding from 28.04 to 28.19 m BGS							
29		seam of very fine sand 0.51 m thick at 28.96 m BGS		22	CC	n/a	50" 83%		
30		SILTY CLAY AND FINE SAND brown, mottled, moist	348.74 29.47						
31		SAND fine to medium grained, brown, moist to wet	347.68 30.53	23	CC	n/a	55" 92%		
32				24	CC	n/a	57" 95%		
33		black banding 1-3 mm thick between 33.02 to 33.10 m BGS		25	CC	n/a	57" 95%		
34		black banding 1-3 mm thick between 33.35 to 33.45 m BGS							
35		black banding 1-3 mm thick between 35.05 to 35.36 m BGS		26	CC	n/a	49" 82%		
36		black banding 1-3 mm thick between 35.81 to 36.00 m BGS							
37		odour beginning at 37.09 m BGS seam of silty clay and very fine sand 0.05 m thick at 37.57 m BGS		27	CC	n/a	57" 95%		
38				28	CC	n/a	57" 92%		
39				29	CC	n/a	58" 97%		
40			347.68						

Screen Interval: 46.63 - 49.68 m BGS
 Sand Pack Interval: 45.36 - 50.22 m BGS
 Well Seal Interval: 0.91 - 45.36 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

Drawn By/Checked By: OR/KM

n/a - not available/applicable



Stantec

Sheet 3 of 4

Monitoring Well: WT-EBS-OW6A-09

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Jan-2-2009 / Jan-3-2009
 Ground surface elevation: 378.21 m AMSL
 Top of casing elevation: 378.96 m AMSL
 Easting: 533190.802
 Northing: 4809730.08

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth (ft) (m)	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
135 41		SAND fine to medium grained, brown, moist to wet	30.53	30	CC	n/a	57" 98%		
		seam of very fine sand 0.23 m thick at 41.43 m BGS							
140 42		seam of mottled light brown and brown fine sand 0.10 m thick at 42.21 m BGS		31	CC	n/a	58" 97%		Top of holeplug (41.81 m BGS)
		very fine sand beginning at 42.44 m BGS							
145 43		seam of mottled grey and brown fine sand 0.48 m thick at 42.70 m BGS							Holeplug
		black coloured fine sand seams from 43.18 to 43.87 m BGS		32	CC	n/a	58" 100%		
150 44		seam of medium sand 0.08 m thick at 43.87 m BGS							
		fine sand beginning at 43.94 m BGS							
155 45		black coloured fine sand seams 1-3 mm thick from 44.20 to 44.27 m BGS							Top of sand (45.36 m BGS)
		grey and brown mottling from 44.35 to 44.65 m BGS		33	CC	n/a	18" 30%		
160 46		seam of very fine sand with black seams from 44.65 to 46.18 m BGS							
		very wet at 46.17 m BGS							
165 47		seams of black colour 1-3 mm thick from 46.17 to 46.89 m BGS							Top of screen (46.63 m BGS)
		becoming brownish grey at 46.34 m BGS		34	CC	n/a	52" 83%		No.1 Silica Sand
170 48		fragments of silt and sand 0.03-0.05 m long and 1-2 mm thick between 48.08 to 48.56 m BGS							No.10 Slot PVC screen 50 mm diameter
		seam of mottled soft grey clay 0.10 m thick at 48.56 m BGS		35	CC	n/a	58" 100%		
175 49		seams of black colouring 1-3 mm thick from 49.25 to 49.79 m BGS							Bottom of screen (49.68 m BGS)
				36	CC	n/a	62" 100%		Sand
180 50		SILTY CLAY TILL	328.15						
		trace fine gravel, trace coarse sand, brownish grey, very stiff, moist	50.06	37	CC	n/a	60" 100%		
185 51									
190 52									
195 53									
200 54									
		End of Borehole	52.35						

Screen Interval: 46.63 - 49.68 m BGS
 Sand Pack Interval: 45.36 - 50.22 m BGS
 Well Seal Interval: 0.91 - 45.36 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTCC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

Drawn By/Checked By: OR/KM

n/a - not available/applicable



Stantec

Sheet 4 of 4

Monitoring Well: WT-EBS-OW6B-09

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
 Date started/completed: Jan-2-2009
 Ground surface elevation: 378.15 m AMSL
 Top of casing elevation: 379.01 m AMSL
 Easting: 533190.626
 Northing: 4809733.161

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
0	0	Ground Surface	378.15						Stick up=0.86 m Blue steel protective casing
		For Lithological Description see WT-EBS-OW6A-08	0.00	1	SS	2-2-2-2 (4)	3" 13%		Concrete
	1			2	SS	1-2-2-2 (4)	16" 67%		
5	2			3	SS	1-3-3-3 (6)	18" 75%		
				4	SS	1-2-3-3 (5)	16" 67%		
10	3			5	SS	n/a	36" 95%		
	4			6	SS	n/a	45" 75%		PVC Sch80 50 mm diameter
15	5			7	CC	n/a	37" 61%		Bentonite Grout
20	6			8	CC	n/a	42" 71%		
	7			9	CC	n/a	40" 67%		
25	8			10	CC	n/a	53" 88%		
30	9			11	CC	n/a	57" 95%		
	10								
35	11								
	12								
40			378.15						

Screen Interval: 35.05 - 38.10 m BGS
 Sand Pack Interval: 33.48 - 38.79 m BGS
 Well Seal Interval: 0.91 - 33.48 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTCC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Monitoring Well: WT-EBS-OW6B-09

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
 Date started/completed: Jan-2-2009
 Ground surface elevation: 378.15 m AMSL
 Top of casing elevation: 379.01 m AMSL
 Easting: 533190.626
 Northing: 4809733.161

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)		For Lithological Description see WT-EBS-OW6A-08	0.00						
45	14			12	CC	n/a	42" 70%		
50	15			13	CC	n/a	60" 100%		
55	16			14	CC	n/a	61" 100%		
60	17			15	CC	n/a	45" 76%		Bentonite Grout
65	18			16	CC	n/a	53" 88%		
70	19			17	CC	n/a	57" 95%		
75	20			18	CC	n/a	53" 88%		
80	21			19	CC	n/a	49" 82%		
85	22			20	CC	n/a	57" 95%		
			378.15						

Screen Interval: 35.05 - 38.10 m BGS
 Sand Pack Interval: 33.48 - 38.79 m BGS
 Well Seal Interval: 0.91 - 33.48 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 2 of 3

Monitoring Well: WT-EBS-OW6B-09

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
Date started/completed: Jan-2-2009
Ground surface elevation: 378.15 m AMSL
Top of casing elevation: 379.01 m AMSL
Easting: 533190.626
Northing: 4809733.161

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
27		For Lithological Description see WT-EBS-OW6A-08	0.00	21	CC	n/a	57" 95%		
28				22	CC	n/a	50" 83%		
29				23	CC	n/a	55" 92%		Top of holeplug (30.30 m BGS)
30				24	CC	n/a	57" 95%		Holeplug
31				25	CC	n/a	57" 95%		Top of sand (33.48 m BGS)
32				26	CC	n/a	49" 82%		Top of screen (35.05 m BGS)
33				27	CC	n/a	57" 95%		No.1 Silica Sand
34				28	CC	n/a	57" 92%		No.10 Slot PVC screen 50 mm diameter
35									Bottom of screen (38.1 m BGS)
36									Sand
37									
38									
39		End of Borehole	38.79						
40									

Screen Interval: 35.05 - 38.10 m BGS
 Sand Pack Interval: 33.48 - 38.79 m BGS
 Well Seal Interval: 0.91 - 33.48 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 3 of 3

6502371
WT-EB-OW6-57-A

WFL-57

WFL-57

Address Waterloo, Ontario

Date Drilling started October 9, 1957 Date Test Hole Completed October 9, 1957

Total depth to bottom of Well121'..... Diameter Test Hole

Water stands when not pumping feet inches from the surface of the ground

$$\begin{array}{r} 1220 \\ 105 \\ \hline 1115 \end{array}$$

B. S. Abbott

Driller.

WELL OBJECT ID 9201415 MOE NUMBER REGION ID WT-EL-OW322A-02 CONSULTANT ID OW322A-02 MUNICIPALITY CODE WT-EB-OW322-02-A

COUNTY WATERLOO TOWNSHIP/BOROUGH/CITY/TOWN/VILLAGE CON LOT NUMBER LOT LETTER
OWNER'S SURNAME RMOW FIRST NAME MIDDLE NAME LOCATION OF WELL DATE COMPLETED

ZONE 17 UTM EASTING 533528.91 UTM NORTHING 4809674.14 GND.ELEVATION 397.36 UTM RELIABILITY < 3 M MARGIN OF ERROR; MEASURED FROM MAPPED FEATURES (I.E. ROAD INTERSECTIONS; BUILDINGS; RAILWAYS; LOT LINES, ETC) OR GPS TECHNOLOGY ELEVATION RELIABILITY INSTRUMENT LEVEL ACCURATE TO 0.3 M (1')

LOG OF OVERBURDEN AND BEDROCK MATERIALS

LAYER #	COLOUR	PRIME MATERIAL	OTHER MATERIAL 1	OTHER MATERIAL 2	BOTTOM_DEPTH
1	BROWN	SAND	SILT	TOPSOIL	0.31
2	GREY	SILT	CLAY	GRAVEL	7.32
3	BROWN	SAND	SILT	NA	9.45
4	GREY	SAND	CLAY	SILT	12.19
5	GREY	SILT	CLAY	SAND	17.07
6	GREY	SAND	GRAVEL	SILT	19.51
7	GREY	SAND	SILT	GRAVEL	38.41
8	GREY	SILT	CLAY	SAND	48.16
9	BROWN	SAND	SILT	NA	68.28
10	GREY	SILT	NA	NA	74.37
11	GREY	SILT	CLAY	GRAVEL	74.68

☒ DETAILED LITHOLOGY DATA IS AVAILABLE IF THIS BOX IS CHECKED

WATER RECORD

CASING AND OPEN HOLE RECORD

ID	DIAMETER	MATERIAL	DEPTH TO	TOC ELEV.	PIPE HT.
A	51	PVC	65.23	398.18	0.82
B					

SCREEN RECORD

ID	SLOT	DIAMETER	DEPTH FROM	DEPTH TO
A	10	51	65.23	68.28
B			53.34	56.39

PLUGGING AND SEALING RECORD

ID	DEPTH FROM	DEPTH TO	PLUG MATERIAL
A	68.73	74.68	BENTONITE
B	63.7	68.73	SAND PACK
C	62	63.7	BENTONITE
D	0.6	62	BENTONITE GROUT
E	0	0.6	CEMENT

PUMPING TEST

WELL OBJECT ID	MOE NUMBER	REGION ID	CONSULTANT ID	MUNICIPALITY CODE	
9201416		WT-EL-OW332-02	OW332-02		
COUNTY	TOWNSHIP/BOROUGH/CITY/TOWN/VILLAGE		CON	LOT NUMBER	LOT LETTER
WATERLOO					
OWNER'S SURNAME	FIRST NAME	MIDDLE NAME	LOCATION OF WELL	DATE COMPLETED	
RMOW					
ZONE	UTM EASTING	UTM NORTHING	GND.ELEVATION	UTM RELIABILITY	ELEVATION RELIABILITY
17	533411.997	4809820.512	392.79	< 3 M MARGIN OF ERROR; MEASURED FROM MAPPED FEATURES (I.E. ROAD INTERSECTIONS; BUILDINGS; RAILWAYS; LOT LINES, ETC) OR GPS TECHNOLOGY	INSTRUMENT LEVEL ACCURATE TO 0.3 M (1')

LOG OF OVERBURDEN AND BEDROCK MATERIALS

LAYER #	COLOUR	PRIME MATERIAL	OTHER MATERIAL 1	OTHER MATERIAL 2	BOTTOM_DEPTH
1	BROWN	SAND	SILT	TOPSOIL	0.61
2	GREY	CLAY	SILT	TILL	4.57
3	BROWN	SAND	CLAY	SILT	8.53
4	GREY	SILT	CLAY	SAND	10.06
5	BROWN	SAND	SILT	CLAY	32
6	BROWN	SILT	CLAY	NA	42.67
7	GREY	SAND	SILT	CLAY	56.39

☒ DETAILED LITHOLOGY DATA IS AVAILABLE IF THIS BOX IS CHECKED

WATER RECORD

CASING AND OPEN HOLE RECORD

ID	DIAMETER	MATERIAL	DEPTH TO	TOC ELEV.	PIPE HT.
A	51	PVC	49.07	393.68	0.89

SCREEN RECORD

ID	SLOT	DIAMETER	DEPTH FROM	DEPTH TO
A	10	51	49.07	52.12

PLUGGING AND SEALING RECORD

ID	DEPTH FROM	DEPTH TO	PLUG MATERIAL
A	53.34	56.39	DRILL CUTTINGS
B	47.85	53.34	SAND PACK
C	46.3	47.85	BENTONITE
D	0.6	46.3	BENTONITE GROUP
E	0	0.6	CEMENT

PUMPING TEST

FINAL STATUS OF WELL
OBSERVATION

WATER USE

First Use:

Second Use:

METHOD OF CONSTRUCTION

NAME OF WELL CONTRACTOR WELL CONTRACTOR'S LICENSE

CONTRACTOR ADDRESS

SUBMISSION DATE

☐ WELL HAS BEEN ABANDONNED/DESTROYED IF THIS BOX IS CHECKED

W. of N. expansion

WT-EB-OW322-02-A



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

PROJECT NUMBER: 823-02

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

LOCATION: AS PER PLAN

HOLE DESIGNATION: OW322A-02

DATE COMPLETED: 15 July 2002

DRILLING METHOD: ROTASONIC

FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (m)	N' VALUE
	TOP OF RISER GROUND SURFACE	398.11 397.29					
1	SILTY SAND (TOPSOIL), loose, fine grained, poorly graded, dark brown, moist, vegetative matter (grass, rootlets)	396.98	CONCRETE SEAL				
2	ML/CL - CLAYEY SILT (TILL), trace gravel, firm, grey/brown, dry						
3							
4	- moist at 3.66m BGS						
5	- silty clay, stiff, grey at 4.27m BGS						
6							
7							
8	SM - SILTY SAND, dense, slightly cohesive, medium grained, well graded, brown, moist to wet	389.97	51 mm Ø SCH 80 PVC RISER PIPE				
9							
10	SC - CLAYEY SAND, with silt, trace gravel, dense, moderately cohesive, fine grained, well graded, grey, moist	387.84	BENTONITE GROUT				
11							
12	ML/CL - CLAYEY SILT (TILL), with sand, trace to with gravel, stiff, grey, moist	385.10	152 mm Ø BOREHOLE				
13							
14							
15							
16	- light brown at 15.85m BGS						
17	- sandy, very moist at 16.46m BGS						
18	SP - SAND, with gravel, trace silt, dense, slightly cohesive, medium grained, poorly graded, grey/brown, moist	380.22					
19	- fine grained at 17.98m BGS						
	SM - SILTY SAND, trace gravel, dense, moderately	377.78					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 000823-2002 GPJ CRA CORP GDT 14/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 4

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW322A-02
DATE COMPLETED: 15 July 2002
DRILLING METHOD: ROTASONIC
FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (m)	N' VALUE
41							
42							
43							
44							
45							
46							
47							
48	- sandy at 47.55m BGS						
49	SP - SAND, with silt, dense, slightly cohesive, medium grained, poorly graded, brown, moist to very moist	349.13					
50							
51							
52	- trace silt, coarse grained at 52.43m BGS						
53							
54							
55	- interbedded silt and clay layers. 1cm thick at 54.86m BGS						
56	- silty sand, cohesive, fine grained at 56.39m BGS						
57							
58	- wet at 57.91m BGS						
59							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 000823-2002.GPJ CRA CORP.GDT 1/4/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 3

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW332-02
DATE COMPLETED: 8 August 2002
DRILLING METHOD: ROTOSONIC
FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (m)	'N' VALUE
	TOP OF RISER GROUND SURFACE	393.59 392.70					
	SILTY SAND (TOPSOIL), loose, fine grained, poorly graded, dark brown, moist, vegetative matter (grass, rootlets) ML/CL - SILTY CLAY (TILL), trace gravel, stiff, grey, moist	392.09	CONCRETE SEAL				
2							
4							
	SC - CLAYEY SAND, trace silt, soft, brown/grey, wet	388.13					
6			51 mm SCH 80 PVC RISER PIPE				
8							
	ML/CL - CLAYEY SILT (TILL), trace sand, trace gravel, grey, moist	384.17	BENTONITE GROUT				
10							
	SP - SAND, trace silt, trace clay, dense, fine grained, poorly graded, light brown, dry	382.64					
12	- with silt, grey, moist at 11.58m BGS - heavy oxidation at 12.50m BGS - silty sand, wet at 13.11m BGS		152 mm Ø BOREHOLE				
14							
16	- very hard, dry at 15.85m BGS						
18	- trace silt, trace gravel, light grey/beige at 17.68m BGS						
20							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG D00823-2002.GPJ CRA_CORP.GDT 1/4/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 2 of 3

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW332-02
DATE COMPLETED: 8 August 2002
DRILLING METHOD: ROTOSONIC
FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
22								
24								
26								
28								
30	- silty, dense, brown, moist to very moist at 29.57m BGS - wet at 30.48m BGS		51 mm SCH 80 PVC RISER PIPE BENTONITE GROUT 152 mm Ø BOREHOLE					
32	ML - SILT (WATERLAID), with clay, firm, brown, wet	360.70						
34	- brown/grey, moist at 33.53m BGS							
36								
38	- light grey, dry at 38.10m BGS							
40	- with fine grained sand, trace clay at 39.62m BGS							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 000823-2002.GPJ CRA CORP.GDT 1/4/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 3

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW332-02
DATE COMPLETED: 8 August 2002
DRILLING METHOD: ROTASONIC
FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (m)	'N' VALUE
44	SM/ML - SILTY SAND, trace clay, dense, medium grained, poorly graded, light grey, wet	350.03	152 mm Ø BOREHOLE				
46			BENTONITE HOLEPLUG				
48			SAND PACK				
50			WELL SCREEN				
52	- moist at 51.82m BGS						
54	- wet at 54.86m BGS		HEAVED SAND				
56	END OF BOREHOLE @ 56.39m BGS	336.31					
58							
60							
62							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 000823-2002.GPJ CRA CORP.GDT 1/4/04

obj.# 9205772 = W-OW-OW358A-08
 9205773 = W-EL-OW358B-08

W-EL-OW358A-08-A



STRATIGRAPHIC AND INSTRUMENTATION LOG (BEDROCK)

Page 1 of 4

PROJECT NAME: WATERLOO LANDFILL SITE
 PROJECT NUMBER: 823-02
 CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
 LOCATION: AS PER PLAN
 DRILLING SUBCONTRACTOR: ALL-TERRAIN DRILLING

HOLE DESIGNATION: OW358A-08
 DATE COMPLETED: December 9, 2008
 DRILLING METHOD: PQ CORING (WET)
 FIELD PERSONNEL: J. LEADER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITORING WELL	RUN NUMBER	CORE RECOVERY %	RQD %
1	TOPSOIL - silt loam, dark brown, frozen; rootlets ML - SANDY SILT, firm, slight plasticity, damp SM - SILTY SAND, compact, dense, fine grained, brown, damp, horizontally stratified	0.10 0.21	CONCRETE			
2						
3	- silt with sand, firm, fine grained from 2.74 to 3.00m BGS	3.15				
4	- silt and sand, dense, fine to med. grained, horizontally stratified, slight plasticity, damp from 3.00 to 3.15m BGS					
5	ML - SILT, trace clay, stiff, slight plasticity, brown, damp, massive	4.44				
6	- silt with sand, fine grained, brown, damp from 4.56 to 4.60m BGS					
7	SP/SM - SAND, trace silt, compact/dense, fine grained, brown, dry to damp, horizontally stratified		BENTONITE GROUT			
8	- silt and sand, fine grained, brown, damp from 4.72 to 4.80m BGS					
9	- SW - sand, compact, fine to medium grained, stratified, becoming finer grained with depth from 4.80 to 12.85m BGS					
10	- trace silt from 5.94 to 6.40m BGS					
11	- with silt from 6.40 to 6.71m BGS					
12	- trace silt from 6.45 to 6.65m BGS					
13	ML/SM - SANDY SILT, firm/compact, brown, dry/damp, horizontally stratified; occasional thin sand seams and thin silt seams	12.85				
14	GP/GM - GRAVELLY SAND, with to trace silt, compact, fine to coarse gravel, subrounded	13.54 13.79				
15	SP/SM - SAND, trace silt, compact, fine to medium grained, brown, dry/damp; occasionally with silt					
16	- silty sand with gravel, both fine grained from 14.45 to 14.50m BGS					
17	- sand and gravel, trace silt, fine to coarse sand, fine gravel from 14.96 to 15.06m BGS					
18	- silty sand, trace gravel from 15.06 to 15.19m BGS					
19	- sand, medium grained, trace fine grained, occasional thin silty seams and fine sand seams from 15.19 to 17.81m BGS					
	- black streak, no odour at 17.73m BGS					
	- sand, trace silt, fine grained, trace medium grained at 17.83m BGS					
	- silty sand, fine grained from 19.40 to 19.43m BGS					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE



STRATIGRAPHIC AND INSTRUMENTATION LOG (BEDROCK)

Page 2 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW358A-08

PROJECT NUMBER: 823-02

DATE COMPLETED: December 9, 2008

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING (WET)

LOCATION: AS PER PLAN

FIELD PERSONNEL: J. LEADER

DRILLING SUBCONTRACTOR: ALL-TERRAIN DRILLING

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITORING WELL	RUN NUMBER	CORE RECOVERY %	RQD %
21	- sand, medium grained, trace fine grained from 20.37 to 20.57m BGS - silty sand, fine grained from 20.57 to 20.73m BGS					
22	- sand, fine to medium grained from 20.73 to 20.83m BGS - silty sand, fine grained from 20.83 to 20.96m BGS					
23	- sand, fine to medium grained from 20.96 to 23.39m BGS					
24	- sand, fine to medium grained, trace coarse sand from 23.39 to 24.31m BGS					
25	- sand, medium to coarse grained, trace fine grained, trace gravel from 24.31 to 25.07m BGS					
26	- sand with to trace silt, fine grained from 25.07 to 27.56m BGS					
27						
28	- silty sand, fine grained from 27.56 to 28.12m BGS					
29	- sand, trace silt, fine to medium grained from 28.12 to 28.29m BGS					
30	- sand, medium grained, trace fine grained from 28.29 to 28.73m BGS - sand, trace gravel, medium to coarse sand, fine gravel from 28.73 to 29.51m BGS					
31						
32						
33	- silty sand, fine grained from 33.25 to 34.34m BGS					
34						
35	- silt and sand, firm/dense, fine grained from 34.34 to 35.05m BGS - silty sand, fine grained from 35.05 to 37.16m BGS					
36						
37		37.16				
38	SM/ML - SILTY SAND to SILT with SAND, alternating beds 10 to 30 cm thick; stratified, brown, dry/damp					
39						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

BEDROCK LOG 823-02 (2008) GPJ CRA CORP GDT 6/24/09



STRATIGRAPHIC AND INSTRUMENTATION LOG (BEDROCK)

Page 3 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW358A-08

PROJECT NUMBER: 823-02

DATE COMPLETED: December 9, 2008

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING (WET)

LOCATION: AS PER PLAN

FIELD PERSONNEL: J. LEADER

DRILLING SUBCONTRACTOR: ALL-TERRAIN DRILLING

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITORING WELL	RUN NUMBER	CORE RECOVERY %	RQD %
41						
42						
43						
44	- silt, firm from 44.17 to 44.24m BGS	44.17				
45	SM/SP - SILT AND SAND, firm to stiff/compact to dense, fine grained, brown, dry/damp; varying consistencies of silt and sand					
46	- sand, trace silt, stratified from 45.46 to 46.20m BGS					
47	- sand, trace silt, fine to medium grained from 46.94 to 47.24m BGS	47.55				
48	ML - SILT, trace sand, firm to stiff, massive, fine grained sand, brown, damp					
49						
50	- silt and sand, firm to stiff, fine grained from 49.58 to 50.01m BGS					
51	- silt at 50.01m BGS	51.36				
52	SM/SP - SILT AND SAND, firm to stiff/compact to dense, fine grained, brown, dry/damp; varying consistencies					
53	- sand, trace silt, fine to medium grained, stratified at 52.58m BGS					
54						
55						
56						
57						
58		58.29				
59	ML - SILT, trace clay, very stiff, massive, brown, damp, slight plasticity					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

BEDROCK LOG 823-02 (2008) GPJ CRA CORP.GDT 6/24/09



STRATIGRAPHIC AND INSTRUMENTATION LOG (BEDROCK)

Page 4 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW358A-08

PROJECT NUMBER: 823-02

DATE COMPLETED: December 9, 2008

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO


DRILLING METHOD: PQ CORING (WET)

LOCATION: AS PER PLAN

FIELD PERSONNEL: J. LEADER

DRILLING SUBCONTRACTOR: ALL-TERRAIN DRILLING

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITORING WELL	RUN NUMBER	CORE RECOVERY %	RQD %
61	- silt and sand, firm to stiff/compact to dense, fine grained from 60.25 to 60.63m BGS					
62	- silt and sand, firm to stiff/compact to dense, fine grained from 61.65 to 61.95m BGS					
63	- silt and sand, firm to stiff/compact to dense, fine grained from 62.10 to 62.76m BGS					
64	- silt and sand, firm to stiff/compact to dense, fine grained from 64.03 to 64.41m BGS	64.64				
65	ML/CI - SILT with CLAY (MARYHILL TILL), trace gravel, very dense, moderate plasticity, brown, damp					
66	END OF BOREHOLE @ 66.14m BGS	66.14				
67						
68						
69						
70						
71						
72						
73						
74						
75						
76						
77						
78						
79						



WELL DETAILS
Screened interval:
55.47 to 58.52m BGS
Length: 3.05m
Diameter: 51mm
Slot Size: 8
Material: STAINLESS STEEL
Seal:
51.51 to 52.43m BGS
Material: 3/8" BENTONITE GRAVEL
Sand Pack:
52.43 to 58.83m BGS
Material: #1 SILICA SAND
Seal:
58.83 to 66.14m BGS
Material: 3/8" BENTONITE GRAVEL

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

BEDROCK LOG 823-02 (2008).GPJ CRA_CORP.GDT 6/24/09

Obj # 9205774 = W-EL-OW359A-08

9205775 = W-EL-OW359A-08

W-EL-OW359A-08-A



STRATIGRAPHIC AND INSTRUMENTATION LOG (BEDROCK)

Page 1 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW359A-08

PROJECT NUMBER: 823-02

DATE COMPLETED: November 19, 2008

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING (WET)

LOCATION: AS PER PLAN

FIELD PERSONNEL: J. LEADER

DRILLING SUBCONTRACTOR: ALL-TERRAIN DRILLING

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITORING WELL	RUN NUMBER	CORE RECOVERY %	RQD %
1	TOPSOIL - silt loam, trace sand, trace gravel, soft, dark brown, damp to moist; rootlets and worms	0.15	CONCRETE			
2	FILL - sand with silt, compact, fine grained, brown, dry to damp					
3	- sandy silt, trace gravel, compact, fine grained, dark brown, dry to damp; rootlets, piece of rope at 1.17m BGS					
4	- 2.5 cm piece of red brick at 1.27m BGS					
5	- cobble encountered, subrounded at 1.35m BGS					
6	- silt, trace sand, trace gravel, trace clay, dense, low plasticity, dark brown, dry to damp; rootlets at 1.40m BGS					
7	- sand with silt, trace gravel, compact, fine grained, tan, dry to damp; iron staining; occasional thin silt lenses at 1.57m BGS					
8	- cobble, granit from 3.40 to 3.48m BGS					
9	- plastic encountered at 3.55m BGS					
10	- wood, root inclusions from 4.34 to 5.49m BGS					
11	- high density plastic and a cobble encountered at 4.37m BGS					
12	- silt, trace sand, trace gravel; occasional rootlets at 4.42m BGS					
13	- plastic encountered at 6.88m BGS					
14	- wood debris and rootlets at 8.03m BGS	8.31				
15	- sand, trace gravel, fine grained sand at 8.13m BGS					
16	- GW - SAND AND GRAVEL, trace silt, compact to dense, coarse grained gravel, subrounded, brown, fine to medium sand, brown, damp; trace coarse grained sand	9.30				
17	- GW - SAND AND GRAVEL, with cobbles, trace silt, compact to dense, subrounded, fine to coarse grained, brown, damp; sand is becoming coarser with depth					
18	- SM to ML - SAND, with silt, compact, fine to medium grained, dry to damp, horizontally stratified from 12.97 to 13.37m BGS	12.88				
19	- ML - SILT, trace gravel, very stiff, subrounded, fine to coarse grained, brown, dry to damp; horizontally stratified					
20	- ML to SM - SILT, with sand, trace gravel, stiff from 13.49 to 14.10m BGS					
21	- ML to SM - SILT, with sand, trace gravel, stiff from 14.10 to 14.27m BGS					
22	- GP - GRAVELLY SAND, trace silt, trace cobbles, dense, fine sand, fine to coarse gravel, subrounded, brown, dry from 14.27 to 14.73m BGS					
23	- GP - SILTY SAND, trace gravel, compact to dense, fine grained gravel, fine grained sand, subrounded, brown, dry to damp from 14.73 to 16.92m BGS					
24	- SM/ML/GP - SILTY SAND, with gravel, fine to coarse grained, damp from 16.92 to 17.73m BGS					
25	- GM - SAND AND GRAVEL, trace silt, trace cobbles, compact to dense, fine to coarse grained					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

BEDROCK LOG 823-02 (2008) GPJ CRA CORP GDT 6/24/09



STRATIGRAPHIC AND INSTRUMENTATION LOG (BEDROCK)

Page 2 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW359A-08

PROJECT NUMBER: 823-02

DATE COMPLETED: November 19, 2008

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING (WET)

LOCATION: AS PER PLAN

FIELD PERSONNEL: J. LEADER

DRILLING SUBCONTRACTOR: ALL-TERRAIN DRILLING

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITORING WELL	RUN NUMBER	CORE RECOVERY %	RQD %
21	brown from 17.73 to 18.92m BGS - ML - SILT, trace sand, stiff, moderate plasticity, brown, damp from 18.92 to 19.05m BGS - SM/ML - SAND, with silt, trace gravel, compact, brown; occasional cobble from 19.05 to 19.71m BGS					
22	- ML - SILT, trace sand, trace gravel, stiff, fine grained, brown, damp; no structure apparent from 19.71 to 20.12m BGS					
23	- GM - SAND AND GRAVEL, with silt, compact, brown, occasional cobbles from 20.12 to 20.27m BGS					
24	- SM/ML - SAND AND SILT, compact to firm, fine to medium grained, brown; no structure from 20.27 to 21.64m BGS					
25	- SM/ML - SAND, with silt, compact, fine to medium grained, occasional sand and silt lenses; horizontally stratified with black banding from 21.64 to 23.37m BGS					
26	- SM/ML - SILT AND SAND, firm to compact, brown, damp; horizontal deposition; alternating silt/sand from 23.37 to 26.29m BGS					
27	- ML/SM - SILT, with sand, firm to stiff, fine grained, brown, damp; iron oxide staining (discolouration) at base of contact with lower unit from 26.29 to 26.82m BGS	26.82				
28	- sand, medium grained from 26.57 to 26.62m BGS					
29	- silty sand from 26.87 to 26.97m BGS					
30	- sandy silt, trace coarse sand, trace fine gravel from 26.97 to 27.48m BGS					
31	SP - SAND, compact, poorly graded/well sorted, medium grained, greyish, inferred to be wet					
32	- medium to coarse sand seam from 28.70 to 28.73m BGS					
33	- medium to coarse grained sand seam from 29.54 to 29.57m BGS					
34	- fine to medium grained sand from 30.58 to 34.11m BGS					
35	- SM - SILT, with sand, fine grained, firm, stratified from 34.11 to 34.20m BGS					
36	- medium grained sand, trace fine gravel from 34.20 to 34.90m BGS					
37	- fine to medium sand, stratified from 34.90 to 35.36m BGS					
38	- medium sand, trace coarse sand, stratified from 35.36 to 35.51m BGS					
39	- fine to medium grained sand, stratified from 35.51 to 36.27m BGS					
	- medium grained sand, trace fine from 36.27 to 39.17m BGS					
	- medium to coarse sand, trace fine gravel from 39.17 to 39.52m BGS					
	- sand and gravel seam, coarse sand, fine gravel					

BENTONITE
GROUT

2" Ø SCH 80
PVC RISER
PIPE

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE



STRATIGRAPHIC AND INSTRUMENTATION LOG (BEDROCK)

Page 3 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW359A-08

PROJECT NUMBER: 823-02

DATE COMPLETED: November 19, 2008

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING (WET)

LOCATION: AS PER PLAN

FIELD PERSONNEL: J. LEADER

DRILLING SUBCONTRACTOR: ALL-TERRAIN DRILLING

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITORING WELL	RUN NUMBER	CORE RECOVERY %	RQD %
41	from 39.24 to 39.27m BGS - ML - SANDY SILT, firm fine grained, stratified, brown from 39.52 to 39.80m BGS - ML/SM - SILT AND SAND, compact, brown from 39.80 to 41.50m BGS					
42	- SP - medium grained sand, trace fine gravel, trace fine and coarse sand from 41.50 to 44.14m BGS - seam of firm silt from 41.73 to 41.81m BGS					
43						
44	- SM - SILTY SAND, compact/firm, fine grained, brown, horizontally stratified from 44.14 to 45.82m BGS					
45						
46	- silty sand, fine to medium grained from 45.82 to 46.05m BGS					
47	- SP - SAND, trace gravel, compact, well graded, fine to coarse sand, fine gravel, grey from 46.05 to 46.18m BGS					
48	- SM - SAND, with silt, compact, fine to med. grained from 46.18 to 46.38m BGS - cobble, subrounded at 46.20m BGS					
49	- GM - SAND, with gravel, trace silt, fine to coarse sand from 46.38 to 47.22m BGS - no recovery (suspect washed out) from 48.56 to 48.56m BGS					
50	- gravel and cobbles from 48.59 to 48.69m BGS					
51	- sand, trace silt, fine grained sand, trace med. sand, increasing grain size with depth from 48.69 to 49.25m BGS					
52	- SILT, trace clay, firm, mod. plast., brown, damp from 49.25 to 49.30m BGS					
53	- SP - SAND, trace silt, fine grained, trace medium grained from 49.30 to 50.47m BGS - SILT, trace clay, firm, mod. plasticity, brown, damp from 50.47 to 50.54m BGS					
54	- SP - SAND, trace silt, fine to medium sand, brownish from 50.54 to 51.18m BGS					
55	- SM/ML - SILTY SAND, compact, fine grained, horizontally stratified, brown from 51.18 to 52.12m BGS					
56	- SP - SAND, compact, medium grained, trace fine, brown from 52.12 to 54.18m BGS - seam of coarse gravel from 54.18 to 54.20m BGS					
57	- GW - SAND, with gravel, subrounded, fine to coarse grained sand, fine gravel, grey from 54.69 to 55.78m BGS					
58	- SM/ML - SAND, with silt, compact, horizontally stratified, fine grained, grey from 55.78 to 58.62m BGS - seam of silt, trace clay, firm, mod. plasticity, brownish grey, damp from 56.49 to 56.52m BGS					
59	- seam of silt, trace clay, firm, mod. plasticity, brownish grey, damp from 58.01 to 58.09m BGS - SM/ML - SILT AND SAND, compact/firm, mod. plasticity, rapid dilatancy, fine grained, brownish					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

BEDROCK LOG 823-02 (2008) GPJ CRA CORP GDT 6/24/09



STRATIGRAPHIC AND INSTRUMENTATION LOG (BEDROCK)

Page 4 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

PROJECT NUMBER: 823-02

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

LOCATION: AS PER PLAN

DRILLING SUBCONTRACTOR: ALL-TERRAIN DRILLING

HOLE DESIGNATION: OW359A-08

DATE COMPLETED: November 19, 2008

DRILLING METHOD: PQ CORING (WET)

FIELD PERSONNEL: J. LEADER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	DEPTH m BGS	MONITORING WELL	RUN NUMBER	CORE RECOVERY %	RQD %
61	grey from 58.62 to 59.72m BGS - SM to SP - SAND, trace SILT, compact, fine to medium grained from 59.61 to 59.66m BGS - SP - SAND, compact, medium grained, trace fine grained, grey from 59.72 to 60.17m BGS - ML/SM - SILT SAND, compact/fimr, rapid dilatency, mod. plasticity, fine grained, grey, stratified from 60.17 to 61.87m BGS - SM - SAND, with silt, compact, fine grained, stratified from 61.87 to 62.33m BGS - ML/SM - SAND AND SILT, compact, fine grained, stratified from 62.33 to 63.58m BGS - silt and sand from 63.58 to 64.08m BGS - sand, fine to medium grained from 64.08 to 64.16m BGS					
62						
63						
64						
65						
66						
67						
68						
69						
70	- trace gravel, trace silt, fine to coarse, stratified, grey, saturated at 70.10m BGS					
71						
72						
73		73.46				
74	ML/CL - SILT AND CLAY (MARYHILL TILL), trace to with sand, trace to with gravel, stiff, low to mod. plasticity, grey END OF BOREHOLE @ 74.07m BGS	74.07				
75						
76						
77						
78						
79						

BEDROCK LOG 823-02 (2008) GPJ CRA CORP GDT 6/24/09

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

Monitoring Well: WT-EBS-OW1A-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R. Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Oct-24-2008
 Ground surface elevation: 389.04 m AMSL
 Top of casing elevation: 389.80 m AMSL
 Easting: 532684.989
 Northing: 4809092.453

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
0	0	Ground Surface	389.04						Stick up=0.76 m
		Not logged	0.00						Steel protective casing
1									Concrete
5									
10			386.30						
			2.74						
		SAND TILL	385.86	4	CC	n/a	21"		
		fine grained sand, trace medium to coarse sand, some fine to coarse	3.18				100%		
		gravel, brown	3.51						
		seam of silt and gravel 76 mm thick at 2.82 m BGS							
		SILT TILL		5	CC	n/a	55"		
		trace fine, medium and coarse sand, brown, hard, moist					90%		
		CLAYEY SILT TO SILTY CLAY							
		some fine sand, trace medium to coarse sand, trace fine and coarse							
		gravel, brownish grey, stiff, moist							
15									PVC Sch80 50 mm diameter
20				6	CC	n/a	54"		
		trace pockets of soft grey clay (2 mm diameter)					90%		
		alternating varved and mottled structures beginning at 6.10 m BGS							
		seams of fine sand 3 to 25 mm thick beginning at 6.17 m BGS							
25				7	CC	n/a	45"		
							75%		
30				8	CC	n/a	54"		
							90%		
35				9	CC	n/a	62"		
							102%		
40				10	CC	n/a	61"		
		trace soft, dry red clay pockets, 2 mm diameter, at 10.67 m BGS					102%		
		becoming light brown at 11.51 m BGS	377.33						
		SAND	11.71						
		fine grained, light brown, some mottled pockets of light brown silty							
		clay, moist	376.57						
		sand and soft silty clay, soft sandy silt beginning at 11.92 m BGS	12.47						
		becoming brownish grey at 12.28 m BGS							

Screen Interval: 56.08 - 59.13 m BGS
 Sand Pack Interval: 54.33 - 61.06 m BGS
 Well Seal Interval: 0.91 - 54.33 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTCC - metres below top of casing
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 1 of 5

Monitoring Well: WT-EBS-OW1A-08

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field Investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
Date started/completed: Oct-24-2008
Ground surface elevation: 389.04 m AMSL
Top of casing elevation: 389.80 m AMSL
Easting: 532684.989
Northing: 4809092.453

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
13		varved structure of fine sand, sandy silt, silty clay and clay beginning at 12.50 m BGS	376.57 12.47	11	CC	n/a	n/a		
45		SILTY CLAY little fine sand, trace medium and coarse sand, trace fine gravel, brownish grey, moist seam of light brown 8.9 cm thick at 13.18 m BGS	375.12 13.92	12	CC	n/a	18* 30%		
14		SAND AND SILT trace medium and coarse sand, light brown, moist varved structure of silty clay, sand and sandy silt beginning at 13.92 m BGS		13	CC	n/a	55* 92%		
15				14	CC	n/a	44* 73%		
50				15	CC	n/a	59* 100%		
16				16	CC	n/a	36* 62%		
55				17	CC	n/a	46* 77%		
17				18	CC	n/a	28* 46%		
18				19	CC	n/a	38* 63%		
60			370.29 18.75						
19		SAND fine grained, trace medium and coarse sand, trace coarse and fine gravel, brownish grey, moist varved soft grey clay 5-10 cm thick beginning at 18.87 m BGS, repeating every 10-20 cm							
65									
20									
21		beginning light brown at 21.01 m BGS							
70		well graded with little fine and coarse gravel (max 60 mm), subrounded at 21.56 m BGS							
22									
75									
23									
80									
24									
85									
25									
26									

Screen Interval: 56.08 - 59.13 m BGS
 Sand Pack Interval: 54.33 - 61.06 m BGS
 Well Seal Interval: 0.91 - 54.33 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTCC - metres below top of casing
 CC - continuous core sample
 n/a - not available/applicable



Stantec

Drawn By/Checked By: OR/KM

Sheet 2 of 5

Monitoring Well: WT-EBS-OW1A-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field Investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Oct-24-2008
 Ground surface elevation: 389.04 m AMSL
 Top of casing elevation: 389.80 m AMSL
 Easting: 532684.989
 Northing: 4809092.453

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth (ft) (m)	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
27		SAND fine grained, trace medium and coarse sand, trace coarse and fine gravel, brownish grey, moist	18.75	20	CC	n/a	55" 92%		Bentonite Grout
28				21	CC	n/a	56" 93%		
29				22	CC	n/a	56" 100%		
30		SAND AND GRAVEL brown, well graded, subrounded (max 75 mm), moist	359.22 29.82	23	CC	n/a	56" 93%		
31		layer of little coarse gravel from 31.04 to 31.45 m BGS		24	CC	n/a	54" 90%		
32		layer of little coarse gravel from 31.85 to 32.00 m BGS cobble at 32.05 m BGS cobble at 32.23 m BGS cobble at 32.31 m BGS		25	CC	n/a	4" 7%		
33		seam of little sand 25.4 cm thick at 32.81 m BGS	355.56 33.48	26	CC	n/a	60" 100%		
34		SAND fine grained, little coarse gravel, brown, moist		27	CC	n/a	52" 87%		
35		GRAVEL little sand (well graded), brown, wet cobble at 35.38 m BGS	353.83 35.20	28	CC	n/a	56" 95%		
36		cobble at 36.65 m BGS							
37									
38			349.29 39.75						
39		SAND medium grained, trace to some gravel, brown	349.29						

Screen Interval: 56.08 - 59.13 m BGS
 Sand Pack Interval: 54.33 - 61.06 m BGS
 Well Seal Interval: 0.91 - 54.33 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM




Stantec

Monitoring Well: WT-EBS-OW1A-08

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
Date started/completed: Oct-24-2008
Ground surface elevation: 389.04 m AMSL
Top of casing elevation: 389.80 m AMSL
Easting: 532684.989
Northing: 4809092.453

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
135 41		SAND medium grained, trace to some gravel, brown	39.75	29	CC	n/a	30" 50%		Bentonite Grout
140 42				30	CC	n/a	59" 95%		
145 43		seam of coarse gravel from 43.41 to 44.39 m BGS		31	CC	n/a	57" 95%		
145 44			344.65 44.39						
150 45		SAND AND GRAVEL well graded, brown, subrounded (max 75 mm), moist		32	CC	n/a	36" 60%		
155 46				33	CC	n/a	28" 47%		
160 47				34	CC	n/a	38" 63%		
165 48				35	CC	n/a	43" 72%		
170 49			338.55 50.48						
175 50		SAND medium grained, trace fine gravel, brown		36	CC	n/a	13" 22%		
		seam of gravel 5.1 cm thick at 51.94 m BGS		37	CC	n/a	32" 53%		
			338.55						Top of holeplug (51.69 m BGS) Holeplug

Screen Interval: 56.08 - 59.13 m BGS
Sand Pack Interval: 54.33 - 61.06 m BGS
Well Seal Interval: 0.91 - 54.33 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 4 of 5

Monitoring Well: WT-EBS-OW1A-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Oct-24-2008
 Ground surface elevation: 389.04 m AMSL
 Top of casing elevation: 389.80 m AMSL
 Easting: 532684.989
 Northing: 4809092.453

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
180 55		SAND medium grained, trace fine gravel, brown	50.48	38	CC	n/a	38" 63%		Top of sand (54.33 m BGS)
185 56		cobble at 55.68 m BGS		39	CC	n/a	45" 75%		Top of screen (56.08 m BGS)
190 57				40	CC	n/a	50" 67%		No.10 Slot PVC screen 50 mm diameter
195 58		coarse sand and trace fine gravel beginning at 58.19 m BGS		41	CC	n/a	50" 83%		Bottom of screen (59.13 m BGS)
200 59		seams of hard, brown clay till, 5-7.62 cm thick at 59.51 m BGS		42	CC	n/a	52" 87%		No.1 Silica Sand
205 60		seams of hard, brown clay till, 5-7.62 cm thick at 60.05 m BGS seams of hard, brown clay till, 5-7.62 cm thick at 60.15 m BGS seams of hard, brown clay till, 5-7.62 cm thick at 60.23 m BGS		43	CC	n/a	57" 95%		Holeplug
210 61		SAND very fine grained, some silt seam of fine sand 5 cm thick at 61.95 m BGS	327.32 61.72						
215 62		CLAY brownish grey, hard, moist	326.43 62.61	44	CC	n/a	61" 102%		
220 63		End of Borehole	324.70 64.34						

Screen Interval: 56.08 - 59.13 m BGS
 Sand Pack Interval: 54.33 - 61.06 m BGS
 Well Seal Interval: 0.91 - 54.33 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 5 of 5

Monitoring Well: WT-EBS-OW1B-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: C. Stewart
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Oct-30-2008
 Ground surface elevation: 389.20 m AMSL
 Top of casing elevation: 390.04 m AMSL
 Easting: 532682.557
 Northing: 4809090.487

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth (ft) (m)	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
0	0	Ground Surface	389.20						Stick up=0.84 m
		Refer to WT-EBS-OW1A-08 for Lithology	0.00						Steel protective casing
1									Concrete
5									
10				4	CC	n/a	21" 100%		
15				5	CC	n/a	55" 90%		
20				6	CC	n/a	54" 90%		
25				7	CC	n/a	45" 75%		
30				8	CC	n/a	54" 90%		
35				9	CC	n/a	62" 102%		
40				10	CC	n/a	61" 102%		
			389.20						PVC Sch80 50 mm diameter

Screen Interval: 44.22 - 47.27 m BGS
 Sand Pack Interval: 42.80 - 47.45 m BGS
 Well Seal Interval: 0.91 - 42.80 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Monitoring Well: WT-EBS-OW1B-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: C.Stewart
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Oct-30-2008
 Ground surface elevation: 389.20 m AMSL
 Top of casing elevation: 390.04 m AMSL
 Easting: 532682.557
 Northing: 4809090.487

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
13		Refer to WT-EBS-OW1A-08 for Lithology	0.00	11	CC	n/a	n/a		Bentonite Grout
45				12	CC	n/a	18" 30%		
14				13	CC	n/a	55" 92%		
15				14	CC	n/a	44" 73%		
50				15	CC	n/a	59" 100%		
16				16	CC	n/a	36" 62%		
55				17	CC	n/a	46" 77%		
17				18	CC	n/a	28" 46%		
18				19	CC	n/a	38" 63%		
60									
19									
65									
20									
21									
70									
22									
75									
23									
24									
80									
25									
85									
26			389.20						

Screen Interval: 44.22 - 47.27 m BGS
 Sand Pack Interval: 42.80 - 47.45 m BGS
 Well Seal Interval: 0.91 - 42.80 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Monitoring Well: WT-EBS-OW1B-08

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: C.Stewart
Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
Date started/completed: Oct-30-2008
Ground surface elevation: 389.20 m AMSL
Top of casing elevation: 390.04 m AMSL
Easting: 532682.557
Northing: 4809090.487

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
		Refer to WT-EBS-CW1A-08 for Lithology	0.00	20	CC	n/a	55" 92%		
90	27			21	CC	n/a	56" 93%		
95	28			22	CC	n/a	56" 100%		
100	29			23	CC	n/a	56" 93%		
105	30			24	CC	n/a	54" 90%		
110	31			25	CC	n/a	4" 7%		
115	32			26	CC	n/a	60" 100%		
120	33			27	CC	n/a	52" 87%		
125	34			28	CC	n/a	56" 97%		
130	35								
	36								
	37								
	38								
	39								
	40								
			389.20						

Screen Interval: 44.22 - 47.27 m BGS
Sand Pack Interval: 42.80 - 47.45 m BGS
Well Seal Interval: 0.91 - 42.80 m BGS

Notes:
m AMSL - metres above mean sea level
m BGS - metres below ground surface
m BTOC - metres below top of casing
CC - continuous core sample

n/a - not available/applicable



Stantec


Drawn By/Checked By: OR/KM

Sheet 3 of 4

Monitoring Well: WT-EBS-OW1B-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: C.Stewart
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Oct-30-2008
 Ground surface elevation: 389.20 m AMSL
 Top of casing elevation: 390.04 m AMSL
 Easting: 532682.557
 Northing: 4809090.487

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
135	41	Refer to WT-EBS-OW1A-08 for Lithology	0.00	29	CC	n/a	30" 50%		Holeplug
140	42			30	CC	n/a	59" 97%		Top of sand (42.80 m BGS)
145	43			31	CC	n/a	57" 95%		Top of screen (44.22 m BGS)
150	44			32	CC	n/a	36" 60%		No.1 Silica Sand
155	45			33	CC	n/a	28" 47%		No.10 Slot PVC screen 50 mm diameter
160	46	End of Borehole	341.75						Bottom of screen (47.27 m BGS)
165	47		47.45						No.1 Silica Sand
170	48								
175	49								
	50								
	51								
	52								
	53								

Screen Interval: 44.22 - 47.27 m BGS
 Sand Pack Interval: 42.80 - 47.45 m BGS
 Well Seal Interval: 0.91 - 42.80 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 4 of 4

Monitoring Well: WT-EB-OW1-15									
Project: RMOW Well Replacement				Field investigator: L.Carson					
Client: Regional Municipality of Waterloo				Contractor: Gerrits Well Drilling Inc.					
Location:Cambridge, ON				Drilling method: Air Rotary					
Number: 160900798				Date started/completed:11-May-2015 / 15-May-2015					
SUBSURFACE PROFILE					HYDROGEOLOGY		SAMPLE DETAILS		WELL DETAILS
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Hydro Stratigraphic Unit	Description	Sample Number	Sample Type	Name: WT-EB-OW1A-15 GS Elev: 370.48 m AMSL TOC Elev: 371.24 m AMSL Easting: 533141 Northing: 4809141 Stick-up: 0.76 m	Name: WT-EB-OW1B-15 GS Elev: 370.48 m AMSL TOC Elev: 371.01 m AMSL Easting: 533143 Northing: 4809139 Stick-up: 0.53 m
(ft)	(m)								
0	0	Ground Surface	370.48						
		TOPSOIL organics, medium to coarse sand, fine to medium gravel, trace clay, dark brown (10YR 3/3)	0.00						
			369.56			1	GB		
5	2	TILL silty to clayey till, some fine and coarse sand, greyish- brown (10YR 5/2), medium to high placticity, soft	0.91						
				Possible ATB1	Possible Upper Maryhill Till	2	GB		
10		sand and gravel content increasing with depth							
						3	GB		
15	4								
						4	GB		
20	6	SAND and GRAVEL fine to coarse, trace silt, angular to subrounded, greyish-brown (10YR 5/2)	364.38						
			6.10			5	GB		
25				Possible AFB1	Possible Upper Waterloo Moraine stratified sediments and equivalents				
		yellowish brown (10YR 5/4) at 7.92 m BGS				6	GB		
30			361.33						
		TILL silt till, some fine to coarse sand and gravel, some clay, subangular to subrounded, greyish brown (10YR 5/2)	9.14			7	GB		
35	10								
						8	GB		
40	12	sand and gravel content increasing with depth		Possible ATB2	Possible Middle Maryhill Till and equivalents				
						9	GB		
45	14								
						10	GB		
50		SAND AND GRAVEL fine to coarse sand, fine to medium gravel, trace silt and clay, subangular to subrounded, greyish brown (10YR 5/4)	355.24						
			15.24			11	GB		
55	16								
						12	GB		
60	18	SAND fine to coarse, gravel, trace silt, subangular to subrounded, grey (7.5YR 6/1)	352.19						
			18.29			13	GB		
65	20								
						14	GB		
70		SAND and GRAVEL medium to coarse sand, fine to coarse gravel, trace silt, subangular and subrounded, grey (7.5YR 6/1)	349.14						
			21.34						
22									

STANTEC BOREHOLE AND WELL - CLUST 11X17 160900798_20150309_CD.GPJ STANTEC - DATA TEMPLATE.GDT 1/26/16 NSPINA



Notes:
m AMSL - metres above mean sea level
m BGS - metres below ground surface
m BTOC - metres below top of casing
GB - grab sample
n/a - not available

WT-EB-OW1A-15 WRAS No. 9207191
WT-EB-OW1B-15 WRAS No. 9207192

Drawn By/Checked By: EH, NS/LV

Sheet 1 of 2

Monitoring Well: WT-EB-OW1-15

Project: RMOW Well Replacement

Client: Regional Municipality of Waterloo

Location: Cambridge, ON

Number: 160900798

Field investigator: L.Carson

Contractor: Gerrits Well Drilling Inc.

Drilling method: Air Rotary

Date started/completed:11-May-2015 / 15-May-2015

SUBSURFACE PROFILE					HYDROGEOLOGY		SAMPLE DETAILS		WELL DETAILS			
Depth		Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Hydro Stratigraphic Unit	Description	Sample Number	Sample Type	Name: WT-EB-OW1A-15		Name: WT-EB-OW1B-15	
(ft)	(m)								GS Elev: 370.48 m AMSL TOC Elev: 371.24 m AMSL Easting: 533141 Northing: 4809141 Stick-up: 0.76 m	GS Elev: 370.48 m AMSL TOC Elev: 371.01 m AMSL Easting: 533143 Northing: 4809139 Stick-up: 0.53 m		
75 24 80 26 85 28 90 30 95 32 100 34 105 36 110 38 115 40 120 42 125 44			SAND and GRAVEL medium to coarse sand, fine to coarse gravel, trace silt, subangular and subrounded, grey (7.5YR 6/1)		Possible AFB2	Possible Middle Waterloo Moraine stratified sediments and equivalents	15	GB				
			silt content decreasing at 22.86 m BGS				16	GB				
							17	GB				
							18	GB				
							19	GB				
							20	GB				
							21	GB				
							22	GB				
							23	GB				
							24	GB				
125 38 130 40 135 42 140 44			SAND fine to coarse sand and gravel, trace silt, subangular to subrounded, grey (7.5YR 6/1)	332.38 38.10			25	GB				
							26	GB				
							27	GB				
			decreasing gravel content, dark greyish brown (10YR 4/2) at 41.15 m BGS				28	GB				
							29	GB				
			TILL clay, some sand and silt, grey (7.5YR 6/1), firm, medium to high plasticity End of Borehole	326.89 43.59 326.74 43.74	Possible ATB3	Possible Lower Maryhill Till						

Notes:

m AMSL - metres above mean sea level

m BGS - metres below ground surface

m BTOC - metres below top of casing

GB - grab sample

n/a - not available

WT-EB-OW1A-15 WRAS No. 9207191

WT-EB-OW1B-15 WRAS No. 9207192



Monitoring Well: WT-EBS-OW2A-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Nov-4-2008
 Ground surface elevation: 390.01 m AMSL
 Top of casing elevation: 390.85 m AMSL
 Easting: 533255.455
 Northing: 4808920.28

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
0	0	Ground Surface	390.01						Stick-up = 0.84 m Blue steel protective casing
		TOPSOIL brown, moist	0.00						
		SILTY SAND fine grained, light brown, moist	389.80	1	SS	1-1-2-1 (3)	15" 63%		Concrete
1		seam of fine sand with trace fine gravel 51mm thick at 1 m BGS	0.20						
		seam of mottled brown and white silty fine sand 76 mm thick at 1.17m BGS		2	SS	2-2-3-2 (5)	16" 67%		
5		SAND AND SILT TILL fine grained, little medium to coarse sand, light brown, hard, moist	388.48						
			1.52	3	SS	2-4-5-5 (9)	14" 58%		
2				4	SS	n/a	20" 83%		
		alternating layers of silty clay and sandy silt 305 mm thick at 3.0 m BGS	386.71						
10		SILTY SAND brown, firm, moist to wet	3.30	5	CC	n/a	35" 100%		
		SAND fine grained, brown, moist, increasing grain size with depth	386.33						
4			3.68	6	CC	n/a	52" 87%		PVC Sch80 50 mm diameter
15		seam of sandy silt, 38 mm thick at 4.7 m BGS							
				7	CC	n/a	55" 92%		
20									
		some medium sand beginning at 7.3 m BGS		8	CC	n/a	48" 80%		
25									
				9	CC	n/a	50" 83%		Bentonite Grout
30									
				10	CC	n/a	60" 100%		
35									
		seam of soft clay pockets 101.5 mm thick at 12.11 m BGS		11	CC	n/a	54" 90%		
40		seam of brown clay mottled with silt and sand 76.2 mm thick at 12.21 m BGS							
		seam of brown clay mottle with silt and sand 38 mm thick at 12.32 m BGS							
			386.33						

Screen Interval: 58.83 - 61.87 m BGS
 Sand Pack Interval: 57.05 - 62.64 m BGS
 Well Seal Interval: 0.91 - 57.05 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Monitoring Well: WT-EBS-OW2A-08

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
Date started/completed: Nov-4-2008
Ground surface elevation: 390.01 m AMSL
Top of casing elevation: 390.85 m AMSL
Easting: 533255.455
Northing: 4808920.28

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
45	14	m BGS SAND fine grained, brown, moist, increasing grain size with depth	3.68	12	CC	n/a	34" 56%		Bentonite Grout
50	15	seam of soft brown clay 101.6 mm thick at 14.45 m BGS seam of pockets of soft brown clay, 25.4 mm thick at 14.8 m BGS		13	CC	n/a	58" 97%		
55	16			14	CC	n/a	60" 100%		
60	18	seam of fine white sand 5 mm thick at 18.0 m BGS seams of soft brown clay 4 mm between 18.3 and 18.4 m BGS		15	CC	n/a	49" 82%		
65	20			16	CC	n/a	56" 97%		
70	21			17	CC	n/a	58" 95%		
75	23	trace fine gravel at 22.9 m BGS		18	CC	n/a	57" 93%		
80	24			19	CC	n/a	58" 97%		
85	26			20	CC	n/a	55" 92%		

Screen Interval: 58.83 - 61.87 m BGS
 Sand Pack Interval: 57.05 - 62.64 m BGS
 Well Seal Interval: 0.91 - 57.05 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample
 n/a - not available/applicable

Drawn By/Checked By: OR/KM




Stantec

Sheet 2 of 5

Monitoring Well: WT-EBS-OW2A-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Nov-4-2008
 Ground surface elevation: 390.01 m AMSL
 Top of casing elevation: 390.85 m AMSL
 Easting: 533255.455
 Northing: 4808920.28

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth (ft) (m)	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
27		SAND AND GRAVEL some cobble, grey, well graded, subrounded, wet	362.93 27.08	21	CC	n/a	36" 60%		Bentonite Grout
28		CLAY TILL some well graded gravel, brown, soft, moist	361.92 28.09	22	CC	n/a	24" 40%		
29		SAND AND GRAVEL brown and grey, well graded, subrounded, wet	360.82 29.18	23	CC	n/a	29" 50%		
30				24	CC	n/a	40" 67%		
31				25	CC	n/a	49" 82%		
32		pockets of soft brown clay at 32.06 m BGS cobble at 32.2 m BGS		26	CC	n/a	41" 71%		
33		cobble at 33.15 m BGS cobble at 33.28 m BGS cobble at 33.58 m BGS		27	CC	n/a	58" 97%		
34				28	CC	n/a	21" 33%		
35		cobble at 35.05 m BGS cobble at 35.18 m BGS		29	CC	n/a	51" 85%		
36		cobble at 36.22 m BGS							
37									
38		cobble at 38.61 m BGS							
39									
40		cobble at 39.85 m BGS cobble at 40.16 m BGS	360.82						

Screen Interval: 58.83 - 61.87 m BGS
 Sand Pack Interval: 57.05 - 62.64 m BGS
 Well Seal Interval: 0.91 - 57.05 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOT - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 3 of 5

Monitoring Well: WT-EBS-OW2A-08

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
Date started/completed: Nov-4-2008
Ground surface elevation: 390.01 m AMSL
Top of casing elevation: 390.85 m AMSL
Easting: 533255.455
Northing: 4808920.28

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
		SAND AND GRAVEL brown and grey, well graded, subrounded, wet	29.18						
135	41	cobble at 41.15 m BGS		30	CC	n/a	60" 100%		
	42								
140	43			31	CC	n/a	16" 29%		
	44								
145	45	cobble at 44.40 m BGS		32	CC	n/a	22" 36%		
	46								
150	47			33	CC	n/a	17" 29%		
	48	cobble at 47.70 m BGS		34	CC	n/a	53" 88%		
155	49		341.90						
	50	SAND fine to medium grained, trace fine gravel, brown, moist	48.11	35	CC	n/a	50" 83%		
160	51								
	52			36	CC	n/a	0" 0%		
165	53	no trace gravel beginning at 50.82 m BGS							
	54			37	CC	n/a	54" 89%		
170	55								
	56			38	CC	n/a	58" 93%		
175	57	trace coarse sand beginning at 53.65 m BGS							
	58		341.90						
	59								
	60								
	61								
	62								
	63								
	64								
	65								
	66								
	67								
	68								
	69								
	70								
	71								
	72								
	73								
	74								
	75								
	76								
	77								
	78								
	79								
	80								
	81								
	82								
	83								
	84								
	85								
	86								
	87								
	88								
	89								
	90								
	91								
	92								
	93								
	94								
	95								
	96								
	97								
	98								
	99								
	100								
	101								
	102								
	103								
	104								
	105								
	106								
	107								
	108								
	109								
	110								
	111								
	112								
	113								
	114								
	115								
	116								
	117								
	118								
	119								
	120								
	121								
	122								
	123								
	124								
	125								
	126								
	127								
	128								
	129								
	130								
	131								
	132								
	133								
	134								
	135								
	136								
	137								
	138								
	139								
	140								
	141								
	142								
	143								
	144								
	145								
	146								
	147								
	148								
	149								
	150								
	151								
	152								
	153								
	154								
	155								
	156								
	157								
	158								
	159								
	160								
	161								
	162								
	163								
	164								
	165								
	166								
	167								
	168								
	169								
	170								
	171								
	172								
	173								
	174								
	175								
	176								
	177								
	178								
	179								
	180								
	181								
	182								
	183								
	184								
	185								
	186								
	187								
	188								
	189								
	190								
	191								
	192								
	193								
	194								
	195								
	196								
	197								
	198								
	199								
	200								
	201								
	202								
	203								
	204								
	205								
	206								
	207								
	208								
	209								
	210								
	211								
	212								
	213								
	214								
	215								
	216								
	217								
	218								
	219								
	220								
	221								
	222								
	223								
	224								
	225								
	226								
	227								
	228								
	229								
	230								
	231								
	232								
	233								
	234								
	235								
	236								
	237								
	238								
	239								
	240								
	241								
	242								
	243								
	244								
	245								
	246								
	247								
	248								
	249								
	250								
	251								
	252								
	253								
	254								
	255								
	256								
	257								
	258								
	259								
	260								
	261								
	262								
	263								
	264								
	265								
	266								
	267								
	268								
	269								
	270								
	271								
	272								
	273								
	274								
	275								
	276								
	277								
	278								
	279								
	280								
	281								
	282								
	283								
	284								
	285								
	286								
	287								
	288								
	289								

Screen Interval: 58.83 - 61.87 m BGS
Sand Pack Interval: 57.05 - 62.64 m BGS
Well Seal Interval: 0.91 - 57.05 m BGS

Notes:
m AMSL - metres above mean sea level
m BGS - metres below ground surface
m BTOC - metres below top of casing
SS - split-spoon sample
CC - continuous core sample

n/a - not available/applicable



Stantec



Drawn By/Checked By: OR/KM

Sheet 4 of 5

Monitoring Well: WT-EBS-OW2A-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Nov-4-2008
 Ground surface elevation: 390.01 m AMSL
 Top of casing elevation: 390.85 m AMSL
 Easting: 533255.455
 Northing: 4808920.28

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
180	55	SAND fine to medium grained, trace fine gravel, brown, moist	48.11	39	CC	n/a	42" 70%		Holeplug
	56	band of black sand 2 mm thick at 55.85 m BGS		40	CC	n/a	60" 100%		
185	57	band of black sand 2 mm thick at 56.69 m BGS							Top of sand (57.05 m BGS)
	58	alternating layers of fine or coarser fine sand between 152 to 187 mm thick beginning at 57.25 m BGS bands of black sand 4 mm thick at 57.43 m BGS bands of black sand 4 mm thick at 57.58 m BGS bands of black sand 4 mm thick at 58.04 m BGS bands of black sand 4 mm thick at 58.01 m BGS interlaced black sand seams beginning at 58.04 m BGS		41	CC	n/a	49" 82%		No.1 Silica Sand
190	59			42	CC	n/a	52" 87%		Top of screen (58.83 m BGS)
195	60	seam of 1 mm thick layered brown silt 25 mm thick at 59.72 m BGS		43	CC	n/a	54" 90%		No.10 Slot PVC screen 50 mm diameter
200	61								Bottom of screen (61.87 m BGS)
	62			44	CC	n/a	50" 83%		Top of coated holeplug 62.64 m BGS
205	63		326.84 63.17						
	64	CLAY TILL trace fine gravel, trace coarse sand, brown/grey, very stiff, moist		45	CC	n/a	60" 100%		Coated Holeplug
210	65			46	CC	n/a	28" 100%		
215	66	End of Borehole	324.68 65.33						
	67								
220									

Screen Interval: 58.83 - 61.87 m BGS
 Sand Pack Interval: 57.05 - 62.64 m BGS
 Well Seal Interval: 0.91 - 57.05 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

Drawn By/Checked By: OR/KM

n/a - not available/applicable



Stantec

Sheet 5 of 5

Monitoring Well: WT-EBS-OW2B-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
 Date started/completed: Nov-4-2008
 Ground surface elevation: 389.87 m AMSL
 Top of casing elevation: 390.72 m AMSL
 Easting: 533253.708
 Northing: 4808923.303

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
0	0	Ground Surface Refer to WT-EBS-OW2A-08 for Lithology	389.87 0.00						Stick up=0.85 m Steel protective casing
				1	SS	1-1-2-1 (3)	15" 63%		Concrete
	1			2	SS	2-2-3-2 (5)	16" 67%		
5				3	SS	2-4-5-5 (9)	14" 58%		
	2			4	SS	n/a	20" 83%		
10	3			5	CC	n/a	35" 100%		
	4			6	CC	n/a	52" 87%		PVC Sch80 50 mm diameter
15				7	CC	n/a	55" 92%		
	5			8	CC	n/a	48" 80%		
20	6			9	CC	n/a	50" 83%		
	7			10	CC	n/a	60" 100%		
25				11	CC	n/a	54" 90%		
	8								
30	9								
	10								
35									
	11								
40	12								
			389.87						

Screen Interval: 44.81 - 47.85 m BGS
 Sand Pack Interval: 43.18 - 48.06 m BGS
 Well Seal Interval: 0.91 - 43.18 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: CR/KM



Stantec

Monitoring Well: WT-EBS-OW2B-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R. Dong
 Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
 Date started/completed: Nov-4-2008
 Ground surface elevation: 389.87 m AMSL
 Top of casing elevation: 390.72 m AMSL
 Easting: 533253.708
 Northing: 4808923.303

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
13		Refer to WT-EBS-OW2A-08 for Lithology	0.00						
45				12	CC	n/a	34" 56%		
50				13	CC	n/a	58" 97%		
55				14	CC	n/a	60" 100%		
60				15	CC	n/a	49" 82%		
65				16	CC	n/a	56" 97%		
70				17	CC	n/a	58" 95%		
75				18	CC	n/a	57" 93%		
80				19	CC	n/a	58" 97%		
85				20	CC	n/a	55" 92%		
			389.87						Bentonite Grout

Screen Interval: 44.81 - 47.85 m BGS
 Sand Pack Interval: 43.18 - 48.06 m BGS
 Well Seal Interval: 0.91 - 43.18 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

Drawn By/Checked By: OR/KM

n/a - not available/applicable



Monitoring Well: WT-EBS-OW2B-08

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
Date started/completed: Nov-4-2008
Ground surface elevation: 389.87 m AMSL
Top of casing elevation: 390.72 m AMSL
Easting: 533253.708
Northing: 4808923.303

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)		Refer to WT-EBS-OW2A-08 for Lithology	0.00						
27				21	CC	n/a	36" 60%		
90									
28				22	CC	n/a	24" 40%		
95									
29				23	CC	n/a	29" 50%		
30									
100				24	CC	n/a	40" 67%		
31									
105				25	CC	n/a	49" 82%		
32									
33				26	CC	n/a	41" 71%		
110									
34				27	CC	n/a	58" 97%		
115									
35				28	CC	n/a	21" 33%		
36									
120				29	CC	n/a	51" 85%		
37									
125									
38									
39									
130									
40			389.87						Top of holeplug (39.70 m BGS)

Screen Interval: 44.81 - 47.85 m BGS
 Sand Pack Interval: 43.18 - 48.06 m BGS
 Well Seal Interval: 0.91 - 43.18 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable



Stantec

Drawn By/Checked By: OR/KM

Sheet 3 of 4

Drilling method: Tricone mud rotary 5"
Date started/completed: Nov-4-2008
Ground surface elevation: 389.87 m AMSL
Top of casing elevation: 390.72 m AMSL
Easting: 533253.708
Northing: 4808923.303

Sheet 4 of 4

9 20 3 576

WT-EB-OW3-08-A

Monitoring Well: WT-EBS-OW3A-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Nov-18-2008 / Nov-20-2008
 Ground surface elevation: 385.13 m AMSL
 Top of casing elevation: 386.01 m AMSL
 Easting: 532634.653
 Northing: 4809715.33

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
0	0	Ground Surface	385.13						Stick up=0.88 m
		SAND AND GRAVEL FILL moist	0.00	1	SS	3-3-2-2 (5)	2" 8%		Steel protective casing
			384.37						
		SAND AND GRAVEL trace topsoil, medium grained, dark brown, moist	0.76	2	SS	3-2-3-3 (5)	8" 33%		
5				3	SS	3-2-4-7 (6)	6" 25%		
2			382.84						
		SILT AND SAND TILL trace to some fine sand, trace gravel, brown, moist	2.29	4	SS	2-2-3-3 (5)	11.5" 48%		
10				5	CC	n/a	20" 100%		
		seam of sand and gravel 0.1 m thick at 3.25 m BGS seam of sand and gravel 0.05 m thick at 3.25 m BGS	381.65 3.48						
4		SILTY CLAY brown grey, stiff, moist seam of fine to medium sand with trace silt 0.58 m thick at 3.76 m BGS seam of fine sand and trace silt 0.13 m thick at 4.42 m BGS		6	CC	n/a	44" 75%		PVC Sch80 50 mm diameter
15									
5		seam of silt with trace sand 0.20 m thick at 4.9 m BGS	380.02 5.11						
		SILTY CLAY TILL trace to little gravel, brown grey, firm, moist		7	CC	n/a	22" 37%		
20									
7				8	CC	n/a	29" 47%		
25									
9				9	CC	n/a	50" 82%		
30									
10				10	CC	n/a	47.5" 86%		
35									
11									
40				11	CC	n/a	59" 95%		
		seam of silt and fine sand 0.05 m thick at 13.23 m BGS	380.02						

Screen Interval: 53.67 - 56.72 m BGS
 Sand Pack Interval: 51.89 - 56.72 m BGS
 Well Seal Interval: 0.00 - 51.89 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 1 of 5

Monitoring Well: WT-EBS-OW3A-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Nov-18-2008 / Nov-20-2008
 Ground surface elevation: 385.13 m AMSL
 Top of casing elevation: 386.01 m AMSL
 Easting: 532634.653
 Northing: 4809715.33

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
45	14	SILTY CLAY TILL trace to little gravel, brownish grey, firm, moist	5.11	12	CC	n/a	60" 100%		Bentonite Grout
50	15			13	CC	n/a	60" 100%		
55	16			14	CC	n/a	60" 100%		
60	17			15	CC	n/a	60" 98%		
65	18	trace to little medium to coarse sand beginning at 18.6 m BGS		16	CC	n/a	60" 100%		
70	19	trace mottling pattern with clayey silt beginning at 19.59 m BGS		17	CC	n/a	46" 77%		
75	20			18	CC	n/a	60" 95%		
80	21	trace soft grey clay pockets 2 mm diameter beginning at 22.43 m BGS trace dry red clay pockets 2 mm diameter beginning at 22.56 m BGS		19	CC	n/a	60" 100%		
85	22			20	CC	n/a	61" 100%		
	23	seam of very fine sand 10 mm thick at 24.61 m BGS seam of very fine sand 20 mm thick at 24.64 m BGS little fine sand beginning at 25.30 m BGS seam of very fine sand 10 mm thick at 25.40 m BGS	380.02						

Screen Interval: 53.67 - 56.72 m BGS
 Sand Pack Interval: 51.89 - 56.72 m BGS
 Well Seal Interval: 0.00 - 51.89 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Monitoring Well: WT-EBS-OW3A-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
 Date started/completed: Nov-18-2008 / Nov-20-2008
 Ground surface elevation: 385.13 m AMSL
 Top of casing elevation: 386.01 m AMSL
 Easting: 532634.653
 Northing: 4809715.33

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
27		SILTY CLAY TILL trace to little gravel, brown grey, firm, moist	5.11	21	CC	n/a	60" 100%		
90		seam of silty clay 0.7 m thick at 27.4 m BGS							
28		mottling of clayey silt and fine sand beginning at 28.07 m BGS trace to little fine to coarse sand, trace fine and coarse gravel, beginning at 28.09 m BGS		22	CC	n/a	59" 98%		
95		trace soft grey clay pockets begining at 28.22 m BGS							
30		trace dry, red pockets 1 mm deameters beginning at 28.07 m BGS		23	CC	n/a	60" 100%		
100									
31		seam of soft clay 4 mm thick at 31.55 m BGS		24	CC	n/a	64" 100%		
105									
32									
33				25	CC	n/a	57" 100%		
110									Bentonite Grout
34									
115		seam of very fine sand 10 mm thick at 35.00 m BGS trace to little fine gravel beginning at 35.36 m BGS		26	CC	n/a	58" 97%		
36									
120				27	CC	n/a	60" 100%		
37		cobble at 37.03 m BGS							
125		horizontal banding and mottled structure present		28	CC	n/a	4" 7%		
39									
130				29	CC	n/a	60" 100%		
40			380.02						

Screen Interval: 53.67 - 56.72 m BGS
 Sand Pack Interval: 51.89 - 56.72 m BGS
 Well Seal Interval: 0.00 - 51.89 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable



Stantec




Sheet 3 of 5

Drawn By/Checked By: OR/KM

Monitoring Well: WT-EBS-OW3A-08

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
Date started/completed: Nov-18-2008 / Nov-20-2008
Ground surface elevation: 385.13 m AMSL
Top of casing elevation: 386.01 m AMSL
Easting: 532634.653
Northing: 4809715.33

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth (m)	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
41		SILTY CLAY TILL trace to little gravel, brownish grey, firm, moist	5.11	30	CC	n/a	60° 100%		Bentonite Grout
42		seam of soft clay 20 mm thick at 41.68 m BGS		31	CC	n/a	60° 100%		
43		seam of little fine gravel 0.3 m thick at 42.62 m BGS layering of silty clay and sandy clayey silt (10 mm) beginning at 42.87 m BGS	342.05 43.08						
44		SAND fine grained, little silt, brownish grey, homogenous, wet		32	CC	n/a	49° 82%		
45		CLAYEY SILT AND SAND TILL fine grained, little medium to coarse sand, trace fine gravel, brownish grey, stiff, moist	340.04 45.09	33	CC	n/a	49° 82%		
46		SAND fine grained, little silt, brownish grey, homogeneous, moist	339.43 45.70						
47		CLAYEY SILT AND SAND TILL fine grained, trace to little medium to coarse sand, trace fine gravel, brownish grey, very stiff, moist seam of silty clay till 0.05 m thick at 46.73 m BGS seam of silty clay till 0.1 m at 47.40 m BGS trace soft brownish grey clay pockets 2 to 4 mm diameter beginning at 47.65 m BGS seam of clayey silt 0.15 m thick at 47.70 m BGS cobble at 48.21 m BGS	338.55 46.58	34	CC	n/a	60° 100%		
48				35	CC	n/a	61° 100%		
49			335.47 49.66	36	CC	n/a	53° 88%		Top of holeplug (49.20 m BGS)
50		SAND fine grained, brownish grey, homogenous, wet	335.49 49.94						Holeplug
51		SAND AND GRAVEL fine grained, well graded gravel, angular to subrounded seam of clayey silt and sand 0.1 m thick at 50.52 m BGS seam of fine sand 0.1 m thick at 50.62 m BGS sand becoming well graded at 50.72 m BGS		37	CC	n/a	60° 107%		Top of sand (51.89 m BGS)
52		cobble at 52.33 m BGS							No. 1 Silica Sand
53		cobble at 52.73 m BGS		38	CC	n/a	59° 98%		
54		cobble at 53.19 m BGS cobble at 53.46 m BGS seam of silt and sand 0.48 m thick at 53.67 m BGS	335.19						Top of screen (53.67 m BGS)

Screen Interval: 53.67 - 56.72 m BGS
 Sand Pack Interval: 51.89 - 56.72 m BGS
 Well Seal Interval: 0.00 - 51.89 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable


Drawn By/Checked By: OR/KM



Monitoring Well: WT-EBS-OW3A-08

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: CME 75 PQ Coring
Date started/completed: Nov-18-2008 / Nov-20-2008
Ground surface elevation: 385.13 m AMSL
Top of casing elevation: 386.01 m AMSL
Easting: 532634.653
Northing: 4809715.33

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)									
180	55	SAND AND GRAVEL fine grained, well graded gravel, angular to subrounded cobble at 54.53 m BGS	49.94	39	CC	n/a	60" 100%		No.10 Slot PVC screen 50 mm diameter
185	56		328.41						Bottom of screen (56.72 m BGS)
185	57	End of Borehole	56.72						
190	58								
195	59								
200	60								
205	61								
210	62								
215	63								
220	64								
	65								
	66								
	67								

Screen Interval: 53.67 - 56.72 m BGS
 Sand Pack Interval: 51.89 - 56.72 m BGS
 Well Seal Interval: 0.00 - 51.89 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTCC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable

Drawn By/Checked By: OR/KM



Stantec

Sheet 5 of 5

Monitoring Well: WT-EBS-OW3B-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R. Dong
 Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
 Date started/completed: Nov-18-2008 / Nov-20-2008
 Ground surface elevation: 385.23 m AMSL
 Top of casing elevation: 386.14 m AMSL
 Easting: 532633.541
 Northing: 4809717.798

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft)	(m)								
0	0	Ground Surface	385.23						Stick up=0.91 m
		Refer to WT-EBS-OW3A-08 for Lithology	0.00						Steel protective casing
				1	SS	3-3-2-2 (5)	2" 8%		Concrete
	1			2	SS	3-2-3-3 (5)	8" 33%		
5	2			3	SS	3-2-4-7 (6)	6" 25%		
				4	SS	2-2-3-3 (5)	11.5" 48%		
10	3			5	CC	n/a	20" 111%		
	4			6	CC	n/a	44" 76%		
15	5			7	CC	n/a	22" 37%		PVC Sch80 50 mm diameter
20	6			8	CC	n/a	29" 47%		
	7			9	CC	n/a	50" 82%		
25	8			10	CC	n/a	47.5" 86%		
30	9			11	CC	n/a	59" 95%		
35	10								
40	11								
	12								
			385.23						

Screen Interval: 43.28 - 46.33 m BGS
 Sand Pack Interval: 41.86 - 46.48 m BGS
 Well Seal Interval: 0.91 - 41.86 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

n/a - not available/applicable



Drawn By/Checked By: OR/KM

Monitoring Well: WT-EBS-OW3B-08

Project: Erb St. Class ESA
Client: Regional Municipality of Waterloo
Location: Erb Street
Number: 1609-00505
Field investigator: R.Dong
Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
Date started/completed: Nov-18-2008 / Nov-20-2008
Ground surface elevation: 385.23 m AMSL
Top of casing elevation: 386.14 m AMSL
Easting: 532633.541
Northing: 4809717.798

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(ft) (m)		Refer to WT-EBS-OW3A-08 for Lithology	0.00						
13				12	CC	n/a	60" 100%		
45									
14				13	CC	n/a	60" 100%		
15									
50				14	CC	n/a	60" 100%		
16									
55				15	CC	n/a	60" 100%		
17									
18				16	CC	n/a	60" 100%		
60									
19				17	CC	n/a	46" 77%		
65									
20				18	CC	n/a	60" 100%		
21									
70				19	CC	n/a	60" 100%		
22									
75				20	CC	n/a	51" 100%		
23									
24									
80									
25									
85									
26									
			385.23						

Screen Interval: 43.28 - 46.33 m BGS
 Sand Pack Interval: 41.86 - 46.48 m BGS
 Well Seal Interval: 0.91 - 41.86 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample
 n/a - not available/applicable



Drawn By/Checked By: OR/KM

Sheet 2 of 4

Monitoring Well: WT-EBS-OW3B-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R. Dong
 Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
 Date started/completed: Nov-18-2008 / Nov-20-2008
 Ground surface elevation: 385.23 m AMSL
 Top of casing elevation: 386.14 m AMSL
 Easting: 532633.541
 Northing: 4809717.798

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-Value	Recovery	Well Diagram	Description
(m)	(m)								
27		Refer to WT-EBS-OW3A-08 for Lithology	0.00	21	CC	n/a	60" 100%		Bentonite Grout
90				22	CC	n/a	59" 98%		
28				23	CC	n/a	57" 95%		
95				24	CC	n/a	67" 105%		
29				25	CC	n/a	57" 100%		
30				26	CC	n/a	58" 97%		
31				27	CC	n/a	60" 100%		
32				28	CC	n/a	4" 7%		
33				29	CC	n/a	60" 100%		
34									
35									
36									
37									
38									
39									
40									
			385.23						

Screen Interval: 43.28 - 46.33 m BGS
 Sand Pack Interval: 41.86 - 46.48 m BGS
 Well Seal Interval: 0.91 - 41.86 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample

Drawn By/Checked By: OR/KM

n/a - not available/applicable



Stantec

Monitoring Well: WT-EBS-OW3B-08

Project: Erb St. Class ESA
 Client: Regional Municipality of Waterloo
 Location: Erb Street
 Number: 1609-00505
 Field investigator: R.Dong
 Contractor: Pro Core Drilling

Drilling method: Tricone mud rotary 5"
 Date started/completed: Nov-18-2008 / Nov-20-2008
 Ground surface elevation: 385.23 m AMSL
 Top of casing elevation: 386.14 m AMSL
 Easting: 532633.541
 Northing: 4809717.798

SUBSURFACE PROFILE			SAMPLE DETAILS					WELL DETAILS	
Depth	Graphic Log	Lithologic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	N-value	Recovery	Well Diagram	Description
(ft) (m)									
		Refer to WT-EBS-OW3A-08 for Lithology	0.00						
135	41			30	CC	n/a	60" 100%		Top of sand (41.86 m BGS)
	42			31	CC	n/a	60" 100%		
140	43			32	CC	n/a	49" 82%		Top of screen (43.28 m BGS)
145	44			33	CC	n/a	49" 82%		No. 1 Silica Sand
	45								No. 10 Slot PVC screen 50 mm diameter
150	46		338.75						Bottom of screen (46.33 m BGS)
	47	End of Borehole	46.48						No. 1 Silica Sand
155	48								
	49								
160	50								
	51								
165	52								
170	53								
175									

Screen Interval: 43.28 - 46.33 m BGS
 Sand Pack Interval: 41.86 - 46.48 m BGS
 Well Seal Interval: 0.91 - 41.86 m BGS

Notes:
 m AMSL - metres above mean sea level
 m BGS - metres below ground surface
 m BTOC - metres below top of casing
 SS - split-spoon sample
 CC - continuous core sample
 n/a - not available/applicable



Stantec

Drawn By/Checked By: OR/KM

Sheet 4 of 4





STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 4

PROJECT NAME: WATERLOO LANDFILL SITE
 PROJECT NUMBER: 823-02
 CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
 LOCATION: AS PER PLAN

HOLE DESIGNATION: OW322A-02
 DATE COMPLETED: 15 July 2002
 DRILLING METHOD: ROTASONIC
 FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
	TOP OF RISER GROUND SURFACE	398.11 397.29						
1	SILTY SAND (TOPSOIL), loose, fine grained, poorly graded, dark brown, moist, vegetative matter (grass, rootlets) ML/CL - CLAYEY SILT (TILL), trace gravel, firm, grey/brown, dry	396.98						
2								
3								
4	- moist at 3.66m BGS - silty clay, stiff, grey at 4.27m BGS							
5								
6								
7								
8	SM - SILTY SAND, dense, slightly cohesive, medium grained, well graded, brown, moist to wet	389.97						
9								
10	SC- CLAYEY SAND, with silt, trace gravel, dense, moderately cohesive, fine grained, well graded, grey, moist	387.84						
11								
12	ML/CL - CLAYEY SILT (TILL), with sand, trace to with gravel, stiff, grey, moist	385.10						
13								
14								
15								
16	- light brown at 15.85m BGS - sandy, very moist at 16.46m BGS							
17	SP - SAND, with gravel, trace silt, dense, slightly cohesive, medium grained, poorly graded, grey/brown, moist - fine grained at 17.98m BGS	380.22						
18								
19	SM - SILTY SAND, trace gravel, dense, moderately	377.78						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 000823-2002.GPJ CRA_CORP.GDT 1/4/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 2 of 4

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW322A-02
DATE COMPLETED: 15 July 2002
DRILLING METHOD: ROTOSONIC
FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
21	cohesive, medium to coarse grained, poorly graded, grey/brown, moist							
22								
23	- trace cobbles at 22.56m BGS							
24								
25	- cemented, dry at 24.38m BGS							
26								
27								
28								
29								
30								
31								
32								
33								
34								
35								
36	- with clay, compact, moist to very moist at 35.66m BGS							
37								
38								
39	ML - SILT (TILL), trace clay, trace fine grained sand, stiff, grey, moist	358.88						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 000823-2002.GPJ CRA_CORP.GDT 1/4/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

PROJECT NUMBER: 823-02

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

LOCATION: AS PER PLAN

HOLE DESIGNATION: OW322A-02

DATE COMPLETED: 15 July 2002

DRILLING METHOD: ROTASONIC

FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
41								
42								
43								
44								
45								
46								
47	- sandy at 47.55m BGS							
48	SP - SAND, with silt, dense, slightly cohesive, medium grained, poorly graded, brown, moist to very moist	349.13						
49								
50								
51								
52	- trace silt, coarse grained at 52.43m BGS							
53								
54								
55	- interbedded silt and clay layers, 1cm thick at 54.86m BGS							
56	- silty sand, cohesive, fine grained at 56.39m BGS							
57								
58	- wet at 57.91m BGS							
59								

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 000823-2002.GPJ CRA_CORP.GDT 1/4/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 4 of 4

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW322A-02
DATE COMPLETED: 15 July 2002
DRILLING METHOD: ROTASONIC
FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
61								
62								
63								
64	- coarse grained at 64.01m BGS							
65								
66								
67								
68	ML - SILT (WATERLAID), stiff, dark grey, moist	329.01						
69								
70								
71								
72								
73								
74	ML/CL - CLAYEY SILT (TILL), trace gravel, stiff, light grey/brown, dry to moist	322.92 322.61						
75	END OF BOREHOLE @ 74.68m BGS							
76								
77								
78								
79								

WELL DETAILS
Screened interval:
332.06 to 329.01m AMSL
65.23 to 68.28m BGS
Length: 3.05m
Diameter: 51mm
Slot Size: 10
Material: STAINLESS STEEL
Material: BENTONITE CHIPS
Sand Pack:
333.59 to 328.56m AMSL
63.70 to 68.73m BGS
Material: #1 SILICA SAND

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 000823-2002.GPJ CRA CORP.GDT 1/4/04

STRATIGRAPHIC AND INSTRUMENTATION LOG

(OVERBURDEN)

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: TW30-86

PROJECT NO.: 823-50

DATE COMPLETED: AUG. 12, 1986

CLIENT: MACLAREN ENGINEERS INC.

DRILLING METHOD: ROTARY WITH MUD

LOCATION: AS PER PLAN

CRA SUPERVISOR: G. PUCOVSKY

DEPTH ft BG	STRATIGRAPHY DESCRIPTION & REMARKS	ELEVATION ft AMSL	MONITOR INSTALLATION	SAMPLE		
				N U M B E R	S T A T E	N V A L U E
0	TOPSOIL	1215.32	well cap			
10	BROWN CLAY, SILT, SAND	1212.54				
20	BROWN CLAYEY SILT (some sand)			1		
30		1182.5				
40	GRAY CLAYEY SILT TILL (minor to some sand)			2		
50						
60	GRAY CLAY, SILT, SAND	1157.5		3		
70	GRAY SILT, SAND, FINE GRAVEL	1147.5		4		
80				5		
90	GRAY FINE TO MEDIUM SAND AND GRAVEL			6		
100		1117.5		7		
110	GRAY MEDIUM TO COARSE SAND AND GRAVEL			8		
120				9		
				10		
				11		
				12		
				13		
				14		
				15		
				16		

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS

WATER FOUND

STATIC WATER LEVEL

STRATIGRAPHIC AND INSTRUMENTATION LOG

(OVERBURDEN)

PAGE 2

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: TW30-86

PROJECT NO.: 823-50

DATE COMPLETED: AUG. 12, 1986

CLIENT: MACLAREN ENGINEERS INC.

DRILLING METHOD: ROTARY WITH MUD

LOCATION: AS PER PLAN

CRA SUPERVISOR: G. PUCOVSKY

DEPTH ft BG	STRATIGRAPHY DESCRIPTION & REMARKS	ELEVATION ft AMSL	MONITOR INSTALLATION	SAMPLE		
				N U M B E R	S T A T E	'N' V A L U E
120						
130		1082.5		17		
				18		
	GRAY MEDIUM SAND,			19		
	FINE TO MEDIUM GRAVEL			20		
140				21		
				22		
150	GRAY MEDIUM SAND, FINE GRAVEL			23		
				24		
160				25		
		1045.5		26		
170	GRAY CLAYEY SILT			27		
				28		
180		1032.5		29		
	END OF HOLE @ 180 Ft BGS					
190						
200						
210						
220						
230						
240						

Screen Details

Set screen to
166 ft BGS
(EL. 1046.5 ft)

Type - Johnson
wire wound,
stainless steel
Length - 12 ft
Diameter - 6 inch
telescopic
Slot - 20 slot
(0.020 inch)

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS

WATER FOUND

STATIC WATER LEVEL



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 3

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW332-02

PROJECT NUMBER: 823-02

DATE COMPLETED: 8 August 2002

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: ROTASONIC

LOCATION: AS PER PLAN

FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE				
				NUMBER	INTERVAL	REC (m)	N' VALUE	
	TOP OF RISER GROUND SURFACE	393.59 392.70						
2	SILTY SAND (TOPSOIL), loose, fine grained, poorly graded, dark brown, moist, vegetative matter (grass, rootlets) ML/CL - SILTY CLAY (TILL), trace gravel, stiff, grey, moist	392.09	CONCRETE SEAL					
4								
6	SC - CLAYEY SAND, trace silt, soft, brown/grey, wet	388.13	51 mm SCH 80 PVC RISER PIPE					
8								
10	ML/CL - CLAYEY SILT (TILL), trace sand, trace gravel, grey, moist	384.17	BENTONITE GROUT					
12	SP - SAND, trace silt, trace clay, dense, fine grained, poorly graded, light brown, dry - with silt, grey, moist at 11.58m BGS - heavy oxidation at 12.50m BGS - silty sand, wet at 13.11m BGS	382.64	152 mm Ø BOREHOLE					
14								
16	- very hard, dry at 15.85m BGS							
18	- trace silt, trace gravel, light grey/beige at 17.68m BGS							
20								

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 2 of 3

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW332-02

PROJECT NUMBER: 823-02

DATE COMPLETED: 8 August 2002

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: ROTOSONIC

LOCATION: AS PER PLAN

FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
22								
24								
26								
28								
30	- silty, dense, brown, moist to very moist at 29.57m BGS - wet at 30.48m BGS							
32	ML - SILT (WATERLAID), with clay, firm, brown, wet	360.70						
34	- brown/grey, moist at 33.53m BGS							
36								
38	- light grey, dry at 38.10m BGS							
40	- with fine grained sand, trace clay at 39.62m BGS							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE




STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 3

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN

HOLE DESIGNATION: OW332-02
DATE COMPLETED: 8 August 2002
DRILLING METHOD: ROTOSONIC
FIELD PERSONNEL: K. PETER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
44	SM/ML - SILTY SAND, trace clay, dense, medium grained, poorly graded, light grey, wet	350.03						
46								
48								
50								
52	- moist at 51.82m BGS							
54	- wet at 54.86m BGS							
56	END OF BOREHOLE @ 56.39m BGS	336.31						
58								
60								
62								

WELL DETAILS

Screened interval:
343.63 to 340.58m AMSL
49.07 to 52.12m BGS

Length: 3.05m
Diameter: 51mm
Slot Size: 10
Material: STAINLESS STEEL
Material: BENTONITE CHIPS
Sand Pack:
344.85 to 339.36m AMSL
47.85 to 53.34m BGS
Material: #1 SILICA SAND

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 000823-2002.GPJ CRA CORP.GDT 1/4/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW338A-05

PROJECT NUMBER: 823-02

DATE COMPLETED: September 16, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO


DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
	TOP OF RISER GROUND SURFACE	384.59 383.67						
	TOPSOIL	383.21		01	PQ			
1	FILL - silt and sand, trace gravel, brown, dry to moist, occasional pieces of refuse, occasional clayey layers within increasing with depth - plastic bag at 4.57m BGS			02	PQ			
2				03	PQ			
3				04	PQ			
4				05	PQ			
5				06	PQ			
6								
7	SM - SAND (NATIVE), trace to with silt, compact, fine grained, trace stratification, brown with occasional grey layering, wet, no odour	376.66		06	PQ			
8	SP - SAND (WATERLAIN), trace silt, fine to medium grained, some stratification, brown, wet	375.44		07	PQ			
9				08	PQ			
10	- coarse sand seam at 10.36m BGS							
11	- coarse sand seam at 10.97m BGS							
12	SW - SAND (WATERLAIN), with gravel to and gravel, trace silt, fine to coarse grained, stratified, grey/brown, wet	372.39		09	PQ			
13	ML/SM - SILT AND SAND (TILL), with gravel and clay, stiff, fine grained sand, till structure with sand and gravel seams, buff to brown, wet	371.47						
14	- drilling fluid lost to formation from 13.14 to 15.62m BGS	370.56		10	PQ			
15	GW - GRAVEL (WATERLAIN), with sand, coarse grained gravel,			11	PQ			
16	SM/SP - SAND (WATERLAIN), with silt, fine to medium grained sand, stratified, brown and grey, wet, no odour	368.05		12	PQ			
17	- coarse sand from 17.07 to 19.20m BGS				PQ			

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2005).GPJ CRA CORP.GDT 3/27/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 2 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW338A-05

PROJECT NUMBER: 823-02

DATE COMPLETED: September 16, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
19	- medium sand from 19.20 to 20.42m BGS			13	PQ			
20				14	PQ			
21	- medium sand with coarse sand from 20.42 to 21.03m BGS			15	PQ			
21	- silt and clay seam from 20.73 to 20.80m BGS	362.64		16	PQ			
22	ML/CL - SILT AND CLAY (TILL), trace sand and gravel, firm, medium plasticity, massive, buff, very moist to wet	361.93		17	PQ			
22	SW/GW - SAND AND GRAVEL (WATERLAIN), medium to coarse grained, some stratification, grey			18	PQ			
23	- coarser with depth, coarse gravel and cobbles from 23.16 to 24.08m BGS			19	PQ			
24		359.59		20	PQ			
25	SM/SP - SILTY SAND (WATERLAIN), fine to medium grained sand, stratified/laminated, layers of fine to medium sand apparent, light/brown grey, coarsening upward, grey, wet			21	PQ			
26			BENTONITE GROUT	22	PQ			
27			122 mm Ø BOREHOLE	23	PQ			
28			51 mm Ø SCH 80 PVC RISER PIPE	24	PQ			
29				25	PQ			
30				26	PQ			
31				27	PQ			
32					PQ			
33					PQ			
34					PQ			
35					PQ			

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW338A-05

PROJECT NUMBER: 823-02

DATE COMPLETED: September 16, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
37				28	PQ			
38				29	PQ			
39	SP - SAND (WATERLAIN), primarily medium grained sand, occasionally silty, brown, saturated	345.26		30	PQ			
40			122 mm Ø BOREHOLE	31	PQ			
41			BENTONITE GROUT	32	PQ			
42	SM - SILTY SAND (WATERLAIN) fine grained sand, laminated, brown/grey, wet, coarsening with depth	341.60		33	PQ			
43			51 mm Ø SCH 80 PVC RISER PIPE	34	PQ			
44				35	PQ			
45	- trace silt, medium grained sand, becoming SP, coarsening downward at 45.11m BGS			36	PQ			
46				37	PQ			
47	- trace to with silt, fining downward at 46.63m BGS			38	PQ			
48				39	PQ			
49	ML - SANDY SILT (WATERLAIN), firm, fine grained, low plasticity, dilatant, grey, saturated	334.59						
50								
51								
52	SP - SAND (WATERLAIN), with silt, fine grained sand, some stratification, grey, saturated	331.85	BENTONITE GRAVEL					
53	- no sample recovery, suspected fine sand (sampler problem) from 52.12 to 55.17m BGS							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 4 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW338A-05

PROJECT NUMBER: 823-02

DATE COMPLETED: September 16, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO


DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
55	- fine to medium grained sand, trace to with silt from 55.17 to 56.69m BGS			40	PQ			
56				41	PQ			
57	ML - SILT (WATER LAIN), trace to with fine sand, stiff to hard, low plasticity, some laminations, grey, coarsening downwards	326.97		42	PQ			
58	- buff clay seam, hard, high plasticity from 57.61 to 57.66m BGS			43	PQ			
59	- buff clay seam, hard, high plasticity from 57.91 to 57.99m BGS	325.45		44	PQ			
60	SM/ML - SAND AND SILT (WATERLAIN), fine grained sand, stratified, grey, saturated			45	PQ			
61	- buff clay seam, hard, high plasticity from 59.13 to 59.18m BGS							
62	ML/CL - SILT AND CLAY (MARYHILL TILL), trace sand and gravel, very stiff, medium plasticity, massive, grey, saturated	322.71						
63	END OF BOREHOLE @ 62.94m BGS	320.73						
64								
65								
66								
67								
68								
69								
70								
71								

WELL DETAILS

Screened interval:

330.02 to 326.97m AMSL

53.64 to 56.69m BGS

Length: 3.05m

Diameter: 51mm

Slot Size: 8

Material: STAINLESS STEEL

Seal:

332.46 to 331.55m AMSL

51.21 to 52.12m BGS

Material: BENTONITE GRAVEL

Sand Pack:

331.55 to 320.73m AMSL

52.12 to 62.94m BGS

Material: #00 SILICA SAND

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW337A-05

PROJECT NUMBER: 823-02

DATE COMPLETED: October 4, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO


DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE						
				NUMBER	INTERVAL	REC (m)	'N' VALUE			
	TOP OF RISER GROUND SURFACE	377.73 376.77								
	TOPSOIL									
1	SM/ML - SILTY SAND, compact, fine grained sand, medium brown, moist	376.46		01	PQ					
2	ML - SILT (TILL), with fine sand to sandy, trace gravel and clay, stiff, low plasticity, some fractures, light brown, moist	375.55		02	PQ					
3	SM - SAND (TILL), trace gravel and clay, dense, brown, moist	373.72		03	PQ					
				04	PQ					
4				05	PQ					
5	ML - SILT (TILL), with fine grained sand, trace to with gravel and clay, stiff to hard, massive with some fractures, grey, low available moisture	371.28		06	PQ					
6										
7				07	PQ					
8										
9				08	PQ					
10										
11				09	PQ					
12										
13	SW/GW - SAND AND GRAVEL (WATERLAIN), fine to grained, well graded, grey, moist	364.57		10	PQ					
				11	PQ					
14	ML/CL - CLAYEY SILT (TILL), with fine grained sand, trace gravel, stiff to hard, low plasticity, massive, grey, low available moisture	363.05								
15										
16			12	PQ						
17			13	PQ						
			14	PQ						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2005).GPJ CRA CORP.GDT 3/27/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 2 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW337A-05

PROJECT NUMBER: 823-02

DATE COMPLETED: October 4, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	N' VALUE	
19				15	PQ			
20				16	PQ			
21	SM/ML - SAND AND SILT, firm to stiff, fine grained sand, light brown, moist, till-like structure in part	356.34		17	PQ			
22	- becoming coarser, trace to with gravel at 21.34m BGS			18	PQ			
23	- thin sand seams within from 22.86 to 23.47m BGS			19	PQ			
24	SP/SM - SAND (WATERLAIN), trace to with silt, fine to medium grained sand, stratified, layers of clean medium sand to very fine sand and silt, laminations apparent in finer layers, moist	353.30		20	PQ			
25				21	PQ			
26				22	PQ			
27				23	PQ			
28	SM - SILTY SAND (WATERLAIN), very fine grained sand, laminated, stratified, grey-brown, moist to wet	349.33		24	PQ			
29	- saturated, slightly coarse matrix with depth starting at 28.96m BGS			25	PQ			
30				26	PQ			
31								
32								
33	SP - SAND (WATERLAIN), trace silt, fine to medium grained sand, stratified, grey, saturated	344.46						
34	SM - SILTY SAND (WATERLAIN), very fine grained sand, laminated, stratified, grey-brown, moist to wet	343.24						
35								

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2005) GPJ CRA CORP.GDT 3/27/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW337A-05

PROJECT NUMBER: 823-02

DATE COMPLETED: October 4, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
37			122 mm Ø BOREHOLE		PQ			
38			BENTONITE GROUT	27	PQ			
39		337.75		28	PQ			
40	SM/SP - SAND (WATERLAIN), trace silt to silty, fine to medium grained sand, stratified/laminated, grey, saturated		51 mm Ø SCH 80 PVC RISER PIPE	29	PQ			
41				30	PQ			
42			BENTONITE GRAVEL	31	PQ			
43				32	PQ			
44				33	PQ			
45		331.35	#00 SILICA SAND	34	PQ			
46	SP - SAND (WATERLAIN), trace silt, fine-medium to medium grained sand, stratified, laminated, grey, occasional layer oxidation stained, saturated		51 mm Ø STAINLESS STEEL WELL SCREEN	35	PQ			
47								
48		328.61						
49	ML/CL - SILT AND CLAY (MARYHILL TILL), trace sand and gravel, hard, medium plasticity, massive, grey							
50								
51	END OF BOREHOLE @ 50.39m BGS	326.38						
52								
53								

WELL DETAILS

Screened interval:

331.96 to 328.91m AMSL

44.81 to 47.85m BGS

Length: 3.05m

Diameter: 51mm

Slot Size: 8

Material: STAINLESS STEEL

Seal:

335.01 to 333.48m AMSL

41.76 to 43.28m BGS

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 4 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW337A-05

PROJECT NUMBER: 823-02

DATE COMPLETED: October 4, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	N' VALUE	
55			Material: BENTONITE GRAVEL Sand Pack: 333.48 to 328.91m AMSL 43.28 to 47.85m BGS Material: #00 SILICA SAND					
56								
57								
58								
59								
60								
61								
62								
63								
64								
65								
66								
67								
68								
69								
70								
71								

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2005).GPJ CRA CORP.GDT 3/27/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 3

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN
DRILLING CONTRACTOR: ALLTERRAIN DRILLING

HOLE DESIGNATION: OW337B-05
DATE COMPLETED: October 6, 2005
DRILLING METHOD: PQ CORING
FIELD PERSONNEL: B. KEMPEL
DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE			
				NUMBER	INTERVAL	REC (m)	N' VALUE
	TOP OF RISER GROUND SURFACE	377.73 376.82	CONCRETE SEAL 122 mm Ø BOREHOLE BENTONITE GROUT 51 mm Ø SCH 80 PVC RISER PIPE				
	TOPSOIL	376.51					
1	SM/ML - SILTY SAND, compact, fine grained sand, medium brown, moist	375.60					
2	ML - SILT (TILL), with fine sand to sandy, trace gravel and clay, stiff, low plasticity, some fractures, light brown, moist	373.77					
3	SM - SAND (TILL), trace gravel and clay, dense, brown, moist	371.33					
4							
5							
6	ML - SILT (TILL), with fine grained sand, trace to with gravel and clay, stiff to hard, massive with some fractures, grey, low available moisture	364.62					
7							
8							
9							
10							
11							
12	SW/GW - SAND AND GRAVEL (WATERLAIN), fine to grained, well graded, grey, moist	363.10					
13							
14	ML/CL - CLAYEY SILT (TILL), with fine grained sand, trace gravel, stiff to hard, low plasticity, massive, grey, low available moisture						
15							
16							
17							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2005) GPJ CRA CORP.GDT 3/27/08



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 2 of 3

PROJECT NAME: WATERLOO LANDFILL SITE
PROJECT NUMBER: 823-02
CLIENT: REGIONAL MUNICIPALITY OF WATERLOO
LOCATION: AS PER PLAN
DRILLING CONTRACTOR: ALLTERRAIN DRILLING

HOLE DESIGNATION: OW337B-05
DATE COMPLETED: October 6, 2005
DRILLING METHOD: PQ CORING
FIELD PERSONNEL: B. KEMPEL
DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE			
				NUMBER	INTERVAL	REC (m)	N' VALUE
19							
20							
21	SM/ML - SAND AND SILT, firm to stiff, fine grained sand, light brown, moist, till-like structure in part - becoming coarser, trace to with gravel at 21.34m BGS	356.39					
22							
23	- thin sand seams within from 22.86 to 23.47m BGS						
24	SP/SM - SAND (WATERLAIN), trace to with silt, fine to medium grained sand, stratified, layers of clean medium sand to very fine sand and silt, laminations apparent in finer layers, moist	353.35					
25							
26							
27							
28	SM - SILTY SAND (WATERLAIN), very fine grained sand, laminated, stratified, grey-brown, moist to wet	349.38					
29	- saturated, slightly coarse matrix with depth starting at 28.96m BGS						
30							
31							
32							
33	SP - SAND (WATERLAIN), trace silt, fine to medium grained sand, stratified/laminated, grey, saturated	344.51					
34	SM - SILTY SAND (WATERLAIN), very fine grained sand, laminated, stratified, grey-brown, moist to wet	343.29					
35							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2005) GPJ CRA CORP GDT 3/27/08



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 3

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW337B-05

PROJECT NUMBER: 823-02

DATE COMPLETED: October 6, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE			
				NUMBER	INTERVAL	REC (m)	'N' VALUE
			 SCREEN				
37	END OF BOREHOLE @ 36.58m BGS	340.24	<u>WELL DETAILS</u> Screened interval: 343.29 to 340.24m AMSL 33.53 to 36.58m BGS Length: 3.05m Diameter: 51mm Slot Size: 8 Material: STAINLESS STEEL Seal: 346.34 to 344.81m AMSL 30.48 to 32.00m BGS Material: BENTONITE GRAVEL Sand Pack: 344.81 to 340.24m AMSL 32.00 to 36.58m BGS Material: #00 SILICA SAND				
38	STRATIGRAPHY FROM NESTED WELL OW337A-05						
39							
40							
41							
42							
43							
44							
45							
46							
47							
48							
49							
50							
51							
52							
53							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG: 823-02 (2005).GPJ CRA CORP.GDT 3/27/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW336-05

PROJECT NUMBER: 823-02

DATE COMPLETED: September 29, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
	TOP OF RISER GROUND SURFACE	391.19 390.41						
	TOPSOIL	390.11						
1	ML - SILT (POSSIBLE FILL), with sand and gravel, trace clay, firm to stiff, low plasticity, brown, moist	389.19		01	PQ			
	SM/ML - SAND AND SILT (WATERLAIN), firm, fine grained, fine stratified, brown, moist	388.58		02	PQ			
2	ML - SILT (WATERLAIN), with fine sand and clay, very stiff, low plasticity, some laminations, brown, moist			03	PQ			
3		387.36		04	PQ			
4	SM/ML - SAND AND SILT (TILL), with gravel and clay, occasional cobbles, firm to stiff, variable structure and stoniness, brown, very moist, some water modification evident, majority of till is fine grained sand			05	PQ			
5				06	PQ			
6				07	PQ			
7				08	PQ			
8	- some alternating layers of silt and sand till with variable strength and gravel contents at 7.62m BGS			09	PQ			
9				10	PQ			
10				11	PQ			
11				12	PQ			
12		378.22		13	PQ			
13	ML - SILT (TILL), with sand to sandy, with gravel, trace clay, stiff, massive, light brown/buff, moist to wet			14	PQ			
14				15	PQ			
15				16	PQ			
16				17	PQ			
17	ML/SM - SILT AND SAND (WATERLAIN), trace gravel, firm, fine grained sand, partially laminated, light brown/buff, moist, till structure occasionally apparent, coarser with depth	373.65						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2005), GPJ CRA CORP GDT 3/27/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 2 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW336-05

PROJECT NUMBER: 823-02

DATE COMPLETED: September 29, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	N' VALUE	
19					PQ			
20	SP - SAND (WATERLAIN), trace silt, trace gravel, medium grained, poorly graded, gray/brown, moist, fining upwards - with gravel to gravelly from 20.57 to 22.10m BGS	370.90		14	PQ			
21				15	PQ			
22	- fine to medium gravel from 22.10 to 22.86m BGS			16	PQ			
23	SW/GW - SAND AND GRAVEL (WATERLAIN), medium to coarse grained, well graded, grey, moist	367.55		17	PQ			
24				18	PQ			
25	SW - SAND (WATERLAIN), trace to with gravel, medium coarse grained, variable to well graded, grey, moist to wet	366.03		19	PQ			
26				20	PQ			
27				21	PQ			
28	SW/GW - SAND AND GRAVEL (WATERLAIN), medium to coarse grained, well graded, grey, moist	362.98		22	PQ			
29				23	PQ			
30	SW - SAND (WATERLAIN), trace to with gravel, medium coarse grained, variable to well graded, grey, moist to wet	361.45		24	PQ			
31				25	PQ			
32								
33								
34								
35	ML - SILT (LACUSTRIAN), trace to fine sand, trace clay, firm to stiff, low plasticity, some laminations, brown, moist	356.27						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2005).GPJ CRA CORP.GDT 3/27/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW336-05

PROJECT NUMBER: 823-02

DATE COMPLETED: September 29, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO


DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	'N' VALUE	
37	SM/ML - SAND AND SILT (LACUSTRIAN?), fine sand, stratified/laminated, brown, wet, alternating layers of predominantly fine sand or silt	353.83		26	PQ			
38	- orange oxidized seam from 38.13 to 38.19m BGS	352.31			PQ			
39	SP/SM - SAND (WATERLAIN), trace to with silt, fine to medium grained sand, coarsening upward, grey, wet			27	PQ			
40				28	PQ			
41	SP - SAND (WATERLAIN), trace to with silt, fine to medium grained, grey, saturated	349.26		29	PQ			
42				30	PQ			
43				31	PQ			
44				32	PQ			
45				33	PQ			
46				34	PQ			
47				35	PQ			
48				36	PQ			
49					PQ			

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 4 of 4

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW336-05

PROJECT NUMBER: 823-02

DATE COMPLETED: September 29, 2005

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO


DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B. KEMPEL

DRILLING CONTRACTOR: ALLTERRAIN DRILLING

DRILLER

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITORING WELL	SAMPLE				
				NUMBER	INTERVAL	REC (m)	N' VALUE	
55	SM - SILTY SAND, to and silt, very fine sand, grey, wet	335.55	 BENTONITE GRAVEL #00 SILICA SAND 51 mm Ø STAINLESS STEEL WELL SCREEN BENTONITE GRAVEL	37	PQ			
56				38	PQ			
57	SP - SAND (WATERLAIN), trace to with silt, fine to medium grained, grey, saturated	334.02		39	PQ			
58				40	PQ			
59	- slightly coarse matrix, fine to medium sand, trace silt at 58.83m BGS			41	PQ			
60				42	PQ			
61				43	PQ			
62				44	PQ			
63	ML/CL - CLAYEY SILT (MARYHILL TILL), occasionally to and clay, trace fine sand, hard, low to medium plasticity, massive with some fractures, evidence of some lamination, grey	327.32						
64								
65	END OF BOREHOLE @ 64.92m BGS	325.49						
66			WELL DETAILS Screened interval: 331.58 to 328.54m AMSL 58.83 to 61.87m BGS Length: 3.05m Diameter: 51mm Slot Size: 8 Material: STAINLESS STEEL Seal: 334.63 to 333.11m AMSL 55.78 to 57.30m BGS Material: BENTONITE GRAVEL Sand Pack: 333.11 to 325.49m AMSL 57.30 to 64.92m BGS Material: #00 SILICA SAND					
67								
68								
69								
70								
71								

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-02 (2005).GPJ CRA CORP.GDT 3/27/06



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 1 of 5

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW333-04

PROJECT NUMBER: 823-02

DATE COMPLETED: 20 April 2004

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B.IOTZOV

DRILLING CONTRACTOR: LANTECH DRILLING SERVICES

DRILLER: MIKE SOKOLOV

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (%)	'N' VALUE
	TOP OF RISER GROUND SURFACE	370.07 369.26					
0.5	SM-SAND, with silt, loose to compact, fine to medium grained, massive, poorly to moderately well graded, brown, moist			1		0	-
1.0							
1.5							
2.0							
2.5							
3.0	GM-GRAVEL AND SAND, with silt, compact, fine to coarse grained, very poorly graded, brown, wet	366.36		2		0	-
3.5							
4.0							
4.5				3		10	-
5.0							
5.5							
6.0	CL/ML-CLAY AND SILT TO SILTY CLAY (TILL), trace fine gravel and coarse sand, stiff to very stiff, medium plasticity, subtle fine lamination, brown, moist	363.66		4		60	-
6.5	- grey at 5.80m BGS	363.09					
6.5	SM/ML-SAND AND SILT, lense, loose to compact, fine to medium grained, grey, moist to wet	362.88					
7.0	CL-CLAY (TILL), stiff, low plasticity, crumbly texture, grey, wet	362.61					
7.5	SM-SAND, with silt, compact, medium grained, poorly graded, fine stratified (laminated), grey, saturated	362.10		5		95	-
8.0	ML-SILT(TILL), with clay, with to trace coarse sand and fine gravel, very stiff, medium plasticity, grey, wet, upper and lower contacts are gradational (across 5 cm)	361.41					
8.5	SM-SAND, with silt, compact, medium grained, poorly graded, grey, moist to wet, fine stratified (laminated)						
9.0	- gravelly sand lense from 9.00 to 9.10m BGS			6		70	-
9.5							
	ML-SILT(TILL), trace clay, with gravel (in lenses),	359.56					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-2004 GPJ CRA CORP GDT 18/8/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 2 of 5

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW333-04

PROJECT NUMBER: 823-02

DATE COMPLETED: 20 April 2004

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B.IOTZOV

DRILLING CONTRACTOR: LANTECH DRILLING SERVICES

DRILLER: MIKE SOKOLOV

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (%)	"N" VALUE
10.5	stiff, low plasticity, massive, grey, moist - gravelly lense from 10.43 to 10.60m BGS			7		60	-
11.0		358.16					
11.5	SM-SAND, with silt, compact, medium grained, fine stratified (laminated), poorly graded, grey, moist (saturated in places or locally saturated) - silty sand, lense, loose, very fine grained, massive, saturated, grey from 11.40 to 11.52m BGS			8		75	-
12.0	- silt, with clay, lense, stiff, crumbly texture (desiccation texture), wet, low plasticity from 11.56 to 11.64m BGS						
12.5		356.76					
13.0	ML-SANDY SILT (TILL), with gravel, with to trace clay, hard, low to moderate plasticity, moderately graded, stratified, grey, moist, clay till clasts	356.46					
13.5	ML/CL-CLAYEY SILT, with trace fine sand, stiff, low to medium plasticity, laminated, crumbly desiccation texture, grey, moist, increasing silt and sand content with depth, gradational lower contact	356.10		9		75	-
14.0	ML-SANDY SILT (TILL), with gravel, with to trace clay, hard, low to moderate plasticity, moderately graded, stratified, grey, moist, clay till clasts						
14.5	CL-SILTY CLAY (TILL), very stiff, medium plasticity, grey, moist to wet	355.06					
	ML-SILT, with fine sand, saturated	354.66					
15.0	ML/SM-SILT AND SAND (TILL), loose to compact, fine to medium grained sand, grey, wet to saturated	354.51		10		60	-
15.5	CL-CLAY (TILL), with silt, with to trace gravel, stiff, medium plasticity, faint stratified (laminated), grey, wet	354.16	51 mm SCH 80 PVC RISER PIPE				
16.0	CL/ML-CLAY AND SILT (TILL), with very fine sand and gravel, stiff to hard, low plasticity, grey, moist - some very thin laminae (1mm) from 15.95 to 16.45m BGS	353.76	BENTONITE GROUT	11		100	-
16.5							
17.0			122 mm Ø BOREHOLE				
17.5	- sandy lense from 17.42 to 17.50m BGS			12		100	-
18.0							
18.5		350.66					
19.0	SW-SAND, with gravel, loose, coarse grained, well graded, massive, grey, moist	350.26					
19.5	ML-SILT (TILL), with clay, with to trace gravel and sand, stiff, low plasticity, fine stratified to laminated, grey, moist - sand lense from 19.21 to 19.26m BGS	349.81		13		95	-
	ML/SM-SILT AND SAND, loose, fine grained, massive, grey, saturated	349.56					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-2004.GPJ CRA CORP.GDT 18/8/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 3 of 5

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW333-04

PROJECT NUMBER: 823-02

DATE COMPLETED: 20 April 2004

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO


DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B.IOTZOV

DRILLING CONTRACTOR: LANTECH DRILLING SERVICES

DRILLER: MIKE SOKOLOV

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (%)	"N" VALUE
20.5	ML-SILT (TILL), with clay, with to trace gravel and sand, stiff, low plasticity, fine stratified to laminated, grey, moist	349.26		14		60	-
	ML/SM-SILT AND SAND, loose, fine grained, faintly fine stratified (laminated), grey, saturated	348.66					
21.0	ML-CLAYEY SILT (TILL), with to trace fine gravel and sand, stiff, low plasticity, grey, wet	348.46					
	ML/SM-SILT AND SAND, loose, fine grained, grey, saturated	348.21					
21.5	ML-SILT (TILL), with clay, stiff, low plasticity, grey, moist			15		60	-
22.0	- gravelly, sand seams from 21.60 to 22.00m BGS						
	ML/SM-SILT AND SAND, loose, fine grained, grey, saturated	346.96					
22.5							
23.0	ML/CL-SILT AND CLAY (TILL), stiff to very stiff, low plasticity, massive to fine stratified (laminated), grey, moist	346.31		16		60	-
23.5	SM-SAND, with silt, poorly graded, fine stratified, laminated, grey, moist	345.96					
	ML/CL-SILT AND CLAY (TILL), stiff, low plasticity, grey, moist	345.66					
24.0	ML/SM-SILT AND SAND, loose, fine grained, grey, moist	345.41					
	ML/CL-SILT AND CLAY (TILL), trace fine gravel, stiff to very stiff (locally), low plasticity, massive, grey, dry to moist	345.06		17		55	-
24.5							
25.0							
25.5							
26.0	SM-SAND, with silt to silty (with depth), loose, poorly graded, medium to fine grained sand, fine stratified, grey, moist, gradational lower contact	343.16		18		80	-
26.5							
27.0	ML/CL-SILT AND CLAY (TILL), stiff to very stiff, low plasticity, some lamination, grey, moist to wet, silt content increasing with depth	342.44					
27.5							
28.0	- boulder from 28.30 to 28.40m BGS			19		95	-
28.5	SM/ML-SAND AND SILT (TILL), compact, poorly graded, fine to medium grained, massive, grey, moist to wet	340.86					
29.0							
29.5	GM/SM-GRAVEL AND SAND (TILL), with silt, with clay, compact, coarse grained (cobble), very well graded, grey, wet	339.86					

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-2004.GPJ CRA CORP GDT 18/8/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 4 of 5

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW333-04

PROJECT NUMBER: 823-02

DATE COMPLETED: 20 April 2004

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B.IOTZOV

DRILLING CONTRACTOR: LANTECH DRILLING SERVICES

DRILLER: MIKE SOKOLOV

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE			
				NUMBER	INTERVAL	REC (%)	'N' VALUE
30.5							
31.0				21		30	-
31.5				21.5		0	-
32.0			BENTONITE GROUT				
32.5				22		50	-
33.0							
33.5							
34.0				23		25	-
34.5	SP-SAND, loose to compact, medium to coarse grained, poorly graded, stratified (fine to medium bedded), mostly massive, grey, wet	334.76					
35.0							
35.5				24		60	-
36.0							
36.5							
37.0			SAND PACK				
37.5	- medium to coarse grained from 37.30 to 37.85m BGS			25		75	-
38.0	- medium grained from 37.85 to 39.65m BGS		WELL SCREEN				
38.5							
39.0				26		90	-
39.5	- medium to coarse grained from 39.65 to 39.85m BGS						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-2004 GPJ CRA CORP.GDT 18/8/04



STRATIGRAPHIC AND INSTRUMENTATION LOG (OVERBURDEN)

Page 5 of 5

PROJECT NAME: WATERLOO LANDFILL SITE

HOLE DESIGNATION: OW333-04

PROJECT NUMBER: 823-02

DATE COMPLETED: 20 April 2004

CLIENT: REGIONAL MUNICIPALITY OF WATERLOO

DRILLING METHOD: PQ CORING

LOCATION: AS PER PLAN

FIELD PERSONNEL: B.IOTZOV

DRILLING CONTRACTOR: LANTECH DRILLING SERVICES

DRILLER: MIKE SOKOLOV

DEPTH m BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. m AMSL	MONITOR INSTALLATION	SAMPLE				
				NUMBER	INTERVAL	REC (%)	'N' VALUE	
40.5	- medium grained from 39.85 to 39.95m BGS - medium to coarse grained from 39.95 to 40.70m BGS			27		85	-	
41.0	- very coarse grained from 40.70 to 40.80m BGS - medium to coarse grained from 40.80 to 41.00m BGS							
41.5	- medium grained from 41.00 to 41.40m BGS - fine to medium grained from 41.40 to 41.50m BGS - medium grained from 41.50 to 42.40m BGS			28		85	-	
42.0								
42.5	- medium to coarse grained from 42.40 to 42.80m BGS							
43.0	CL-CLAY (MARY HILL TILL), with silt, trace gravel, stiff to very stiff, low plasticity, laminated, grey, dry to moist	326.31		29		75	-	
43.5								
44.0	END OF BOREHOLE @ 44.00m BGS	325.26						
44.5								
45.0								
45.5								
46.0								
46.5								
47.0								
47.5								
48.0								
48.5								
49.0								
49.5								

WELL DETAILS

Screened interval:

332.73 to 329.72m AMSL

36.53 to 39.54m BGS

Length: 3.01m

Diameter: 2mm

Slot Size: 8

Material: STAINLESS STEEL

Sand Pack:

334.61 to 329.41m AMSL

34.65 to 39.85m BGS

Material: #00 SILICA SAND

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

OVERBURDEN LOG 823-2004 GPJ CRA CORP GDT 18/8/04



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix C

Monitoring Data (Pumped Volumes and Hydrographs)




TABLE C-1
WELL FIELD WATER PRODUCTION SUMMARY
REGION OF WATERLOO - 2025 GROUNDWATER MONITORING REPORT




Well Field	Major or Minor Supply	Production Well Name	Permit to Take Water Details			2021 Production Summary			2022 Production Summary			2023 Production Summary			2024 Production Summary			2025 Production Summary		
			MOE Permit Number ¹	Permitted Capacity (total m ³ /year)*	Permitted Rate (L/s)*	Total Production Well Volume (total m ³ /year)	Average Daily Rate (m ³ /day)	Average Rate (L/s)	Total Production Well Volume (total m ³ /year)	Average Daily Rate (m ³ /day)	Average Rate (L/s)	Total Production Well Volume (total m ³ /year)	Average Daily Rate (m ³ /day)	Average Rate (L/s)	Total Production Well Volume (total m ³ /year)	Average Daily Rate (m ³ /day)	Average Rate (L/s)	Total Production Well Volume (total m ³ /year)	Average Daily Rate (m ³ /day)	Average Rate (L/s)
Erb Street	Major	W6B W6C W7 W8	1541-AWGPZR	1,672,459	53.0	353,540	969	11.2	218,307	598	6.9	58,828	161	1.9	585,874	1,605	18.6	508,799	1,394	16.1
			1541-AWGPZR	2,031,444	64.4	0	0	0	0	0	0	88,257	242	2.8	931,606	2,552	29.5	621,262	1,702	19.7
			1541-AWGPZR	3,345,444	106.1	2,732,706	7,487	86.7	2,696,994	7,389	85.5	2,574,478	7,053	81.6	2,409,089	6,600	76.4	2,501,309	6,853	79.3
			1541-AWGPZR	3,823,214	121.2	472,955	1,296	15.0	543,653	1,489	17.2	635,594	1,741	20.2	492,894	1,350	15.6	500,312	1,371	15.9
			Well Field Total	10,872,562	344.8	3,559,201	9,751	112.9	3,458,954	9,477	109.7	3,357,157	9,198	106.5	4,419,463	12,108	140.1	4,131,682	11,320	131.0
			*Combined taking from all wells not to exceed annual daily average of 17,272,800 L/day																	




REGION OF WATERLOO
2025 GROUNDWATER MONITORING REPORT -
ERB STREET






REGION OF WATERLOO
2025 GROUNDWATER MONITORING REPORT -
ERB STREET




REGION OF WATERLOO
2025 GROUNDWATER MONITORING REPORT -
ERB STREET




REGION OF WATERLOO
2025 GROUNDWATER MONITORING REPORT -
ERB STREET



REGION OF WATERLOO
2025 GROUNDWATER MONITORING REPORT -
ERB STREET




REGION OF WATERLOO
2025 GROUNDWATER MONITORING REPORT -
ERB STREET




REGION OF WATERLOO
2025 GROUNDWATER MONITORING REPORT -
ERB STREET

Actual versus Mean Monthly Precipitation
Weather Station - University of Waterloo Weather Station




Monthly Total Pumped Volumes
ERB STREET WELL FIELD



ERB STREET WELL FIELD

Current Measure Method
(E) - Electronic Datalogger
(M) - Manual





BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix D

Precipitation Data

Table D-1
Precipitation Variation from Average
Region of Waterloo - 2025 Groundwater Monitoring Report

Year	Kitchener/Waterloo Weather Station Established 1966		
	Annual Precipitation (mm)	30-yr NORMAL Precipitation 1981-2010 (mm)	Difference (mm)
2016	748	851	-103
2017	818	851	-33
2018	749	851	-102
2019	695	851	-156
2020	689	851	-162
2021	772	851	-79
2022	438	851	-413
2023	813	851	-38
2024	874	851	23
2025	723	851	-128

Year	University of Waterloo Station Established 1988		
	Annual Precipitation (mm)	Average Precipitation 1998-2024 (mm)	Difference (mm)
2016	891	871	20
2017	989	871	118
2018	950	871	79
2019	923	871	52
2020	953	871	82
2021	1022	871	151
2022	578	871	-293
2023	959	871	88
2024	763	871	-108
2025	943	871	72

Year	Shand Dam Established 1939		
	Annual Precipitation (mm)	Average Precipitation 1940-2025 (mm)	Difference (mm)
2016	976	926	50
2017	1093	926	167
2018	849	926	-77
2019	1081	926	155
2020	1017	926	91
2021	876	926	-50
2022	798	926	-128
2023	1015	926	89
2024	994	926	68
2025	995	926	69

Year	Conestogo Dam Established 1961		
	Annual Precipitation (mm)	Average Precipitation 1961-2025 (mm)	Difference (mm)
2016	983	990	-7
2017	1210	990	220
2018	962	990	-28
2019	992	990	2
2020	1021	990	31
2021	975	990	-15
2022	907	990	-83
2023	1053	990	63
2024	972	990	-18
2025	1025	990	35

Year	Woolwich Dam Established 1960		
	Annual Precipitation (mm)	Average Precipitation 1960-2025 (mm)	Difference (mm)
2016	844	835	9
2017	986	835	151
2018	869	835	34
2019	824	835	-11
2020	862	835	27
2021	649	835	-186
2022	668	835	-167
2023	859	835	24
2024	793	835	-42
2025	732	835	-103

Year	Shade's Mills Dam Established 1960		
	Annual Precipitation (mm)	Average Precipitation 1960-2025 (mm)	Difference (mm)
2016	934	909	24
2017	1092	909	183
2018	1042	909	133
2019	1059	909	150
2020	848	909	-62
2021	1020	909	111
2022	682	909	-227
2023	982	909	73
2024	976	909	67
2025	895	909	-14

Year	Laurel Dam Established 1960		
	Annual Precipitation (mm)	Average Precipitation 1960-2025 (mm)	Difference (mm)
2016	985	938	47
2017	1062	938	124
2018	1071	938	133
2019	940	938	2
2020	938	938	0
2021	1027	938	89
2022	689	938	-249
2023	921	938	-17
2024	907	938	-31
2025	894	938	-44


Year	Roseville Weather Station Established 1972		
	Annual Precipitation (mm)	30-yr NORMAL Precipitation 1981-2010 (mm)	Difference (mm)
2016	899	919	-20
2017	882	919	-37
2018	905	919	-14
2019	957	919	38
2020	817	919	-102
2021	832	919	-87
2022	637	919	-282
2023	945	919	26
2024	856	919	-63
2025	786	919	-133

NOTES:

WIA station data is not subject to review by the National Climate Archives, therefore, undergoes very limited quality checking.
 GRCA Dam stations data is not reviewed extensively and undergoes limited quality checking.

Region of Waterloo – 2025 Groundwater Monitoring Report

Figure D.1
Laurel Creek Dam
Monthly Precipitation





BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix E

Monitoring Program Overview

GROUNDWATER LEVEL MONITORING PROGRAM PROCEDURES

E.1 Overview

The Region of Waterloo (Region) collects water level measurements at specific monitoring wells to ensure sustainable long-term water supply and to meet monitoring and reporting requirements for the Region's water-taking permits. The goal of the program is to manage and protect the Region's groundwater supply and to assess the potential impact of municipal pumping on the groundwater and surface water resources in the Region. The ongoing collection and assessment of groundwater level data is integral to assess any changes to the water resources that may occur due to pumping.

E.1.1 Production Well Pumping and Water Levels

In 2023 the Region managed approximately 132 production wells with status defined as:

- Commissioned – Active wells
- New Not-Commissioned – Well are inactive or locked out until future demand or repairs/maintenance of other wells requires activating them

The well fields are referred to as Urban (Kitchener, Waterloo, and Cambridge) and Rural (North Dumfries, Woolwich, Wilmot, and Wellesley). Well fields in Kitchener, Waterloo, and Cambridge are referred to as the Integrated Urban System (IUS).

The Region's active production wells are monitored through the Region's SCADA (Supervisory Control and Data Acquisition) system, which reads and records the volume pumped on a daily basis. A few wells do not have their own meter but are combined with other nearby well(s) in the well field and the combined flow is divided into a record for each source. Water level measurements are obtained from the production wells where required. All manual measurements are obtained using either an air line or a water level tape.

E.1.2 Monitoring Wells and Surface Water levels

Water levels are measured at monitoring wells and at some surface water features. The objective of this monitoring is to collect data to ensure that the Region's water taking has minimal impact on the environment and on private water takers.

Water levels in the Region's monitoring wells are measured either electronically or manually. Most of the wells that are monitored electronically use datalogger equipment manufactured by *In-Situ Inc.*® LevelTROLLs® and RuggedTROLLs®, as well as, by *Van Essen Instruments (formerly Schlumberger Water Services)* Mini-Divers®, Micro-Divers®, and TD-Divers®; or by *Solinst*® Levelloggers®. The datalogger pressure sensor models used may be either vented (gauged) or non-vented (absolute) for *In-Situ Inc.*®; whereas, for *Van Essen Instruments* and for *Solinst*®, non-vented (absolute) models are used. Barometric dataloggers by each manufacturer suspended in select well locations are also used with the non-vented (absolute) models to provide the required barometric pressure compensation necessary in producing the water level data. Manual monitoring is done using a *Solinst*® and/or *Heron Instruments Inc.* electronic water level meter with both visual and audio indicators.

The electronically monitored wells are typically measured every hour, with increased frequency as required. At the hourly frequency, the following trends can be distinguished in an individual monitoring well:

- Seasonal climate trends;
- Water level changes in the aquifer that is being pumped;
- Water level changes in aquifers connected to the pumped aquifer; and
- Individual precipitation events in unconfined aquifers.

The manually monitored wells are measured once per month. At this frequency only the first three responses listed above can be distinguished.

E.1.3 Climatological Data

To evaluate the reaction of water levels to changes in climatic conditions, precipitation data are monitored at various locations throughout the Region. Within the Region of Waterloo, climate data is collected by Environment Canada at the Region of Waterloo International Airport (WIA) and the Roseville weather station, by the Grand River Conservation Authority (GRCA) at various Dam locations and by the University of Waterloo at a weather station located on the north campus.

E.2 Groundwater Level Collection Protocols

E.2.1 Groundwater Level Monitoring Network Summary Well Checklist

A well checklist and data entry spreadsheet are prepared of all the measuring points where water levels will be collected on a monthly basis. The checklist and spreadsheet are organized by well field so wells in close proximity are grouped together and indicates whether locations are measured with electronic dataloggers or manual measurements only. Once a well is visited, data is entered in the spreadsheet and the well is checked off the list; thus, the checklist and spreadsheet provides an obvious indication that work is unfinished if a location is unchecked and has no data.

E.2.2 Well Inspection

Upon visiting a well for the first time, the well/casing/equipment details are noted, photos taken, and GPS coordinates are recorded in a field book and/or in the monthly data entry spreadsheet. Well/casing/equipment details includes: location, access, condition, materials, diameters, casing security, surface seal condition, requiring repair or not, well/casing stickup measurements from ground level, well total depth, and the type of datalogger and/or sampling equipment installed. Any notable deficiencies, concerns, problems, or changes in the well condition are recorded in a field book and/or in the monthly data entry spreadsheet, as well as, photos are taken. Also, any observed activities taking place around or near the well that are worth noting are recorded in a field book and/or in the monthly data entry spreadsheet.

E.2.3 Monitoring Well Manual Water Level Measurement Procedure

- Unlock well casing and open well casing lid.
- Remove well cap (if present).
- Use an Electronic Water Level meter and lower the probe down the well until the meter beeps to indicate the probe has encountered water.
- The probe is raised up until the beep of the meter stops, indicating the probe is now above the water.
- Then the probe is slowly lowered down until the probe just contacts the water level surface causing the meter to beep.
- At this point the depth (in meters) is read off the water level meter tape from the measuring point of the well (in most cases is the top of the casing or pipe) and this provides the water level depth below the measuring point.
- The date, time, and water level depth measured is recorded in a field book and/or in the monthly data entry spreadsheet.
- This procedure is repeated for each of the well screens inside the well casing.

- Replace well caps.
- Close well casing lid and lock well casing.

E.2.4 Downloading of Water Levels from Electronic Dataloggers Procedure

For Non-Vented (Absolute) Datalogger Models:

In-Situ Inc.® LevelTROLLs® and RuggedTROLLs®, *Van Essen Instruments* Divers®, and *Solinst*® Leveloggers®

- Prior to downloading data from the datalogger, a manual water level is measured in each well screen containing a datalogger.
- The datalogger is pulled out of the well, unthreaded from the cap that is attached to a wire cable and connected to (or placed in) the corresponding datalogger communication device. The communication device is connected to a laptop/tablet PC or a RuggedReader® Handheld PC and the associated datalogger software is started.
- Water level data stored in the datalogger is subsequently downloaded and viewed using the datalogger software and saved on the hard drive/memory.
- Note: downloading data from the datalogger does not automatically stop the datalogger from recording.
- The status of the datalogger is viewed and checked for correct operation and to confirm that the datalogger is hanging in the well water within its operating range.
- Select datalogger details such as the battery level and free/used memory are recorded in a field book and/or in the monthly data entry spreadsheet.
- If the datalogger does not require restarting to free up memory or to change the sample rate, then the datalogger is removed from the communication device and is threaded back onto its cap and lowered back down the well on the wire cable.
- If the datalogger does require restarting to free up memory or to change the sample rate, then the datalogger is stopped, reprogrammed, and restarted using the datalogger software and, as a result, erases the previous data stored in memory on the datalogger.
- This procedure is repeated for each datalogger within each of the well screens inside the well casing.
- After all the non-vented (absolute) dataloggers have been downloaded then the Barometric dataloggers are downloaded following the same procedure as above.

For Vented (Gauged) Datalogger Models:*In-Situ Inc.*® LevelTROLLs®

- Prior to downloading data from the datalogger, a manual water level is measured in each well screen containing a datalogger.
- The desiccant tube is disconnected from the datalogger cable.
- The datalogger cable is connected to a communication cable device that is connected to a laptop/tablet PC or a RuggedReader® Handheld PC and the datalogger software is started.
- Water level data stored in the datalogger is subsequently downloaded and viewed using the datalogger software and saved on the hard drive/memory.
- Note: downloading data from the datalogger does not automatically stop the datalogger from recording.
- The status of the datalogger is viewed and checked for correct operation and to confirm that the datalogger is hanging in the well water within its operating range.
- Select datalogger details such as the battery level, free/used memory, and desiccant condition (colour) are recorded in a field book and/or in the monthly data entry spreadsheet.
- The desiccant tube condition is checked and replaced if necessary.
- If the datalogger does not require restarting to free up memory or to change the sample rate, then the communication cable device is disconnected from the datalogger cable and the desiccant tube is reconnected.
- If the datalogger does require restarting to free up memory or to change the sample rate, then the datalogger is stopped, reprogrammed, and restarted using the datalogger software and, as a result, erases the previous data stored in memory on the datalogger.
- This procedure is repeated for each datalogger within each of the well screens inside the well casing.

E.2.5 Data Entry and Processing into the Burnside MS ACCESS/SQL® Database

- All field data collected (i.e. date, time, manual water level depth measured, comments) and recorded for each well screen and datalogger in a field book is entered into the monthly data entry spreadsheet, unless already entered in the field using a laptop/tablet PC.
- The monthly data entry spreadsheet is checked and reviewed prior to importing the data into a database table using Burnside Water Level Data Tools software. Manual water level depth values are converted into water level elevation values using the software during this import process.
- Any associated well notes, comments, and datalogger details are entered into a database table under the appropriate well and screen.

- Water level data from the dataloggers downloaded to a laptop/tablet PC or a RuggedReader® Handheld PC are transferred to Burnside file folder network upon returning to the office.
- These datalogger water level data files are subsequently read and the data is imported into a database table using Burnside Water Level Data Tools software.
- Using Burnside Water Level Data Tools software, the datalogger water level data are reviewed and processed (as described below) resulting in corrected water level depth values and corrected water level elevation values that are stored in a database table.
- *For Non-Vented (Absolute) Datalogger Models:*
Datalogger water level data is first barometric pressure compensated using selected Barometric datalogger data, then a manual water level depth value measured at the time of the most recent download is applied and used to convert the barometric compensated water level data into corrected water level depth values, which are converted into water level elevation values that are appended to a database table.
- *For Vented (Gauged) Datalogger Models:*
A manual water level depth value measured at the time of the most recent download is applied to the datalogger water level data to convert the water level data into corrected water level depth values, which are converted into water level elevation values that are appended to a database table.
- Temperature data recorded by the dataloggers are also imported into a database table.
- Hydrographs are subsequently created for each well and screen from the water level elevation data in the database for review and presentation. If there are some data points that are erroneous, then these data points are marked as non-reportable (invalid) within the database and/or are removed resulting in them not being plotted on the hydrographs.
- An updated data file is provided to the Region on a quarterly basis for upload into their eWRAS EQUIS database.

